



**BUREAU
VERITAS**

Technical Report: 96253120624
Date Received: NOVEMBER 08, 2025

DECEMBER 06, 2025
Page 1 of 141

DOREL HOME FURNISHINGS INC
410 E FIRST STREET SOUTH WRIGHT CITY MO 63390 USA.

Sample Description:	TWIN/FULL BUNK BED	Sample Size:	01 PC
Vendor:	DOREL HOME FURNISHINGS INC	Manufacturer:	XIN GUAN XING INTERNATIONAL CO., LTD.
Buyer:	/	SKN/SKU No.:	/
Agent:	/	PO No.:	/
Labeled Age Grade:	/	Ref #:	/
Appropriate Age Grade:	/	Country of Origin:	VIETNAM
Client Specified Age Grade:	/	Assortment No.:	/
Tested Age Grade:	/	Department No.:	/
UPC Code:	0-65857-16788-7, 0-65857-16789-4, 0-65857-17026-9, 0-65857-17264-5, 0-65857-17415-1	Phase of Production:	PRODUCTION
Color:	ESPRESSO, WHITE, BLUE, BLACK, GRAY	Item#:	/
Program:	/	Date of Production:	2025.11
Previous No:	/	Model/Style#:	DA6940E, DA6940W, DA6940BL, DA6940BK, DA6940GR
		Country of Destination:	USA

TEST PROPERTY	PASS	FAIL	DATA	N/A	Remark
03016-USA, BED / BED FRAME HMZ	X				
03660-USA, D71 READY TO ASSEMBLE FURNITURE (RTA) UPHOLSTERED AND NON UPHOLSTERED HMZ	X				
13300-USA, REG FURNITURE (INDOOR AND OUTDOOR)	X				
03700-USA, WALMART DEPARTMENT 71 WEIGHT SUPPLEMENT HMZ	X				
08000-USA, QTY TOYS AND CHILDRENS PRODUCTS HMZ	X				
08119-USA, BUNK BED HMZ	X				
18001-USA, REG CHILDREN'S PRODUCT	X				
18037-USA, REG CHILD CARE ARTICLES	X				
00000-USA, ALL PRODUCTS HMZ	X				
10000-USA, REG ALL PRODUCTS	X				
10004-USA, REG BANNED PRODUCTS				X	
SOR/2016-193 Total Lead in Surface Coating Materials	X				
SOR/2018-83 Consumer Products Containing Lead Regulations	X				
SOR 2011-17 S.23b Toxicology Hazards: Heavy metals in surface coating	X				
Phthalates Content	X				
16 CFR 1501 – Small Part	X				
16 CFR 1500.44 Flammability	X				

Bureau Veritas
Consumer Products Services (VN) Ltd.
 Lot C7-C9, Conurbation 2, Cat Lai Industrial Zone,
 Thanh My Loi Ward, Thu Duc City, HCMC, Vietnam
 Tel: 84-028-37421604~6 Fax: 84-028-37421603
 website:www.bureauveritas.com/cps

This report is governed by, and incorporates by reference, the Conditions of Testing as posted at the date of issuance of this report at <http://www.bureauveritas.com/home/about-us/our-business/cps/about-us/terms-conditions/> and is intended for your exclusive use. Any copying or replication of this report to or for any other person or entity, or use of our name or trademark, is permitted only with our prior written permission. This report sets forth our findings solely with respect to the test samples identified herein. The results set forth in this report are not indicative or representative of the quality or characteristics of the lot from which a test sample was taken or any similar or identical product unless specifically and expressly noted. Our report includes all of the tests requested by you and the results thereof based upon the information that you provided to us. Measurement uncertainty is only provided upon request for accredited tests. Statements of conformity are based on simple acceptance criteria without taking measurement uncertainty into account, unless otherwise requested in writing. You have 60 days from date of issuance of this report to notify us of any material error or omission caused by our negligence or if you require measurement uncertainty; provided, however, that such notice shall be in writing and shall specifically address the issue you wish to raise. A failure to raise such issue within the prescribed time shall constitute your unqualified acceptance of the completeness of this report, the tests conducted and the correctness of the report contents.



Note(s):

- The Chemical test following reports listed:

No.	Tested component:	Chemical test	Reference report	Report issued date
1	Espresso Coating (Wood)	CPSIA Lead + Illinois Lead, Canada Lead, Canada Heavy Metal, CPSIA Phthalates, Client's Phthalates	96250720550	March 20, 2025
2	White Coating (Wood)		96250720546	March 19, 2025
3	Blue Coating (Wood)		96250720548	March 19, 2025
4	Black Coating (Wood)		96250720544	March 20, 2025
5	Gray Coating (Wood)		96250720541	March 19, 2025
6	Coating (Warning Label)			
7	Coating (Tracking Label)			96252940682
8	Plywood	CPSIA Lead + Illinois Lead, Canada Lead	EFFN25010375-CG-01 Revised 1	January 23, 2025
9	Black Joint Connector			
10	Black Wood Joint Connector			
11	Black Head Socket Head Bolt			
12	Black Cap Nut			
13	Black Flat Head Screw			
14	Silver Joint Connector			
15	Silver Wood Joint Connector			
16	Silver Hex Socket Head Bolt			
17	Silver Cap Nut			
18	Silver Barrel Nut			
19	Silver Flat Head Screw	EFFN25010373-CG-01	January 16, 2025	
20	Yellow Flat Head Screw			
21	White Plastic Cover (Hook)	CPSIA Lead + Illinois Lead, Canada Lead	EFFN25010374-CG-01	January 16, 2025
		CPSIA Phthalates, Client's Phthalates	Actual test	-
22	Black Plastic Cover (Hook)	CPSIA Lead + Illinois Lead, Canada Lead	EFFN25010374-CG-01	January 16, 2025
		CPSIA Phthalates, Client's Phthalates	Actual test	-

- This report includes the test result(s) which was conducted & reviewed by Analytical department.



If there is any question regarding this report, please contact the following lab personnel:

Administrative inquiries, please contact:

Primary Contact: Elise Vo, Tel: 84-028-37421-604 ~ 6, Ext: 394; email: elise.vo@bureauveritas.com
Back-up Contact: Cynthia Vuong, Tel: 848-37421-604 ~ 6, Ext: 641; email: cynthia.vuong@bureauveritas.com

Technical inquiries, please contact:

Primary Contact: Terry Nguyen, Tel: 84-028-37421-604 ~ 6, Ext: 355; email: terry.nguyen@bureauveritas.com
Back-up Contact: Louis Tran, Tel: 84-028-37421-604 ~ 6, Ext: 339; email: louis.tran@bureauveritas.com

BUREAU VERITAS CONSUMER PRODUCTS SERVICES (VN) LTD.

TERRY NGUYEN
LAB MANAGER – HARDLINE, TOYS & JUVENILE PRODUCTS DIVISION



APPENDIX

List of Phthalates [U. S. 16 CFR 1307] :					
No.	Name of Analyte(s)	CAS-No.	No.	Name of Analyte(s)	CAS-No.
1	Butyl benzyl phthalate (BBP)	85-68-7	5	Di-iso-butyl phthalate (DIBP)	84-69-5
2	Dibutyl phthalate (DBP)	84-74-2	6	Di-n-pentyl phthalate (DnPP or DPENP)	131-18-0
3	Di-2-ethylhexyl phthalate (DEHP)	117-81-7	7	Di-n-hexyl phthalate(DnHP or DHEXP)	84-75-3
4	Di-iso-nonyl phthalate (DINP)	28553-12-0	8	Di-cyclohexyl phthalate (DCHP)	84-61-7
CAS-No. = Chemical Abstracts Service registry number					



RESULT(S):

REQUIREMENTS FOR BUNK BEDS (FHSA, Title 16, CFR, Part 1213 & 1513)

Section	Description	Results
1213.3 1513.3	Requirements	
1213.3(a) 1513.3(a)	Guardrails	
1213.3(a)(1) 1513.3(a)(1)	Two guardrails required if bed is > 30 inches from ground	M
1213.3(a)(2) 1513.3(a)(2)	One guardrail shall be continuous	M
1213.3(a)(3) 1513.3(a)(3)	No greater than 15 inches between either end	M
1213.3(a)(4) 1513.3(a)(4)	Bunk Beds with ladder, continuous guardrail on other side	M
1213.3(a)(5) 1513.3(a)(5)	Guardrails attached so they cannot be removed without releasing a device	M
1213.3(a)(6) 1513.3(a)(6)	The upper edge shall be no less than 5 inches above top surface	M
1213.3(a)(7) 1513.3(a)(7)	No openings in the structure between lower edge and underside	M
1213.3(b) 1513.3(b)	Bed End Structures	
1213.3(b)(1) 1513.3(b)(1)	The upper edge of end structure shall be at least 5 inches above mattress	M
1213.3(b)(2) 1513.3(b)(2)	No openings in the structure above foundation of the upper bunk that permits passage of the wedge block	M
1213.3(b)(3) 1513.3(b)(3)	Tested in accordance with Section 1213.4(c)	M
1213.3(b)(4) 1513.3(b)(4)	Neck entrapment requirements of Section 1213.4(c)(3)	M
1213.5 1513.5	Marking and Labeling	
1213.5(a) 1513.5(a)	Permanent label with name and address, model # and date code	M
1213.5(b) 1513.5(b)	Permanent Warning Label placement	M
1213.6 1513.6	Instructions	
1213.6(a) 1513.6(a)	Size of mattress and foundation	M
1213.6(b) 1513.6(b)	Safety Warning	-
1213.6(b)(1) 1513.6(b)(1)	Do not allow children under 6 years of age to use the upper bunk	M



REQUIREMENTS FOR BUNK BEDS (FHSA, Title 16, CFR, Part 1213 & 1513)

Section	Description	Results
1213.6(b)(2) 1513.6(b)(2)	Use guardrails on both sides of the upper bunk	M
1213.6(b)(3) 1513.6(b)(3)	Prohibit horseplay on or under beds	M
1213.6(b)(4) 1513.6(b)(4)	Prohibit more than one person on upper bunk	M
1213.6(b)(5) 1513.6(b)(5)	Use ladder for entering or leaving upper bunk	M
1213.6(b)(6) 1513.6(b)(6)	If the bed is placed against a wall, use full length guardrail along wall	M

M = Meet NM = Not Meet NA = Not Applicable R = Refer to Comment Section



RESULT(S):

STANDARD CONSUMER SAFETY SPECIFICATION FOR BUNK BEDS (ASTM F1427-21e1)

Section	Requirement	Result
4	Performance Requirements	
4.1	Vertical Protrusions	-
4.1.1	Vertical protrusions along the top inside surface	M
4.1.2	Cap used along the top surface of upper bunk	NA
4.2	Fit of Top Bed to Bottom Bed	NA
4.3	Mattress and Foundation Size and Fit (Top Bed)	M
4.4	Mattress Size and Fit (Lower Foundation)	NA
4.5	Upper and Lower Foundation Support Systems	-
4.5.1	Horizontal position of the mattress and the foundation	M
4.5.2	Utilized event cross-members	M
4.5.3	Release of positive fastening devices or use of hand tools	M
4.5.4	Static load for the foundation support system	M
4.6	Side Rails	-
4.6.1	Bolt-On Side Rails	M
4.6.2	Hook-On Side Rails	NA
4.6.3	Side rail attachments	M
4.7	Guardrails	-
4.7.1	Presence of guardrails	M
4.7.2	Requirement of attachment	M
4.7.3	Requirement of height of the upper edge above the sleeping surface	M
4.7.4	Opening of the guardrail	M
4.7.5	Opening between the either end of the guardrail and the bed end structure	M
4.8	Bed Structure	-
4.8.1	The upper edge of the upper bunk end structures	M
4.8.2	Openings in the rigid end structures of the upper bunk	M
4.8.3	Openings in the end structures of the lower bunk	M
4.8.4	Neck entrapment requirement of all portions of the boundary of any opening of the lower bunk end structure	M
4.9	Ladders	-
4.9.1	Presence of ladder	M
4.9.2	Dimension requirement of ladder	M
4.9.3	Openings between ladder step and upper bunk boundary	M
4.9.4	Gaps between edge of mattress and interior vertical stile	NA
4.10	Metal beds: frame and fastenings	NA
6	Marking and Labeling	M
7	Instructional Literature	M

M = Meet NM = Not Meet NA = Not Applicable R = Refer to Comment Section



WALMART CLAIM VERIFICATION

Claim	Classification	Results	Rating
• GROSS WEIGHT: 134.20 LBS	<input checked="" type="checkbox"/> Actual Test Results: • GROSS WEIGHT: 134 LBS (-0.15%) <input type="checkbox"/> Doc Review <input type="checkbox"/> Subjective Claim	<input checked="" type="checkbox"/> M <input type="checkbox"/> NM <input type="checkbox"/> NT	<input checked="" type="checkbox"/> PASS <input type="checkbox"/> FAIL <input type="checkbox"/> DATA
• TWIN – FULL	<input checked="" type="checkbox"/> Actual Test Results: • TWIN - FULL <input type="checkbox"/> Doc Review <input type="checkbox"/> Subjective Claim	<input checked="" type="checkbox"/> M <input type="checkbox"/> NM <input type="checkbox"/> NT	<input checked="" type="checkbox"/> PASS <input type="checkbox"/> FAIL <input type="checkbox"/> DATA
• BLUE	<input checked="" type="checkbox"/> Actual Test Results: • BLUE <input type="checkbox"/> Doc Review <input type="checkbox"/> Subjective Claim	<input checked="" type="checkbox"/> M <input type="checkbox"/> NM <input type="checkbox"/> NT	<input checked="" type="checkbox"/> PASS <input type="checkbox"/> FAIL <input type="checkbox"/> DATA

Result Key:

M Meets
 NM Does Not Meet
 NT Not Tested

DISCREPANCIES TABLE

Item	BOM Weight (Kg)	Actual Weight (Kg)	%
• Net Weight	56	55.8	0.3
• Gross Weight	61	60.7	0.5



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
03016-USA- (V23)
BED / BED FRAME HMZ**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

Evaluation	Citation / Method	Criteria	Comments	Result	Rating
SCOPE: This protocol is applicable to bed and bed frame.					
SUPPLEMENTARY PROTOCOL					
A All Products	WMRT-GB-PTCL-10000-USA	Test to All Products Protocol WMRT-GB-PTCL-10000-USA		M	PASS
A Law Label	WMRT-GB-PTCL-01990-USA	Test to Supplemental Protocol WMRT-GB-PTCL-01990-USA.		NA	/
A Weight supplemental	WMRT-HL-PTCL-03700-USA	[Walmart USA Department 71 products] Test to Supplemental Protocol WMRT-HL-PTCL-03700-USA (Effective date 03/24/14).		M	PASS
STAR 3 - QUALITY/PERFORMANCE					
Mattress foundation size (twin, full, queen, king)	Dimensional measurements	Report Mattress foundation size (twin, full, queen, king).	Data Only	UPPER BUNK: TWIN SIZE LOWER BUNK:FULL SIZE	DATA
Dimensions - headboard (height x length x width)	Dimensional measurements	Report overall dimensions (if applicable). Shall meet label claims.		OVERALL DIMENSION – HEADBOARD: NO CLAIM RECORD: TWIN BED: 41.75”L x 2.38”W x 31.13”H FULL BED: 58”L x 2.75”W x 33.75”H	DATA
Dimensions - footboard (height x length x width)	Dimensional measurements	Report overall dimensions (if applicable). Shall meet label claims.		OVERALL DIMENSION – FOOTBOARD: NO CLAIM RECORD: TWIN BED: 41.75”L x 2.38”W x 31.13”H FULL BED: 58”L x 2.75”W x 33.75”H	DATA



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
03016-USA- (V23)
BED / BED FRAME HMZ**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

Evaluation	Citation / Method	Criteria	Comments	Result	Rating
Dimensions - frame (height x length x width)	Dimensional measurements	Report overall dimensions (if applicable). Shall meet label claims.		OVERALL DIMENSION – FRAME: NO CLAIM RECORD: TWIN BED: 74.88”L x 40.25”W x 4.25”H FULL BED: 74.88”L x 55.88”W x 4.25”H	DATA
Weight	Weight measurements	[Headboard] Report overall weight (if applicable). Shall meet label claims		NET WEIGHT – HEADBOARD: NO CLAIM RECORD: TWIN BED:12.4 LBS FULL BED:16.4 LBS	DATA
Weight	Weight measurements	[Footboard] Report overall weight (if applicable). Shall meet label claims.		NET WEIGHT – FOOTBOARD: NO CLAIM RECORD: TWIN BED: 12.4 LBS FULL BED: 16.4 LBS	DATA
Weight	Weight measurements	[Frame] Report overall weight (if applicable). Shall meet label claims.		NET WEIGHT – FRAME: NO CLAIM RECORD: TWIN BED: 20 LBS FULL BED: 26.8 LBS	DATA
Material thickness	Dimensional or weight measurements	Report actual.	Data Only	SLAT THICKNESS: UPPER BUNK:1.75” LOWER BUNK:0.88”	DATA



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
03016-USA- (V23)
BED / BED FRAME HMZ**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

Evaluation	Citation / Method	Criteria	Comments	Result	Rating
Number of legs	Visual	Report actual.	Data Only	TWIN BED: 4 LEGS FULL BED: 7 LEGS	DATA
Hardness	In-House Method	[Caster hardness] Report actual.	Data Only	NO CASTER	DATA
Caster diameter	Dimensional measurements	Report actual.	Data Only	NO CASTER	DATA
Caster width	Dimensional measurements	Report actual.	Data Only	NO CASTER	DATA
Dimensions	Dimensional measurement	[Foundation / support structure height from the floor] Record height (in) Note: This dimension cannot exceed 30 inches, if it does, the product has to meet ASTM F1427 Bunk Bed requirements.		FOUNDATION HEIGHT: TWIN BED:13.63" FULL BED:14"	DATA
Moisture content	Weight measurement before and after oven dry method	Wood moisture content (12% max) _____%.		M SOLID WOOD: 10.5%	PASS
Construction	Visual inspection	If a stuffing label (TSSA, Law Label) is present, the stuffing contained in the product visually matches the description on the label. Picture of actual filling material is provided with report.		NA	/
Construction	Visual inspection	Filling / stuffing material(s) visually match any other material identification labeling on the packaging or product. Note: Picture of actual filling material is provided with report.		NA	/
Construction	Visual inspection	Sample exhibits good rigidity and stability		M	PASS
Construction	Visual inspection	All components or parts of the bed, with which the user may come into contact during normal use, shall not have burrs and/or sharp edges, nor shall there be open-ended tubes.		M	PASS
Construction	Visual inspection	Headboard to frame method of attachment (bolted, cleat, etc)	Data only	BOLTED	DATA
Construction	Visual inspection	Bed / Bed Frame fits intended bed size (Twin, Twin XL, Full, Full XL, Queen, King, Cal King).		M	PASS



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
03016-USA- (V23)
BED / BED FRAME HMZ**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

Evaluation	Citation / Method	Criteria	Comments	Result	Rating
Construction	Visual inspection	All metal surfaces are plated, coated, or equivalent to inhibit corrosion.		M	PASS
Construction	Visual inspection	Adjustable / Folding Products		NA	/
Construction	Visual inspection	Provides smooth and easy adjustment or folding and unfolding.		NA	/
Construction	Visual inspection	No pinching, laceration, or personal injury hazard is present during folding, unfolding, or adjusting.		NA	/
Construction	Visual inspection	Easily adjusts or folds and unfolds without binding of the mechanism.		NA	/
Static load test - distributed load	Actual use / functionality	Assembled sample withstands a load uniformly distributed on the surface supported by the frame for 24 hours without collapse or noticeable deformation of any component and with no loss in consumer serviceability Rated load (if applicable) _____ lb 300lb per person load (if not rated) _____ lb		M	PASS
Structural strength test	Actual use / functionality	[Concentrated load] Assembled sample withstands two loads of 300 pounds (600lb total) simultaneously for 1 minute, 12 inches from each side of the center of one side frame member, and 8 inches inboard from the side frame member, without loss of serviceability.		M	PASS

Pricing information please refer to client price list "WMRT-GB-\$LST-GB-PRICE LIST".

No. Of Samples Required for Complete Testing	2	Furniture=2 samples; Toys= 3 samples
No. Of (Fully Packed) Cartons For Transit Testing:	1	
No. Of Working Days For Complete Testing:	5	

Client Approval:	kelly Nasradinaj
	23/Jun/2023
Creation Date:	13/Nov/2008
Last Revision Date:	22/Jun/2023
Pricing Review Date	
Technical Review Date:	

Key

A

Additional Charge For This Test



**TEST PROTOCOL FOR
03016-USA- (V23)
BED / BED FRAME HMZ**

BV Lab Number: **96253120624**
Technician Name: DUY
Test Date: NOVEMBER 08, 2025
Reviewed By/Date: JOHN/ DECEMBER 02, 2025

Key

M Mandatory Requirement
R Regulatory

Result Key

C Claimed
M Meets
R Recorded
NM Does Not Meet
NT Not Tested
NA Not Applicable

Rating Key

PASS Pass
FAIL Fail



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
03660-USA- (V20)
D71 READY TO ASSEMBLE FURNITURE (RTA) UPHOLSTERED AND NON UPHOLSTERED
HMZ**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

Evaluation	Citation / Method	Criteria	Comments	Result	Rating
SCOPE: This protocol is applicable to D71 upholstered and non-upholstered ready to assemble furniture (RTA)					
SUPPLEMENTARY PROTOCOL					
A All Products	WMRT-GB-PTCL-10000-USA	Test to All Products Protocol WMRT-GB-PTCL-10000-USA		M	PASS
STAR 3 - QUALITY/PERFORMANCE					
Packaging/labeling	Walmart requirement	[Applicable to upholstered products only] Care instructions are provided (if cover is intended to be removed for cleaning)		NA	/
Packaging	CPSD-GB-01057-MTHD	Hardware pack contains no extraneous material.		M	PASS
Packaging	CPSD-GB-01057-MTHD	All hardware must be packaged and separated by type and size (sub-packed) and included in the master hardware pack.		M	PASS
Packaging	CPSD-GB-01057-MTHD	All packs are sealed to prevent parts from being separated.		M	PASS
Packaging	CPSD-GB-01057-MTHD	All components are free from oil and other liquid residue.		M	PASS
Instruction or manual	CPSD-GB-01057-MTHD	Picture or line drawing is required on the cover sheet.		M	PASS
Instruction or manual	CPSD-GB-01057-MTHD	Model number or style number for reference is on cover sheet.		M	PASS
Instruction or manual	CPSD-GB-01057-MTHD	Manufacturer company name and contact information for ordering missing or replacement parts are on cover sheet (supplier must include a toll-free number).		M	PASS
Instruction or manual	CPSD-GB-01057-MTHD	Cover provides an area for the consumer to record the lot number.		M	PASS
Instruction or manual	CPSD-GB-01057-MTHD	Cover provides an area for the consumer to record the date.		M	PASS
Instruction or manual	CPSD-GB-01057-MTHD	Must have the following note (verbatim and in upper case): "THIS INSTRUCTION BOOKLET CONTAINS IMPORTANT SAFETY INFORMATION. PLEASE READ AND KEEP FOR FUTURE REFERENCE"		M	PASS
Instruction or manual	CPSD-GB-01057-MTHD	Includes Spanish and English language instructions (this includes cover, safety, and warranty information. Languages shall not be mixed on same page. Translated language can be text only).	Note: Some small and simple units (flat pack) with the approval of the client may be produced with the languages mixed on the same page. "Your Zone" products may have English and Spanish on the same page	M	PASS



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
03660-USA- (V20)
D71 READY TO ASSEMBLE FURNITURE (RTA) UPHOLSTERED AND NON UPHOLSTERED
HMZ**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025


Evaluation	Citation / Method	Criteria	Comments	Result	Rating
Instruction or manual	Visual	<p>Includes assembly instructions which contain both drawings and written instructions for every step in the assembly. Also each step must list the hardware items (including quantity) needed for that step.</p> <p>NOTE: Do not fail until Oct 1 2025 if the product includes assembly instructions which contain drawings and written instructions but does not contain both drawings and instructions for every step in the assembly and lists the hardware items (including quantity) needed for that step. Only fail if the product does not include assembly instructions which contain drawings and written instructions. On Oct 1 2025 both requirements are in effect.</p>	<p>Note: Some small and simple units (flat pack) with the approval of the client may be produced without written instructions.</p>	M	PASS
Instruction or manual	Visual	<p>Instructions are clear and concise and include the following:</p> <ul style="list-style-type: none"> - Listing of tools required for assembly - Cautionary statements which should be read before beginning assembly - Age grading information (as applicable) - Provides maximum weight loading of tops, shelves, and surfaces designed to bear weight (not required for dining tables, beds, benches and chairs) - All hardware and components of the product are listed - A drawing is provided of each part for visual identification. - A letter label identifier for each part is visually drawn unless components are easily identifiable (excludes fasteners and similar hardware) ¹ - Includes a schematic drawing of parts and an area of the unit being assembled by steps - Drawings of screw(s), bolt(s), dowels and washer(s) actual size to be used at each step ² - The font size of the instructions are a minimum of ten(10) point font (0.10 in) ³ 	<p>1 Note: This must correspond with identification on the actual parts</p> <p>2 Note: Some small and simple units (flat pack) with the approval of the client may be produced without written instructions.</p> <p>3 Note: 10 font is .10" (font is measured from the top of any CAPITAL letter to the bottom of the same letter)</p> <p>Some small and simple units (flat pack) with the approval of the client may be produced with a minimum of eight (8) - point font.</p>	M	PASS
Marking	Visual	<p>Furniture that is intended for use with a television has warning labels that are affixed directly to or provided with the product and shall have the following: (Note: Not applicable to products intended exclusively for use with personal computers)</p> <ul style="list-style-type: none"> - A format that complies with ANSI Z535.4 - A maximum weight specified for the television device that can be safely used with the product - A reference addressing the requirement that the base of the television device must be able to rest on the supporting surface of the unit without over-hanging the edges 		NA	/



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
03660-USA- (V20)
D71 READY TO ASSEMBLE FURNITURE (RTA) UPHOLSTERED AND NON UPHOLSTERED
HMZ**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

Evaluation	Citation / Method	Criteria	Comments	Result	Rating
		 <p>Note: This is only an example of the required label. The label does not have to look exactly like the example, and the language does not need to be verbatim</p>			
Finish / Workmanship	CPSD-GB-01057-MTHD	Product is free of chatter or telegraphing (washboard effect).		M	PASS
Finish / Workmanship	CPSD-GB-01057-MTHD	Edge-banding fully adheres with no bubbles or delaminating.		NA	/
Finish / Workmanship	CPSD-GB-01057-MTHD	No exposed staples or screws.		M	PASS
Finish / Workmanship	CPSD-GB-01057-MTHD	No repairs visible after assembly.		M	PASS
Finish / Workmanship	CPSD-GB-01057-MTHD	No loose or mis-aligned moldings or trims.		NA	/
Finish / Workmanship	Visual	Surface Materials (Finished)		M	PASS
Finish / Workmanship	Visual	No scratches or dents are to be present on the product		M	PASS
Finish / Workmanship	Visual	No wrinkles are to be present on the product		M	PASS
Finish / Workmanship	Visual	No excess glue is to be left exposed on any surface viewable after assembly		M	PASS
Finish / Workmanship	Visual	No boring bits from one side are to show through the lamination if using hole on one side		M	PASS
Finish / Workmanship	Visual	No off registration of the pattern is acceptable		NA	/



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
03660-USA- (V20)
D71 READY TO ASSEMBLE FURNITURE (RTA) UPHOLSTERED AND NON UPHOLSTERED
HMZ**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

Evaluation	Citation / Method	Criteria	Comments	Result	Rating
Finish / Workmanship	Visual	Coating has to be smooth and without bubbles		M	PASS
Finish / Workmanship	Visual	<p>Grooves</p> <p>1.) No chipping in grooves is acceptable</p> <p>2.) Grooves are stained or covered with decorative paper to match the veneer pattern used (applies to visible grooves only)</p> <p>3.) Raw edges and unfinished surfaces are not visible in any direction including the back or underside of the unit (The following are exempt for US market products: back of the rear cardboard panel and the platform where the mattress covers the unit)</p> <p>NOTE: Do not fail for visible raw edges and unfinished surfaces (In US Market) on the back edge of rails that are made from fiberboard or the underside of shelves in flat packs until Oct 1 2025.</p>		NA	/
Finish / Workmanship	Visual	<p>Doors:</p> <p>1.) No chipping and or bowing acceptable. All doors are finished on both sides</p> <p>2.) Panel edges match surrounding surface color</p>		NA	/
Finish / Workmanship	CPSD-GB-01057-MTHD	<p>Drawer:</p> <p>- Drawers are set and flush when closed.</p> <p>- The interior of the drawer will not have visible exposed raw or rough edges.</p>		NA	/
Construction	CPSD-GB-01057-MTHD	No more than 1 millimeter (0.04") gap between the edge-band splices.		NA	/
Construction	CPSD-GB-01057-MTHD	<p>[Not applicable to holes used for adjustable shelf supports, drawer sides, end panels, doors - inside 1/8in dia. without cover or plug or holes intended to make doors reversible]</p> <p>There are no extra holes visible when product is in completed state.</p>		M	PASS
Construction	CPSD-GB-01057-MTHD	Solid wood components are sealed on all sides.		M	PASS
Construction	CPSD-GB-01057-MTHD	Safety brackets are provided with four and five drawer dressers, infant change tables, lateral and vertical file drawers, libraries and bookcases, storage cabinets, wardrobes, armoires, entertainment centers, and hutches. (for units 48" or higher).		NA	/



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
03660-USA- (V20)
D71 READY TO ASSEMBLE FURNITURE (RTA) UPHOLSTERED AND NON UPHOLSTERED
HMZ**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

Evaluation	Citation / Method	Criteria	Comments	Result	Rating
Construction	CPSD-GB-01057-MTHD	Casters for tables, carts, wire shelving, beds, etc. must exhibit good mobility when loaded to recommended maximum load and a minimum of 2 casters per item must be capable of being easily locked and unlocked.		NA	/
Construction	CPSD-GB-01057-MTHD	Furniture legs and bottom surfaces include nonmarring feet or end caps.		M	PASS
Construction	Visual inspection	<p>Applicable to Doors:</p> <ol style="list-style-type: none"> 1.) Doors are to consistently be aligned with the outline of the frame 2.) Gap on sides, top, and bottom of doors does not exceed 3.5 millimeter (0.14") (Doors with pivot hinges are allowed a maximum of 6mm gap on top and bottom) 3.) Gap between doors side by side does not exceed 4 millimeter (0.16") 4.) Doors have a minimum of 1 catch for doors less than 30" and 2 catches for doors over 30" (this excludes doors with self-closing hinges) 5.) Door hinges are sufficiently heavy duty to allow for smooth operation without sagging or binding (for armoire's and entertainment centers) 6.) Door handles are symmetrical and measure evenly when closed 		NA	/
Construction	Visual inspection	<p>Applicable to Drawers:</p> <ol style="list-style-type: none"> 1.) Drawers must be set and flush (evenly aligned with frame) when closed if the design is called for. 2.) No chipping and or bowing is acceptable 3.) Gap on sides and bottom of a drawer does not exceed 3.5 millimeter (0.14") 4.) Gap between drawers side by side does not exceed 4 millimeter (0.16") 5.) Gap between drawers vertically does not exceed 4 millimeter (0.16") (Gap between the top of drawer and other structural features does not exceed 6 millimeter (0.24"). Applies to uppermost drawer(s) of single or multi-drawer configurations) 6.) Drawers with internal volume equal to or greater than 180 cubic inches have stops attached to keep drawer from being pulled out. 	<p>Note 8: Force is applied on the side of the drawer face, centered with the sliding mechanism. If sliding mechanism is not on side, force should be applied on the center of the side of the drawer face.</p> <p>Note 11: Example: A black exterior with a white interior fails</p>	NA	/



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
03660-USA- (V20)
D71 READY TO ASSEMBLE FURNITURE (RTA) UPHOLSTERED AND NON UPHOLSTERED
HMZ**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

Evaluation	Citation / Method	Criteria	Comments	Result	Rating
		<p>7.) Drawers are required to pull out a minimum of 70% of full length, based on length as measured from inside back to outside front of drawer</p> <p>8.) Side to side travel on drawers does not exceed 8 millimeters (0.31"). Drawers are tested BOTH fully and half-way extended with no inside load, while applying a 2 pound horizontal force to the forward section of the drawer</p> <p>9.) All drawer guide systems operate without binding and with ease at any point in the travel</p> <p>10.) Drawer sides are a minimum of 50% of height in relation to front of drawer (except as appropriate for file cabinets and drawers intended for media storage)</p> <p>11.) All drawer sides, ends and interior bottoms are to color coordinate. Acceptable finishes: Light woodgrain - maple, dark woodgrain - black, or with the outside surfaces of the furniture</p>			
Construction	Visual inspection	<p>Applicable to Wicker / Rattan Furniture:</p> <p>1.) Conspicuous repairs will not be considered acceptable</p> <p>2.) Warping cracked or split frame or wicker/rattan covering will not be considered acceptable</p> <p>3.) Heavy or objectionable surface odor is not acceptable</p> <p>4.) Noticeable voids, irregularities or damage to paint or stain finish will not be considered acceptable</p>		NA	/
Construction	Visual inspection	<p>Applicable to Metal Components:</p> <p>1.) No weld splatter or defective welding is allowed</p> <p>2.) All holes are free from burrs</p> <p>3.) All metal edges conform to UL 1439 "Test for Sharpness"</p> <p>4.) Corrosion, tarnish, or damage to metal components is unacceptable</p>		M	PASS



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
03660-USA- (V20)
D71 READY TO ASSEMBLE FURNITURE (RTA) UPHOLSTERED AND NON UPHOLSTERED
HMZ**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

Evaluation	Citation / Method	Criteria	Comments	Result	Rating
Construction	Visual inspection	<p>Applicable to Glass:</p> <p>1.) Glass edges that are exposed to the consumer under normal use are rounded (#1 edge (pencil ground))</p> <p>2.) Horizontal glass shelves have a minimum thickness of 3 millimeter (0.12")</p> <p>3.) Bow and warp in glass panels shall be equal to or less than a value determined by the longest dimension of the panel divided by 305 and multiplied by 1.5</p> <p>4.) All glass components shall be "tempered glass"</p> <p>5.) All applicable mirrors must conform to ASTM 1048 (the back of the mirror is to be finished so when the mirror breaks, the glass is to remain together)</p>		NA	/
Construction/Workmanship	Visual	<p>[Applicable to upholstered products only]</p> <p>Poor stitching quality (including, but not limited to, open seams, crooked stitching, obvious repairs, needle holes) will not be considered acceptable</p> <p>Color irregularities, including but not limited to, panel to panel shading, poor coordination of fabric and trim or poor match between fabric and visible thread will not be considered acceptable</p> <p>Poor distribution of fill or inadequate or poor quality fill which results in lumpy or uneven appearance, insufficient cushioning, or noticeable loss of loft will not be considered acceptable</p> <p>Seams are neat with no open, loose, or non-uniform stitching or needle damage</p> <p>Hems are straight, uniform, and consistent</p> <p>Loose thread is neatly trimmed</p> <p>No filling is visible through fabric or at seams</p>		NA	/



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
03660-USA- (V20)
D71 READY TO ASSEMBLE FURNITURE (RTA) UPHOLSTERED AND NON UPHOLSTERED
HMZ**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

Evaluation	Citation / Method	Criteria	Comments	Result	Rating
		No major fabric defects such as stains, holes, yarn flaws, color irregularity, or panel to panel shading.			
Construction	Visual inspection	Applicable to Fastening Methods: 1.) All mechanical fasteners can be removed once tightened (not including glued joints) 2.) A Phillips Driver is required on all screws unless an approved tool is included with the unit. This information must be included in the instruction manual. (A flat head driver is allowable for fastening cam locks. If this tool is required, that information must be included in the instruction manual)	Note: This requirement is applicable to major component assembly steps. (i.e. small nails on the bottom of a drawer are not applicable)	M	PASS
Fabric count of woven fabric	ASTM D3775-17(R2023)	Applicable to upholstered products only Thread Count (Woven) (/ in) Note: 1) If the product specification is provided, use a $\pm 5\%$ tolerance 2) Thread count equals WARP YARNS x FILL YARNS.		NA	/
Fabric weight	ASTM D3776-20	[Applicable to upholstered products only] Unit Weight (oz) Fabric Weight Batting Weight (oz/yd ²) Note: If the product specification is provided, use a $\pm 5\%$ tolerance		NA	/
Static loading	CPSD-GB-01058-MTHD	Assembled furniture tops and shelves are loaded with manufacturer's recommended maximum weight as listed in the assembly instructions for 24 hours. If no maximum weight is given, tops and shelves are to be loaded per weight requirements and distribution of ANSI/SOHO S6.5 for static testing of secondary surfaces, functional load: (product deformation does not exceed .25" while load is applied).	Note: Initial measurement is taken without load applied. Final measurement is taken with load applied.	NA	/
Moisture content	CPSD-HL-01063-MTHD	Moisture content of solid wood must be a minimum of 6% and a maximum of 12%.	If moisture less than 7%, use oven drying method.	M	PASS



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
03660-USA- (V20)
D71 READY TO ASSEMBLE FURNITURE (RTA) UPHOLSTERED AND NON UPHOLSTERED
HMZ**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

Evaluation	Citation / Method	Criteria	Comments	Result	Rating
				SOLID WOOD: 10.5%	
Racking	Actual use / functionality	[Not applicable to chairs] For units 60 inches tall or taller, racking movement is not greater than 0.5 inches when applying a 10 pound horizontal force to front upper corner	Note: Safety Brackets are not used when performing this test. Bottom of unit fixed to prevent sliding using a .5" stop. Add weight to the top or bottom of unit if tipping occurs with less than the 10 lb force	M (BUNK BED)	PASS
Racking	Actual use / functionality	[Not applicable to chairs] For units less than 60 inches in height, racking does not exceed 0.5 inches when applying a 8 pound horizontal force to the front upper corner	Note: Safety Brackets are not used when performing this test. Bottom of unit fixed to prevent sliding using a .5" stop. Add weight to the top or bottom of unit if tipping occurs with less than the 8 lb force	M (TWIN BED, FULL BED)	PASS
Steel ball drop test	CPSD-GB-01058-MTHD	Table top with inlay displays no evidence of cracking or breakage when tested as follows: A 5/8 inch diameter steel ball weighing 16 grams is dropped 3 times from height of twelve (12) inches on four (4) different tiles located on four (4) different sides of the table.		NA	/
Paper or veneer environmental test	Actual use / functionality	Paper and/or veneer must fully adhere to the surface (except cardboard backs) and must pass 4-day intermittent test using the following conditions: 24 hours at 140f, 30% humidity 24 hours at 0F, 0% humidity 24 hours at 140F, 30% humidity 24 hours at 0F, 0% humidity Without delaminating. Note: The following requirements apply: 1) Always perform this test at production full testing 2) Perform only 1 time per year for instore testing 3) Do not perform this test at pre-production testing		NA	/
Drawers	Dimensional measurements	All drawer guide systems will be designed such that the drawer can open and close with ease and without binding at any point in the travel. Side-to-side travel must not exceed 8 millimeter (mm) when drawer is both half-		NA	/



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
03660-USA- (V20)
D71 READY TO ASSEMBLE FURNITURE (RTA) UPHOLSTERED AND NON UPHOLSTERED
HMZ**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

Evaluation	Citation / Method	Criteria	Comments	Result	Rating
		<p>way and fully extended, with no load inside. Product meets requirements of the following test procedures:</p> <ol style="list-style-type: none"> 1) Extend the empty drawer to the required distance (half-way or fully extended) 2) Apply a 2-lb load to one side of the drawer face and release the load. 3) Apply a 2-lb load to the opposite side of the drawer face and record the drawer position 4) The difference between the first and second measurement is the total side-to-side travel. <p>Note: Force is applied centered on the side of the drawer face. Note: Allow the drawer to "settle" into position and then take the first measurement (zero) of drawer position.</p>			
Strength properties	Walmart requirement	<p>[Applicable to upholstered products only]</p> <p>Demonstrates at least 50 lb seam strength (30 lbf for leather materials)</p> <p>Breaking Strength (Wovens) Fabric exhibits a minimum of 50 lb pull force (only perform this test if sufficient amount of sample is available.)</p> <p>Tongue Tear Strength (Wovens) Fabric exhibits a minimum of 6 lb pull force (only perform this test if sufficient amount of sample is available.)</p> <p>Note: Breaking strength and Tongue tear strength tests are not applicable to bonded leather products</p>		NA	/
Zipper performance	Walmart requirement	<p>[Applicable to upholstered products only]</p> <p>Chain Crosswise Strength Slider Pull - Pull-Off Strength</p> <p>Material (record material) Fastener Class (mm) Requirement: (lb) Actual: (lb)</p>		NA	/



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
03660-USA- (V20)
D71 READY TO ASSEMBLE FURNITURE (RTA) UPHOLSTERED AND NON UPHOLSTERED
HMZ**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

Evaluation	Citation / Method	Criteria	Comments	Result	Rating
		Note: Refer to "Zipper Performance Specifications" for Requirements			
Durability	Walmart requirement	Applicable to upholstered products only Fabric exhibits no permanent pile distortion or damage when cleaned according to labeled care instructions For any furniture with a removeable, washable cover: After washing, reinstall the washable cover to ensure it fits properly.		NA	/
Colorfastness to wet/dry crocking	Walmart requirement	[Applicable to upholstered products only] Colorfastness to wet / dry crocking Leather and Denim tested to colorfastness of Wet: Grade 2.0 minimum Dry: Grade 3.0 minimum Actual (wet) Actual (dry): All other Fabrics tested to colorfastness of Grade 3.0 minimum (Wet) Actual (wet):		NA	/
Static wetting	Walmart requirement	Applicable to upholstered products only Fabric exhibits a minimum degree of staining in static wetting of Grade 4.0		NA	/
Colorfastness to light	Walmart requirement	[Option 3] [Applicable to upholstered products only] Fabric exhibits a minimum colorfastness of Grade 4.0 minimum at 20 AFU.		NA	/
Center punch fragmentation test	ANSI Z97.1-2015 (R2020) Sec. 5.2 (Mod)	Note: All glass tops and insets must be tempered glass which does not create long shards when broken. The size of the shards will be determined by the following test method:		NA	/



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
03660-USA- (V20)
D71 READY TO ASSEMBLE FURNITURE (RTA) UPHOLSTERED AND NON UPHOLSTERED
HMZ**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

Evaluation	Citation / Method	Criteria	Comments	Result	Rating
		<p>The weight of 10 of the largest broken pieces of the tempered glass is not greater than the weight of ten square inches of the tempered glass when the glass is broken using a spring loaded center punch impacted 1 inch (25 mm) from the longest edge at the midpoint of that edge until breakage occurs.</p> <p>Weight of a 10 square inch of the tempered glass (oz) Weight of 10 broken pieces (oz)</p>			

Pricing information please refer to client price list "WMRT-GB-\$LST-GB-PRICE LIST"

No. Of Samples Required for Complete Testing	2	Furniture=2 samples; Toys= 3 samples
No. Of (Fully Packed) Cartons For Transit Testing:	1	
No. Of Working Days For Complete Testing:	5	

Client Approval:	Ryan Deleon
	28/Oct/2025
Creation Date:	09/Dec/2014
Last Revision Date:	28/Oct/2025
Pricing Review Date	
Technical Review Date:	

Key

A Additional Charge For This Test
 M Mandatory Requirement
 R Regulatory

Result Key

C Claimed
 R Recorded
 NT Not Tested
 NM Does Not Meet
 NA Not Applicable
 M Meets



**TEST PROTOCOL FOR
03660-USA- (V20)
D71 READY TO ASSEMBLE FURNITURE (RTA) UPHOLSTERED AND NON UPHOLSTERED
HMZ**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

Rating Key

PASS Pass
 FAIL Fail

Image Appendix

Zipper performance specifications.JPG	<p align="center">ZIPPER PERFORMANCE SPECIFICATIONS</p> <table border="0"> <tr> <td>Fastener Class</td> <td align="center">1 - 2</td> <td align="center">3 - 4</td> <td align="center">5 - 6 - 7</td> <td align="center">8 - 9</td> <td align="center">10</td> </tr> <tr> <td>Chain Crosswise Strength (lbs.)</td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>Metal</td> <td align="center">75</td> <td align="center">120</td> <td align="center">120</td> <td align="center">140</td> <td align="center">175</td> </tr> <tr> <td>Aluminum</td> <td align="center">55</td> <td align="center">65</td> <td align="center">85</td> <td align="center">85</td> <td align="center">95</td> </tr> <tr> <td>Molded Plastic</td> <td align="center">30</td> <td align="center">55</td> <td align="center">85</td> <td align="center">110</td> <td align="center">130</td> </tr> <tr> <td>Coil</td> <td align="center">75</td> <td align="center">85</td> <td align="center">140</td> <td align="center">175</td> <td align="center">200</td> </tr> <tr> <td>Slider Pull Pull-Off Strength (lbs.)</td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>Metal</td> <td align="center">30</td> <td align="center">35</td> <td align="center">40</td> <td align="center">50</td> <td align="center">60</td> </tr> </table>	Fastener Class	1 - 2	3 - 4	5 - 6 - 7	8 - 9	10	Chain Crosswise Strength (lbs.)						Metal	75	120	120	140	175	Aluminum	55	65	85	85	95	Molded Plastic	30	55	85	110	130	Coil	75	85	140	175	200	Slider Pull Pull-Off Strength (lbs.)						Metal	30	35	40	50	60
Fastener Class	1 - 2	3 - 4	5 - 6 - 7	8 - 9	10																																												
Chain Crosswise Strength (lbs.)																																																	
Metal	75	120	120	140	175																																												
Aluminum	55	65	85	85	95																																												
Molded Plastic	30	55	85	110	130																																												
Coil	75	85	140	175	200																																												
Slider Pull Pull-Off Strength (lbs.)																																																	
Metal	30	35	40	50	60																																												



BUREAU
VERITAS

TEST PROTOCOL FOR
13300-USA- (V58)
REG FURNITURE (INDOOR AND OUTDOOR)

BV Lab Number: 96253120624
Technician Name: DUY
Test Date: NOVEMBER 08, 2025
Reviewed By/Date: JOHN/ DECEMBER 02, 2025

Evaluation	Citation / Method	Criteria	Comments	Result	Rating
SCOPE:					
Moveable articles: (i) Used to support people or things; (ii) other functional or decorative furniture articles, including, but not limited to, products such as beds, bookcases, chairs, chests, tables, dressers, desks, pianos, console televisions, and sofas. The term "furniture article" does not include appliances, such as ranges, refrigerators, dishwashers, clothes washers and dryers, air conditioners, humidifiers; fixtures such as bathroom fixtures, built-in cabinets, chandeliers, windows, and doors; or household items such as window shades, venetian blinds, or wall hangings and draperies.					
BV Comment: Refer to individual furniture protocols for specific testing					
SUPPLEMENTARY PROTOCOL					
A All Products	WMRT-GB-PTCL-10000-USA	Test to All Products Protocol WMRT-GB-PTCL-10000-USA		M	PASS
A RTA Furniture	WMRT-HL-PTCL-03660-USA	Test to All Products Protocol WMRT-HI-PTCL-03660-USA		M	PASS
A Weight supplemental	WMRT-HL-PTCL-03700-USA	[Walmart USA Department 71 products] Test to Supplemental Protocol WMRT-HL-PTCL-03700-USA.		M	PASS
A Medical Devices	WMRT-HB-PTCL-17600-USA	Test to Supplemental Protocol WMRT-HB-PTCL-17600-USA		NA	/
STAR 2 - REGULATORY/COMPLIANCE STANDARDS					
A Children's chairs and stools.	ASTM F2613	A chair or stool intended to be used by a child with a seat height 15 in. or less. Must comply with the most current version of the standard. In lieu of testing, documentation may be submitted in the form of a test report dated within 1 year.	The Test Report must be from a CPSC approved lab	NA	/
A Bunk bed	ASTM F1427	A bed in which the undersides of any foundation is over 30 inches (760 mm) from the floor. Must comply with the most current requirements. In lieu of testing, documentation may be submitted in the form of a test report dated within 1 year.	The Test Report must be from a CPSC approved lab	M	PASS
A Furniture tipover restraints	ASTM F3096	A tipover restraint is a supplemental device that aids in the prevention of tipover. Must comply with the most current version of the standard. In lieu of testing, documentation may be submitted in the form of a test report dated within 1 year.	The Test Report must be from a CPSC approved lab	NA	/
A Bean bag chairs	ASTM F1912	An article of furniture composed of a fabric, vinyl, leather, or other cover, no internal support mechanism, and a filling of polymeric or natural material beads. Any seams which are not sewn shut are closed with a zipper. Must meet the most current version of the standard. In lieu of testing, documentation may be submitted in the form of a test report dated within 1 year.	The Test Report must be from a CPSC approved lab	NA	/



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
13300-USA- (V58)
REG FURNITURE (INDOOR AND OUTDOOR)**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

Evaluation	Citation / Method	Criteria	Comments	Result	Rating
STAR 2 - REGULATORY/COMPLIANCE REGULATIONS					
A R Bunk bed	16 CFR 1213	A bed in which the underside of any foundation is over 30 inches (760 mm) from the floor. Must comply with the most current version of the regulation. In lieu of testing, documentation may be submitted in the form of a test report dated within 1 year.	The Test Report must be from a CPSC approved lab	M	PASS
A R Bunk bed	16 CFR 1513	A bed in which the underside of any foundation is over 30 inches (760 mm) from the floor. Must comply with the most current version of the regulation. In lieu of testing, documentation may be submitted in the form of a test report dated within 1 year.	The Test Report must be from a CPSC approved lab	M	PASS
A R Children's Folding Chairs and Children's Folding Stools	16 CFR 1232	Foldable chairs and stools with a seat height of 15 inches or less, which are intended to be used by a single child who can get in and out of the product unassisted. Must comply with the most current version of the regulation. In lieu of testing, documentation may be submitted in the form of a test report dated within 1 year.	The Test Report must be from a CPSC approved lab	NA	/
R Clothing storage units	16 CFR 1261	Clothing Storage Units including but not limited to chests, bureaus, dressers, chests of drawers, drawer chests, door chest, chifferobes, armoires, and wardrobes. Must comply with the most current version of the regulation. In lieu of testing, documentation may be submitted in the form of a test report dated within 1 year.	The Test Report must be from a CPSC approved lab	NA	/
STAR 2 - REGULATORY/COMPLIANCE RESTRICTED SUBSTANCES					
A R Lead content (surface coating)	16 CFR 1303	All surface coating shall not contain lead in which the lead content is in excess of 0.009% (90 ppm) of the weight of the total content. Exemptions from Lead Requirements in surface coatings (16 CFR 1303) 1. Mirrors which are part of furniture articles to the extent that they bear lead containing backing paint. 2. Artists' paints and related materials. 3. Metal furniture articles (but not metal children's furniture) bearing factory applied (lead) coatings. In lieu of testing, documentation may be submitted in the form of a test report dated within 1 year.	The Test Report must be from a CPSC approved lab	M	PASS
A R Vinyl Flooring: WA Safer Products	Washington Safer Products Restrictions and	Products with any ortho-phthalate individually or in combination at a level equal to or greater than 1,000 ppm are prohibited from being sold in Washington. In lieu of testing, documentation may be submitted in the form of a test report dated within 1 year.	The Test Report must be from a CPSC approved lab	NA	/



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
13300-USA- (V58)
REG FURNITURE (INDOOR AND OUTDOOR)**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

Evaluation	Citation / Method	Criteria	Comments	Result	Rating
	Reporting WAC 173-337				
STAR 2 - REGULATORY/COMPLIANCE PHYSICAL AND MECHANICAL					
A R Upholstered furniture flammability	16 CFR 1640 / California Bureau of Home Furnishings and Thermal California TB 117	Upholstered furniture shall comply with the California Technical Bulletin 117-2013 flammability requirements. In lieu of testing, documentation may be submitted in the form of a test report dated within 1 year.	The Test Report must be from a CPSC approved lab	NA	/
STAR 2 - REGULATORY/COMPLIANCE PACKAGING AND LABELING					
R Upholstered furniture flammability labeling	16 CFR 1640	Manufacturers of products that are subject to California Technical Bulletin 117-2013 must include the statement "Complies with U.S. CPSC requirements for upholstered furniture flammability" on a permanent label located on the product.		NA	/
A R California Upholstered Furniture Flammability Label TB 117- 13	California Bureau of Home Furnishings and Thermal California TB 117; Cal. Code Reg. Title 4, §1374.3	Shall have a label that meets the requirements of Article 13, Section 1374.3 indicating that product meets CA TB 117, including size, placement and readability requirements. CA TB 117 flammability labels for upholstered furniture are required to reference the "CALIFORNIA BUREAU OF HOUSEHOLD GOODS AND SERVICES," effective January 1, 2020.	Size = Stated font size requirements. Placement = Stated placement of information (i.e. "prominent" or "Principal Display Panel") Readability = Spelling and grammar, abbreviations (i.e. "in" versus "inches")	NA	/
R Upholstered furniture: flame retardant chemicals labeling except size, placement and readability	California Business and Professions Code, Chapter 862, Section 19094	Upholstered furniture shall indicate whether or not the product contains added flame retardant chemicals by including the following "flame retardant chemical statement" and indicate with an "X" in one of the appropriate blanks. "The upholstery materials in this product: _____contain added flame retardant chemicals _____contain NO added flame retardant chemicals. The State of California has updated the flammability standard and determined that the fire safety requirements for this product can be met without adding flame retardant chemicals. The state has identified many flame retardant chemicals as being known to, or strongly suspected of, adversely impacting human health or development."	Refer to WMRT-GB-SUPP-SB 1019 SUPPLIER DECLARATION.	NA	/



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
13300-USA- (V58)
REG FURNITURE (INDOOR AND OUTDOOR)**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

	Evaluation	Citation / Method	Criteria	Comments	Result	Rating
			Suppliers must submit the SB1019 Declaration within 72 hours to the 3rd party test lab for verification.			
R	Upholstered furniture: flame retardant chemicals labeling size, placement and readability of labeling only	California Business and Professions Code, Chapter 862, Section 19094	Label requirement shall comply with Section 1374.3 of Title 4 of the California Code of Regulations for font size of 1/8 in min. and label size of 2 in x 3 in min. The statement shall follow TB 117 flammability compliance statement (on bottom or right hand side of the flammability compliance statement).	Size = Stated font size requirements. Placement = Stated placement of information (i.e. "prominent" or "Principal Display Panel") Readability = Spelling and grammar, abbreviations (i.e. "in" versus "inches")	NA	/
	Upholstered Furniture: Flame Retardant Chemicals	San Francisco, CA, Environment Code Ch. 28, § 2801-2807	SB1019 Declaration indicates that the upholstery materials in the product contains added flame retardant chemicals.	Refer to WMRT-GB-SUPP-SB 1019 SUPPLIER DECLARATION.	NA	/
A R	Registration for durable nursery product	16 CFR 1130 / CPSIA Sec. 104	Manufacturers of durable nursery products for use by children < 5 years must provide consumers with a postage paid consumer registration form with each such product to allow for direct notification to consumers in the event of a recall. The registration card must be attached to the surface of each product so that the consumer must notice and handle the form after purchasing the product. Each manufacturer must maintain a record of the names, addresses, e-mail addresses, and other contact information of consumers who register their ownership of such products. The following information must be permanently placed on the product: manufacturer name and contact information, model name and number, and the date of manufacture. Registration form includes option for the consumer to register through the internet. Note: Manufacturers that do not have web sites must provide an e-mail address with an automatic reply for product registration. Effective Date (Manufactured on or after) June 28, 2010		NA	/

Walmart does not guarantee that the information contained in this protocol is current, or that all requirements are listed. Walmart is committed to providing our customers with safe products that comply with all appropriate regulations and standards. Walmart does not provide legal advice to its suppliers, so where needed, suppliers should seek their own legal counsel on how to comply with all laws applicable to their product.

Pricing information please refer to client price list "WMRT-GB-\$LST-GB-PRICE LIST".



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
13300-USA- (V58)
REG FURNITURE (INDOOR AND OUTDOOR)**

BV Lab Number: **96253120624**
Technician Name: DUY
Test Date: NOVEMBER 08, 2025
Reviewed By/Date: JOHN/ DECEMBER 02, 2025

No. Of Samples Required for Complete Testing	2	
No. Of (Fully Packed) Cartons For Transit Testing:	1	
No. Of Working Days For Complete Testing:	5	

Client Approval:	Ryan Deleon
	11/Feb/2025
Creation Date:	16/Aug/2011
Last Revision Date:	10/Feb/2025
Pricing Review Date	
Technical Review Date:	

Key

A	Additional Charge For This Test
M	Mandatory Requirement
R	Regulatory

Result Key

C	Claimed
M	Meets
R	Recorded
NM	Does Not Meet
NT	Not Tested
NA	Not Applicable

Rating Key

PASS	Pass
FAIL	Fail



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
03700-USA- (V12)
WALMART DEPARTMENT 71 WEIGHT SUPPLEMENT HMZ**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

Evaluation	Citation / Method	Criteria	Comments	Result	Rating
SCOPE:					
This protocol is a weight supplement applicable for Walmart Department 71 products.					
STAR 3 - QUALITY/PERFORMANCE					
Production / Production annual	Standard Measurement	<p>Note 1: Product is weighed assembled excluding all packaging</p> <p>Note : Bill of Material and three-view drawing of all components must be supplied with the sample for production / production annual testing</p> <p>Record overall weight from BOM (lb) Record production weight (lb) Weight difference between production sample and BOM (%)</p>		<p align="center">M</p> <p align="center">BILL OF MATERIAL AND THREE-VIEW DRAWING OF ALL COMPONENT WERE PROVIDED</p> <p align="center">NET WEIGHT FROM BOM: 123.4 LBS</p> <p align="center">PRODUCTION WEIGHT: 123 LBS</p> <p align="center">WEIGHT DIFFERENCE BETWEEN PRODUCTION SAMPLE AND BOM: 0.3%</p>	PASS
Production / Production annual	Standard Measurement	<p>Product meets the following tolerance requirements as applicable:</p> <p>Metal products, plastic products, foam chairs and bean bag chairs are within $\pm 5\%$ of the BOM samples weight (Y/N)</p> <p>Wood products are within $\pm 10\%$ of the BOM samples weight (Note: Hardware such as metal hinges, door pulls, latches, screws, nails, etc. are not considered mix of wood and metal products) (Y/N)</p> <p>Upholstered products, and products with a mix of wood and metal are within $\pm 8\%$ of the BOM samples weight (Note: Mixed wood and metal products are products with structural components that are constructed of wood and metal) (Y/N)</p>	<p>Note: The following directions and examples are not all encompassing.</p> <p>Electric fireplace wooden TV stand combo should follow the wood 10% section.</p> <p>Kitchen cart wooden construction with marble top should follow the 10% section.</p> <p>Glass table with metal frame for the glass and wood for the base material should follow the 8% section.</p> <p>Free standing shelf made with MDF board and plastic pole supports should follow the 8% section.</p>	M	PASS



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
03700-USA- (V12)
WALMART DEPARTMENT 71 WEIGHT SUPPLEMENT HMZ**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

Evaluation	Citation / Method	Criteria	Comments	Result	Rating
Production / Production annual	Standard Measurement	[Production / Production annual] List Of Discrepancies When Product Is Compared To The Three-view Drawing And Bill Of Material (if Applicable): Item BOM Weight Actual Weight %	Note: Mattresses do not require a line drawing	SEE DISCREPANCIES TABLE	DATA

Pricing information please refer to client price list "WMRT-GB-\$LST-GB-PRICE LIST".

No. Of Samples Required for Complete Testing	2	
No. Of (Fully Packed) Cartons For Transit Testing:		
No. Of Working Days For Complete Testing:	5	

Client Approval:	Ryan Deleon
	09/Dec/2024
Creation Date:	23/Oct/2014
Last Revision Date:	09/Dec/2024
Pricing Review Date	
Technical Review Date:	

Key

A Additional Charge For This Test
 M Mandatory Requirement
 R Regulatory

Result Key

C Claimed
 M Meets
 R Recorded
 NM Does Not Meet
 NT Not Tested
 NA Not Applicable

Rating Key

PASS Pass
 FAIL Fail



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
08000-USA- (V47)
QTY TOYS AND CHILDRENS PRODUCTS HMZ**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

Evaluation	Citation / Method	Criteria	Comments	Result	Rating
SCOPE:					
Applies to a consumer product designed or intended by the manufacturer for a child, 12 years of age or younger, for use by the child.					
Excludes US Coast Guard approved life vests / jackets.					
Note that this protocol should be used along with the product specific protocol for the item. For example: A Easter basket that is intended for children should also be evaluated to the requirements in the Basket, Bucket, Pail protocol.					
SUPPLEMENTARY PROTOCOL					
A Toys	WMRT-18000-USA	Product shall be tested to children's toys protocol, if applicable		NA	/
A Children's Product	WMRT-TY-PTCL-18001-USA	Test to Children's Product Protocol WMRT-TY-PTCL-18001-USA		M	PASS
STAR 3 - QUALITY/PERFORMANCE					
Alphanumeric representation	Visual	[D7(43), 18, 19(44/52), 67 and 79] Letters (A-Z) and/or numbers (0-9) shall be represented at least once in products with alphanumeric pieces.	Basic Requirement	NA	/
Staples	Visual	Staples are permitting to be used in the binding of instruction manual booklets. However, the staples must be properly seated with no protruding sharp edges. Staples shall not be used in packaging. However, packaging for the following products is exempt: <ul style="list-style-type: none"> - Products weighing >15 kg (including packaging); - Products that require team lift; - Products that require adult assembly; - Products in D18/67 that require the use of this protocol; - Not applicable to multi pack, party pack, or bulk packaged products sold in D18/67. 	Basic Requirement	NA	/
Twist Ties	Visual	[Applicable to Dept 07 products only] Packaging shall not include any coated or uncoated wire twist ties.	Basic Requirement	NA	/
Play Wear / Role Play Apparel Dimensions	Standard Measure	Product sizes shall meet sizing requirements in WM specifications found in WMRT-GB-SUPP-COSTUME SIZE CHARTS NOTE: If a product is labeled with cross sizing (ie: S/M, X/XL) the larger sizing specifications must be used for measurement verification. For example, a product labeled S/M would use the Medium size specifications. NOTE: Products that contain functional spandex/elastic/stretch, etc. shall meet sizing requirements in a stretched state (maximum dimension obtained with no damage to product).	Basic Requirement	NA	/



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
08000-USA- (V47)
QTY TOYS AND CHILDRENS PRODUCTS HMZ**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

Evaluation	Citation / Method	Criteria	Comments	Result	Rating
		NOTE: Not applicable to D18 costumes.			
Doll Clothing - Textile Seam Requirement	Visual	<p>- Hems shall have a clean finish (does not apply to 14 inch doll clothing). Hems shall be cover stitched to allow them to lay flat. For 18" clothes sold with the doll only: Hems may be single stitched so long as they have a clean finish and lay flat.</p> <p>- Seams on woven fabrics shall include overedge stitching. For 18" clothes sold with the doll only: The supplier may use single stitching on seams if it can provide a clean and neat finish. For seams that cannot provide a clean finish, an overstitch (or lock stitch) will still be required.</p> <p>- Seams shall be neat with no open areas, loose threads, needle damage or puckering or twisting. - Swift tack attachments shall be attached in the seam to prevent fabric holes. - Doll clothing shall exhibit no major fabric defects such as stains, holes, snags, runs, loose threads, excessive pilling and slub yarns. - Doll clothing shall exhibit no noticeable color differences in fabric used.</p> <p>Note 1: Applies to all "My Life As..." brand doll clothing for 14" and 18" dolls, sold with the doll or separately. Note 2: Any exceptions to requirements require approval from the Dept. 07 Home & GM Technical Manager and must be included in the product specification or on the lab test request form.</p>	Basic Requirement	NA	/
Functional test	Actual Use	<p>The product as received, shall function as intended. All claimed functions on package, instructions, etc. shall be verified. All evaluation details shall be reported. If claim cannot be verified by lab, a test report from vendor is acceptable. All functions shall be evaluated 5 times on same sample. For sample with more than 5 different functions, 5 functions shall be randomly selected and shall be evaluated 5 times. They shall function as intended.</p>	Function Check	M	PASS
Function Check after Abuse test	16 CFR 1500.50 (Mod)	<p>[Applies to products age graded under 96 months only] [Products age graded "8+ years" are exempt]</p> <p>The functions evaluated in the functional use test shall operate effectively after safety abuse testing. Note: Disassembly of a component that can be reattached and function properly is not a reason for failure.</p> <p>Modification: - Exclude bite test - For tension testing of foam components, sequins, and paper / fiberboard components (400gsm or less); a minimum of 5 lb is used as the assessment force instead of that specified in 16 CFR 1500.50</p>	Function Check	M	PASS



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
08000-USA- (V47)
QTY TOYS AND CHILDRENS PRODUCTS HMZ**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

	Evaluation	Citation / Method	Criteria	Comments	Result	Rating
A	Environmental testing	ISTA 2A (Mod)	<p>[Applicable to products intended or labeled for Outdoor Use, Liquid Products, Liquid Filled Products] [Not applicable to cosmetics] The product shall still operate after returning to room temperature and liquids or liquid filled products shall exhibit no visual change (such as color change, cloudiness, or separation) and all liquids still function as intended, after one sample is subjected to the following complete environmental test: - 12 hours @ 57 °C (± 3°) and 15 % Relative Humidity; - 4 hours @ ambient temperature; - 12 hours @ -18 °C (± 2°). Note: If product such as bubble solution is frozen it shall still function as intended after unfreezing. Note: Container damage or permanent deformation is not a reason for failure.</p>	Function Check	NA	/
A	Colorfastness to crocking	AATCC 8-16e(2022)e	<p>[Applicable to textiles which are at least 2.0 in. x 5.1 in] [Not applicable to D18 or D67 products] Textiles shall not show noticeable color transfer in dry and wet crocking and shall exhibit colorfastness to crocking of: [Wet and Dry] Light Color Textile: Grade 4.0 minimum Dark Color Textile: Grade 3.0 minimum Dark Color Denim: Grade 2.0 minimum Note: Any failures must include actual swatch results as failure images in final report.</p>	Material Reliability	NA	/
A	Coating adhesion test	ASTM D3359-23 (Mod)	<p>[Not required for surface coatings on areas that are too small to be tested in accordance with the standard] [Not applicable to D18 or D67 products] Surface coating shall demonstrate a minimum 3A rating when tested using test method A of ASTM D3359 (Elcometer 99 tape). Modification: Scope Widened to Non-metallic Substrate</p>	Material Reliability	M GRADE: 4A	PASS
A	Resistance to corrosion	ASTM B117-19 modified	<p>[Applies to accessible metal components only] [Not applicable to components which intentionally use lubricating oil] Shall demonstrate the following minimum reference grade (in accordance with ASTM D610) after salt spray exposure using the following parameters: *Dept 07 - Outdoor Items used with water - 5% Salt Spray 24 hours. principal surface 8.0 / Other surface(s) - 7.0. *Dept 07 - Outdoor Items intended to bear the player's weight - 1% Salt Spray 24 hours. principal surface 8.0 / Other surface(s) - 7.0. *All other products demonstrate the following minimum reference grade (in accordance with ASTM D610) after exposure to 95% humidity for 24 hours. principal surface 8.0 / Other surface(s) - 7.0 Client's requirement</p>	Material Reliability	M	PASS



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
08000-USA- (V47)
QTY TOYS AND CHILDRENS PRODUCTS HMZ**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

	Evaluation	Citation / Method	Criteria	Comments	Result	Rating
A	Cycling	Actual use / functionality	[Applies to switches, buttons, sensors, moving parts & components, functioning parts (including speaker, LED, motor, etc.)] All functioning and moving components (maximum range of movement) shall withstand 50 operation cycles of with no loss of functionality.	Key Components	NA	/
A	Battery operated - Try me	Actual use / functionality	"Try me" must be functional for at least 500 cycles with Supplied Batteries. (Products with solid on/off switch are exempted from this requirement when switch could shut-off the toys or products.) Supplier can provide self testing report for document review.	Key Components	NA	/
A	Trigger activation	Actual use / functionality	[Applicable to toys intended to fire projectiles, missiles, etc.] Shall demonstrate no trigger activation after projectile device is loaded into the firing / launching device and left engaged for 30 minutes. Device is fired 50 times and the trigger activation test is repeated.	Key Components	NA	/
A	Elastic Durability	ASTM F963-23 Sec. 8.9 (Mod)	[Applicable to D7 only] [Not applicable to flat elastic less than or equal to 3/16 in. wide, cord elastic 1/8 in. or narrower] Elastic component(s) shall demonstrate no breakage or deformation when tested as follows: <ul style="list-style-type: none"> - Extend to a maximum of 2 times the original length using a maximum of 10 lbf, for 10 seconds; - Allow to rest in relaxed state for 10 seconds; - Repeat a total of 10 times. Following the stretch / rest cycles above, the elastic shall extend a minimum of 1.5 times its original length and recover within 6% of its original length, without breakage or deformation	Key Components	NA	/
A	Valve strength	ASTM F963-23 Sec. 8.9 (Mod)	Inflation valve withstands a 25 lbs pull with no degradation that may affect operability or cause leakage.	Key Components	NA	/
A	Leakage resistance / inflatable toys	Actual use / functionality	No deflation or water/ air leakage during and after 24 hour with product fully inflated and/or filled with water with claim loading (if no claim loading or the claim is smaller than 150% of the normal player's weight, use 150% of the normal player weight claimed).	Key Components	NA	/
A	Component load strength	Actual use / functionality	[Applicable to product and packaging] Hangers, hooks, towing eyes, anchors, brackets, and handles (on product or package) shall not separate from the product or package when loaded with 3 times the weight of actual usage for 1 minute.	Key Components	NA	/
A	Battery Operated Toy/Vehicle for on, under, or near Water	As per Criteria	[Applies to battery operated toys – any vehicle intended for use under or near water or a boat. Both tests (1&2) apply.]	Electric and Battery Operated Products	NA	/



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
08000-USA- (V47)
QTY TOYS AND CHILDRENS PRODUCTS HMZ**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

	Evaluation	Citation / Method	Criteria	Comments	Result	Rating
	/ Boat, etc - Immersion		<p>Note: "Near water" products include products like all-terrain RC truck that can drive through water or marketed for use around water. If the package shows the vehicle on or near water, or there is a claim about water resistance, it should be tested accordingly. If not, then no water should be included in the testing.</p> <p>1. Product including toy/vehicle/boat shall demonstrate proper function after the unenergized unit is immersed (with New batteries installed) in water at a depth of 15 cm (measured to top of product) for 24 hours. After 24 hours of immersion, remove the product from the water and check for functionality. Note: New batteries are used for function test.</p> <p>2. Shall demonstrate no functional defects and no cracks when fully charged boat on water / vehicle on land, is impacted at full speed 20 times in front against a concrete block. Note: Aesthetic defects as a result of the test are acceptable. Note: For items that can operate on water and land, this test shall be conducted on the surface that results in the highest speed. For products like Hovercrafts or similar where the speeds would be the same on water as on land, Test 2 shall be performed on both water and land.</p>			
A	Battery Operated Flying Toy/Vehicles - Durability	As per criteria	<p>Flying products shall demonstrate no functional failures when tested as follows:</p> <ol style="list-style-type: none"> Product is allowed to free fall from a height of 3 meters onto a smooth concrete surface 5 times. All product functions (not limited to flying functions) are verified. Repeat 1 and 2 until the product no longer functions, not to exceed total of 50 free falls. Record number of free falls when product ceases to function as intended. <p>Product has fully charged battery during test. Product is not controlled during free fall.</p> <p>Note: - Also applies to vehicles that are able to climb walls and/or drive on ceilings. - Aesthetic defects as a result of the test are acceptable.</p>	Electric and Battery Operated Products	NA	/
A	Battery Operated Ground Operated Toy/Vehicles (Wheeled, Crawling, or Hovering) Products - Durability	As per criteria	<p>Shall demonstrate no functional defects and no cracks when fully charged vehicle is impacted at full speed 50 times in front and 50 times in rear against a concrete block.</p> <p>Note 1: Aesthetic defects as a result of the test are acceptable. Note 2: Not applicable to ride on/in vehicles.</p>	Electric and Battery Operated Products	NA	/

Important: in addition to this performance testing protocol, products must comply with all appropriate Directives and Protocols issued by Walmart Product Safety and Compliance team. This Quality Protocol is minimum Performance Requirement for all items. Supplier is the ultimate owner of product's Safety and Quality. Any issue, please refer to the Supplier Agreement.



**TEST PROTOCOL FOR
08000-USA- (V47)
QTY TOYS AND CHILDRENS PRODUCTS HMZ**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

Guideline of Protocol Selection:

- 1, All definitions are same as Safety Directives and Protocols. Protocol Selection is same as Safety Directives and Protocols.
- 2, If there are any conflicts or redundancies against Safety Directives and Protocols, the interpretation from Safety Directives and Protocols takes precedence.
- 3, Preemption: 1st is Safety Directives and Protocols , 2nd is Additional Performance testing in this protocol, 3rd is Basic Requirement, Function Check, Material Reliability and Key components together in this performance protocol. Before and after all life testing, the function need be re-verified.
- 4, If any product can't meet this performance protocol, the supplier needs to discuss with WM Sourcing and MQE before submitting samples to lab for testing. For domestic item, supplier should contact the buyers. Walmart will advise on the application of quality requirements for their product. Supplier needs to submit the final decision with testing samples to the lab together. The testing criteria will be based on the final decision to evaluate the samples.

Pricing information please refer to client price list "WMRT-GB-\$LST-GB-PRICE LIST".

No. Of Samples Required for Complete Testing	2	Additional 2 samples for battery operated
No. Of (Fully Packed) Cartons For Transit Testing:	1	
No. Of Working Days For Complete Testing:	5	Some of the test may depend on the life time of battery and required longer TAT.

Client Approval:	Ryan Deleon
	11/Jul/2025
Creation Date:	06/Jul/2007
Last Revision Date:	10/Jul/2025
Pricing Review Date	
Technical Review Date:	

Key

A Additional Charge For This Test
 M Mandatory Requirement
 R Regulatory

Result Key

C Claimed
 M Meets
 R Recorded
 NM Does Not Meet
 NT Not Tested
 NA Not Applicable



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
08000-USA- (V47)
QTY TOYS AND CHILDRENS PRODUCTS HMZ**

BV Lab Number: **96253120624**
Technician Name: DUY
Test Date: NOVEMBER 08, 2025
Reviewed By/Date: JOHN/ DECEMBER 02, 2025

Page 42 of 141

Rating Key

PASS

FAIL

Pass

Fail



BUREAU
VERITAS

TEST PROTOCOL FOR
08000-USA- (V47)
QTY TOYS AND CHILDRENS PRODUCTS HMZ

BV Lab Number: 96253120624
Technician Name: DUY
Test Date: NOVEMBER 08, 2025
Reviewed By/Date: JOHN/ DECEMBER 02, 2025

Image Appendix

Definition and examples 1.jpg

Seams are neat with no loose threads, needle damage, open seams, puckering etc.

Loose threads



Recommended overedge stitching



Seam stitching to be appropriate to the fabric. Overedge seaming used on woven and hems. Hem areas are to be neat and using a cover stitch allows the hem to lay flat



Recommended overedge stitching



Recommended overedge stitching





**BUREAU
VERITAS**

**TEST PROTOCOL FOR
08000-USA- (V47)
QTY TOYS AND CHILDRENS PRODUCTS HMZ**

BV Lab Number: **96253120624**
Technician Name: DUY
Test Date: NOVEMBER 08, 2025
Reviewed By/Date: JOHN/ DECEMBER 02, 2025

Definition and examples 2.jpg

Color – Exhibits good overall color quality



Each piece of the garment is cut from same color lot of fabric



Fabric Defects – No major defects such as holes, runs, snags, stains, slub yarns, etc.

Swift tacks attachments are to be in the seam to prevent holes in fabrics.





BUREAU
VERITAS

TEST PROTOCOL FOR
08000-USA- (V47)
QTY TOYS AND CHILDRENS PRODUCTS HMZ

BV Lab Number: 96253120624
Technician Name: DUY
Test Date: NOVEMBER 08, 2025
Reviewed By/Date: JOHN/ DECEMBER 02, 2025

WMRT-10100-
Wal-Mart Doll
Clothing 1.jpg

THREAD ENDS –
Two thread tails (or fewer) less than 3/8 inch long at the end of a seam is acceptable.



HOLES -
Swift tacks must be in seams to prevent holes in garments or doll bodies.



COLOR DEFECTS –
Overall garment must exhibit good color quality with each piece of the garment cut from the same color lot of fabric.



Acceptable



Not Acceptable



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
08000-USA- (V47)
QTY TOYS AND CHILDRENS PRODUCTS HMZ**

BV Lab Number: **96253120624**
Technician Name: DUY
Test Date: NOVEMBER 08, 2025
Reviewed By/Date: JOHN/ DECEMBER 02, 2025

WMRT-10100-
Wal-Mart Doll
Clothing 2.jpg

**All hems must be clean
finished.**



Overedge Hem



Turned and Stitched Finish



Not Acceptable



BUREAU
VERITAS

TEST PROTOCOL FOR
08000-USA- (V47)
QTY TOYS AND CHILDRENS PRODUCTS HMZ

BV Lab Number: 96253120624
Technician Name: DUY
Test Date: NOVEMBER 08, 2025
Reviewed By/Date: JOHN/ DECEMBER 02, 2025

WMRT-10100-
Wal-Mart Doll
Clothing 3.jpg

Approved Knit Hems

Turned and lock stitched is also acceptable. Refer to individual specification sheets.



Approved stable knit seams



Overedge



Unfinished

Overedge seaming is required for all WOVEN fabrics.





BUREAU
VERITAS

TEST PROTOCOL FOR
08000-USA- (V47)
QTY TOYS AND CHILDRENS PRODUCTS HMZ

BV Lab Number: 96253120624
Technician Name: DUY
Test Date: NOVEMBER 08, 2025
Reviewed By/Date: JOHN/ DECEMBER 02, 2025

Image Appendix

Definition and examples 1.jpg

Seams are neat with no loose threads, needle damage, open seams, puckering etc.

Loose threads



Recommended overedge stitching



Seam stitching to be appropriate to the fabric. Overedge seaming used on woven and hems. Hem areas are to be neat and using a cover stitch allows the hem to lay flat



Recommended overedge stitching



Recommended overedge stitching



Definition and examples 2.jpg

Color – Exhibits good overall color quality



Each piece of the garment is cut from same color lot of fabric



Fabric Defects – No major defects such as holes, runs, snags, stains, slub yarns, etc.

Swift tacks attachments are to be in the seam to prevent holes in fabrics.



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
08119-USA- (V15)
BUNK BED HMZ**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

Evaluation	Citation / Method	Criteria	Comments	Result	Rating
SCOPE:					
Bunk bed is defined as any structure that includes at least one sleeping surface in which the underside of the foundation is over 30 in. (762 mm) from the floor.					
SUPPLEMENTARY PROTOCOL					
A Toys and children's products	WMRT-TY-PTCL-08000-USA	[If applicable] Test to Supplemental Protocol WMRT-TY-PTCL-08000-USA.		M	PASS
A All Products	WMRT-GB-PTCL-10000-USA	Test to All Products Protocol WMRT-GB-PTCL-10000-USA		M	PASS
A Weight supplemental	WMRT-HL-PTCL-03700-USA	[Walmart USA Department 71 products] Test to Supplemental Protocol WMRT-HL-PTCL-03700-USA (Effective date 03/24/14).		M	PASS
A RTA Furniture	WMRT-HL-PTCL-03660-USA	Test to All Products Protocol WMRT-HI-PTCL-03660-USA		M	PASS
STAR 3 - QUALITY/PERFORMANCE					
Location of warning	Visual	Warning, including mattress dimensions, is displayed on the carton containing bed ends.		M	PASS
Parts inventory	Visual check	Packaging shall includes all hardware required for proper assembly.		M	PASS
Instructions	Visual	Instructions shall be provided with the bed and shall be easy to read and understand.		M	PASS
Instructions - content	Visual	Instructions shall contain the following warning: Prohibit more than one person on upper bunk.		M	PASS
A Ladder strength test	Actual use / functionality	Each step shall withstands an 400 lb load applied in the center of the step. Load is distributed across a 3.5 in. wide wooden over the full depth of the step for one minute.		M	PASS
A Moisture content	Weight measurement before and after oven dry method	[Wood] [For WM USA product other than Dept. 14 or Dept. 74] Shall be maximum 12%. Report the actual moisture content.		M SOLID WOOD: 10.5%	PASS
A Moisture content	Weight measurement before and after oven dry method	[Wood] [For WM USA product in Dept. 14 or Dept. 74] Shall be between 6% - 12%. Report the actual moisture content.		NA	/
Corrosion resistance	CPSD-GB-01057-MTHD	All metal surfaces shall be plated, coated, or equivalent to inhibit corrosion.		M	PASS



**TEST PROTOCOL FOR
08119-USA- (V15)
BUNK BED HMZ**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

IMPORTANT NOTE: The information presented under the "Criteria" of this protocol is for information only and does not replace the content of the standard. Details of the requirements should be referred to the original standards.
 Pricing information please refer to client price list "WMRT-GB-\$LST-GB-PRICE LIST".

No. Of Samples Required for Complete Testing	4	
No. Of (Fully Packed) Cartons For Transit Testing:		
No. Of Working Days For Complete Testing:	10	

Client Approval:	Kelly Nasradinaj
	24/Nov/2022
Creation Date:	03/Apr/2009
Last Revision Date:	23/Nov/2022
Pricing Review Date	
Technical Review Date:	

Key

A Additional Charge For This Test
 M Mandatory Requirement
 R Regulatory

Result Key

C Claimed
 M Meets
 R Recorded
 NM Does Not Meet
 NT Not Tested
 NA Not Applicable

Rating Key

PASS Pass
 FAIL Fail



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
18001-USA- (V85)
REG CHILDREN'S PRODUCT**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

Evaluation	Citation / Method	Criteria	Comments	Result	Rating
SCOPE:					
Applies to products that lack play value, but by design, marketing, or advertising will primarily be used by children 12 years of age or younger. This protocol does not cover Toys or US Coast Guard Approved Life Vests/Jackets. Additional requirements may apply to this product. Please refer to the US Product Safety & Compliance Manual for details. (Retail Link --> Apps --> Product Safety and Compliance Library)					
SUPPLEMENTARY PROTOCOL					
A All Products	WMRT-GB-PTCL-10000-USA	Test to All Products Protocol WMRT-GB-PTCL-10000-USA		M	PASS
A Medical Devices	WMRT-HB-PTCL-17600-USA	Test to Supplemental Protocol WMRT-HB-PTCL-17600-USA		NA	/
STAR 2 - REGULATORY/COMPLIANCE REGULATIONS					
A Connected Devices - Internet of Things (IoT) Devices for Children	Walmart USA Product Safety and Compliance Standard based on 16 CFR 312	Internet of Things (IoT) devices for children that collect personal information from user must meet the Children's Online Privacy Protection rule (COPPA) requirements. Suppliers must submit the Supplier Certification of COPPA Compliance at the time of production testing.	Refer to WMRT-GB-SUPP-SUPPLIER CERTIFICATION OF COPPA COMPLIANCE.	NA	/
STAR 2 - REGULATORY/COMPLIANCE RESTRICTED SUBSTANCES					
A New York Toxic Chemicals in Children's Products	New York Environmental Conservation Law §37-0901 & §37-0909	No person shall sell in New York a children's product, as defined in the legislation, in which tris (1, 3 dichloro-2-propyl) phosphate (CAS 13674-87-8), benzene (CAS 71-43-2) or asbestos (CAS 1332-21-4) is intentionally added. In lieu of testing, documentation may be submitted in the form of either a test report or a Letter of Guarantee dated within 1 year.	"Children's product" means a consumer product primarily intended for, made for or marketed for use by children, such as baby products, toys, car seats, school supplies, personal care products as defined in section 37-0117 of this article, a product designed or intended by the manufacturer to help a child with sucking or teething, to facilitate sleep, relaxation, or the feeding of a child, and children's novelty products, children's jewelry as defined in section 37-0115 of this article, children's bedding, furniture, furnishings, and apparel. "Children" means a person or persons aged twelve and under.	M (LOG WAS PROVIDED DATE: OCTOBER 27, 2025)	PASS



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
18001-USA- (V85)
REG CHILDREN'S PRODUCT**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

Evaluation	Citation / Method	Criteria	Comments	Result	Rating
			The Test Report must be from a CPSC approved lab.		
A R Lead content (substrate)	16 CFR 1500.87 - 16 CFR 1500.91	<p>All accessible substrates on items intended for children 12 years of age and under shall not contain lead in excess of 0.01% (100 ppm) of the weight of the total content.</p> <p>The following materials are exempted from the requirement: precious gemstones, semiprecious gemstones and other minerals, natural and cultured pearls, wood, paper or similar materials made from wood or other cellulosic fiber, CMYK process printing inks, textiles made with natural and manufactured fibers (dyed or undyed), other plant and animal derived materials, surgical steel and other stainless steel within the designation of Unified Numbering System (UNS) S13800-S66286, and precious metals (Gold (at least 10 karat); Sterling Silver (at least 925/1000), Platinum, Palladium, Rhodium, Osmium, Iridium, Ruthenium, Titanium, and certain untreated and unfinished engineered wood products (EWPs), specifically particleboard, hardwood plywood, and medium density fiberboard, made from virgin wood or pre-consumer wood waste.</p> <p>To support testing exemption for EWPs, a material declaration through a formal LOG must be provided to the third party lab at time of testing. If no material declaration is made, the third party lab will conduct lead content testing.</p> <p>In lieu of testing, documentation may be submitted in the form of either a Test Report or a Letter of Guarantee dated within 1 year.</p>	<p>Suppliers must indicate on the test request form any materials (such as stainless steel) which are exempt, to avoid unnecessary testing. Walmart reserves the right to audit supporting documentation at any time. /// CPSD-AN-00007-MTHD/ CPSD-AN-00008-MTHD Compositing up to 3 Aluminum alloy components of - children's die-cast, - ride-on pedal tractors and - similar ride-on children products for children ages 3 years and older shall meet a lead content in substrate limit of 300 ppm, which is exempted from 100 ppm lead content limit. XRF screening should be firstly performed whenever possible, please refer "Application guide of XRF test for CPSIA total lead content" in SUPP.</p> <p>The Test Report must be from a CPSC approved lab.</p>	M	PASS
A R Lead content (surface coating)	16 CFR 1303	<p>All surface coating shall not contain lead in which the lead content is in excess of 0.009% (90 ppm) of the weight of the total content.</p> <p>Exemptions from Lead Requirements in surface coatings (16 CFR 1303)</p> <ol style="list-style-type: none"> 1. Mirrors which are part of furniture articles to the extent that they bear lead containing backing paint. 2. Artists' paints and related materials. 3. Metal furniture articles (but not metal children's furniture) bearing factory applied (lead) coatings. <p>In lieu of testing, documentation may be submitted in the form of a test report dated within 1 year.</p>	<p>Consumer Product Safety Improvement Act of 2008 / 16 CFR 1303 / AOAC 974.02 modified / CPSD-AN-00001-MTHD Compositing up to 3 Component testing is allowed XRF screening should be firstly performed whenever possible, please refer "Application guide of XRF test for CPSIA total lead content" in SUPP.</p> <p>The Test Report must be from a CPSC approved lab.</p>	M	PASS



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
18001-USA- (V85)
REG CHILDREN'S PRODUCT**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

	Evaluation	Citation / Method	Criteria	Comments	Result	Rating
A R	Lead content (electronic components parts in certain children's electronic devices)	16 CFR 1500.88	<p>The electronic component parts in certain children's electronic devices, listed below, are exempt from the lead content substrate requirements. Note, this only exempts the listed component part and does not exempt the entire product.</p> <p>(1) Lead blended into the glass of cathode ray tubes, electronic components, and fluorescent tubes.</p> <p>(2) Lead used as an alloying element in steel. The maximum amount of lead shall be less than 0.35% by weight (3,500 PPM).</p> <p>(3) Lead used in the manufacture of aluminum. The maximum amount of lead shall be less than 0.4% by weight (4,000 PPM).</p> <p>(4) Lead used in copper-based alloys. The maximum amount of lead shall be less than 4% by weight (40,000 PPM). (5) Lead used in lead-bronze bearing shells and bushings.</p> <p>(6) Lead used in compliant pin connector systems.</p> <p>(7) Lead used in optical and filter glass.</p> <p>(8) Lead oxide in plasma display panels (PDP) and surface conduction electron emitter displays (SED) used in structural elements; notably in the front and rear glass dielectric layer, the bus electrode, the black stripe, the address electrode, the barrier ribs, the seal frit and frit ring, as well as in print pastes.</p> <p>(9) Lead oxide in the glass envelope of Black Light Blue (BLB) lamps.</p> <p>(10) Components of electronic devices that are removable or replaceable, such as battery packs and light bulbs that are inaccessible when the product is assembled in functional form or are otherwise granted an exemption.</p> <p>In lieu of testing, documentation may be submitted in the form of a test report dated within 1 year.</p>	<p>Suppliers must indicate on the test request form any materials (such as stainless steel) which are exempt, to avoid unnecessary testing. Walmart reserves the right to audit supporting documentation at any time.</p> <p>The Test Report must be from a CPSC approved lab.</p>	NA	/
STAR 2 - REGULATORY/COMPLIANCE PHYSICAL AND MECHANICAL						
	Breakaway features	Walmart USA Product Safety and Compliance Standard based on 16 CFR 1250	<p>All products with cords, straps or elastics intended, likely, or foreseeable to be hung around the neck of children and that admit the base of the head probe must have a breakaway feature. Under 18 Months: Shall meet the requirement in section 4.14. Between 18 months and 3 years: Breakaway feature shall open at no greater than 10 pounds force.</p> <p>All products with cords, straps or elastics intended to be hung around the neck of children over 3 years of age must have a breakaway feature. The breakaway feature shall open at no greater than 15 pounds force. The breakaway feature shall be capable of being reattached without altering the characteristics of the attachment.</p> <p>Exemptions: products with restraint systems as required by the regulations (e.g. car seat) or ASTM standards (e.g. booster seat).</p>	Modified to expand age.	NA	/



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
18001-USA- (V85)
REG CHILDREN'S PRODUCT**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

	Evaluation	Citation / Method	Criteria	Comments	Result	Rating
A	Magnet requirement	Walmart USA Product Safety and Compliance Standard based on 16 CFR 1250	All children's products must meet the magnet requirements as outlined in ASTM F963 (as received and after abuse testing).	Modified to expand scope for other products.	NA	/
R	Mechanical hazards	16 CFR 1500.48 & 49	Products intended for children under 8 shall not exhibit non-functional sharp edges or sharp points as determined by 16 CFR 1500.48 / 16 CFR 1500.49.		M	PASS
	Sharp edges or points	Walmart USA Product Safety and Compliance Standard based on 16 CFR 1500.48 & 49	Products shall not exhibit any non-functional sharp edges or sharp points that may cause a hazard in the state the product is received.		M	PASS
R	Small parts	16 CFR 1500.18 (a)(9) / 16 CFR 1501	Products intended for children under 3 shall have no original small parts, or small parts as determined by 16 CFR 1501.		M (TEST BY REQUEST)	PASS
STAR 2 - REGULATORY/COMPLIANCE PACKAGING AND LABELING						
R	Tracking label for all children's products	15 U.S.C. § 2063(a)(5)	<p>Record tracking label in comments section</p> <p>Children's products and packaging must have a tracking label, to the extent practicable. The tracking label must appear permanently on the product and any reusable packaging. The tracking label must also remain on disposable packaging up to the point of sale.</p> <p>The tracking label may include any alpha-numeric content that would , in the event of a recall, allow the manufacturer and the ultimate purchaser of the children's product to determine the product manufacturer, location of production, date of production, and any cohort information or other identifying characteristics such as batch or lot number.</p> <p>Not evaluated at pre-production, but must be provided at production testing.</p>	The abbreviation 'WM' is acceptable per Walmart to identify 'Walmart' as the manufacturer/private labeler.	M	PASS

IMPORTANT NOTE: The information presented under the "Criteria" of this protocol is for information only and does not replace the content of the standard. Details of the requirements should be referred to the original standards. Walmart does not guarantee that the information contained in this protocol is current, or that all requirements are listed. Walmart is committed to providing our customers with safe products that comply with all appropriate regulations and standards. Walmart does not provide legal advice to its suppliers, so where needed, suppliers should seek their own legal counsel on how to comply with all laws applicable to their product. Pricing information please refer to client price list "WMRT-GB-\$LST-GB-PRICE LIST".



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
18001-USA- (V85)
REG CHILDREN'S PRODUCT**

BV Lab Number: **96253120624**
Technician Name: DUY
Test Date: NOVEMBER 08, 2025
Reviewed By/Date: JOHN/ DECEMBER 02, 2025

No. Of Samples Required for Complete Testing		Toys and Hardgoods (case by case for assortments) For over 3 years of age 6 pcs For under 3 years of age 12 pcs
No. Of (Fully Packed) Cartons For Transit Testing:		
No. Of Working Days For Complete Testing:		6

Client Approval:	Heather Webb
	24/Jan/2025
Creation Date:	05/Oct/2016
Last Revision Date:	23/Jan/2025
Pricing Review Date	
Technical Review Date:	

Key

A	Additional Charge For This Test
M	Mandatory Requirement
R	Regulatory

Result Key

C	Claimed
M	Meets
R	Recorded
NM	Does Not Meet
NT	Not Tested
NA	Not Applicable

Rating Key

PASS	Pass
FAIL	Fail



BUREAU
VERITAS

TEST PROTOCOL FOR
18001-USA- (V85)
REG CHILDREN'S PRODUCT

BV Lab Number: 96253120624
Technician Name: DUY
Test Date: NOVEMBER 08, 2025
Reviewed By/Date: JOHN/ DECEMBER 02, 2025

Image Appendix

T-0002 Abuse Test Conditions
w Age.jpg

Testing Parameter	Age (Months)	Abuse Test Conditions
Drop Test	0 to ≤18	4.5 ft. (1.37 m) 10 drops
	>18 to ≤36	3 ft. (0.91 m) 4 drops
	>36 to ≤96	3 ft. (0.91 m) 4 drops
Torque Test	0 to ≤18	2 in - lb. (0.23 N - m)
	>18 to ≤36	3 in - lb. (0.34 N - m)
	>36 to ≤96	4 in - lb. (0.45 N - m)
Tension Test	0 to ≤18	10 lb. (44.5 N)
	>18 to ≤36	15 lb. (66.8 N)
	>36 to ≤96	15 lb. (66.8 N)
Compression Test	0 to ≤18	20 lb. (89 N)
	>18 to ≤36	25 lb. (111.3 N)
	>36 to ≤96	30 lb. (133.5 N)



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
18037-USA- (V28)
REG CHILD CARE ARTICLES**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

Evaluation	Citation / Method	Criteria	Comments	Result	Rating
SCOPE: Applies to Child Care Articles defined as consumer products designed, marketed, or intended to facilitate sleep, relaxation, eating or feeding for children 6 years of age or younger, or to help such children with sucking or teething; this includes bibs and children's pajamas for children under 6 years of age.					
SUPPLEMENTARY PROTOCOL					
A All Products	WMRT-GB-PTCL-10000-USA	Test to All Products Protocol WMRT-GB-PTCL-10000-USA		M	PASS
A Medical Devices	WMRT-HB-PTCL-17600-USA	Test to Supplemental Protocol WMRT-HB-PTCL-17600-USA		NA	/
STAR 2 - REGULATORY/COMPLIANCE RESTRICTED SUBSTANCES					
Volatile N-Nitrosamine Levels in Rubber Nipples on Pacifiers	16 CFR 1250 / ASTM F1313	Rubber Pacifier Nipples shall contain 10 ppb or less of any one nitrosamine or 20ppb of total nitrosamine levels. In lieu of testing, documentation may be submitted in the form of a test report dated within 1 year.	The Test Report must be from a CPSC approved lab.	NA	/
R Phthalates Content	16 CFR 1199 / 16 CFR 1307 / 16 CFR 1308	For accessible components: DEHP, DIBP, BBP, DBP, DPENP, DHEXP, DCHP, DINP: shall not be contained with concentration exceeding 0.1% 1000 ppm each for the product. Requirement also applies to reusable packaging. Accessible plastic components made from polypropylene (PP), polyethylene (PE), acrylonitrile butadiene styrene (ABS), general purpose polystyrene (GPPS), medium-impact polystyrene (MIPS), high-impact polystyrene (HIPS) and super high-impact polystyrene (SHIPS) and their additives as listed in 16 CFR 1308 are exempt from testing. Certain untreated and unfinished engineered wood products (EWPs), specifically particleboard, hardwood plywood, and medium density fiberboard, made from virgin wood or pre-consumer wood waste are exempt from testing. To support testing exemptions, a material declaration through a formal LOG must be provided to the third party lab at time of testing. If no material declaration is made, the third party lab will conduct phthalate testing on all accessible plastic materials and EWPs.	The Test Report must be from a CPSC approved lab. Only accessible components of printed designs, coatings, surface treatments, and elastic should be tested. Examples include the following - Polyvinyl chloride and related polymers, such as polyvinylidene chloride (PVDC) and polyvinyl acetate (PVA) - Soft or flexible plastics, except polyolefins - Soft or flexible rubber, except silicone rubber and natural latex - Foam rubber or foam plastic, such as polyurethane (PU) - Surface coatings, non-slip coatings, finishes, decals, and printed	M	PASS



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
18037-USA- (V28)
REG CHILD CARE ARTICLES**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

	Evaluation	Citation / Method	Criteria	Comments	Result	Rating
			<p>Labs must test using an acceptable CPSC method and the CPSC "Statement of Policy: Testing of Component Parts with Respect to Section 108 of the Consumer Product Safety Improvement Act".</p> <p>In lieu of testing, documentation may be submitted in the form of a test report dated within 1 year.</p>	<p>designs - Adhesives and sealants - Electrical insulation</p>		
STAR 2 - REGULATORY/COMPLIANCE PACKAGING AND LABELING						
A R	Lead - Illinois (All Depts. Except Dept. 7)	410 ILCS 45	<p>Child Care Articles (intended for children 6 years of age or younger) for sale in Illinois with substrate containing between 40 ppm and 100 ppm lead by total weight or surface coating containing between 40 ppm and 90 ppm lead by total weight must display the following warning statement:</p> <p>WARNING—CONTAINS LEAD. MAY BE HARMFUL IF EATEN OR CHEWED.COMPLIES WITH FEDERAL STANDARDS.”</p> <p>In addition, the following formatting criteria are required: 1) the statement shall be located in a prominent place on the item or package such that consumers are likely to see the statement when it is examined under retail conditions; 2) the statement shall be conspicuous and not obscured by other written matter; 3) the statement shall be legible; and 4) the statement shall contrast with typography, layout and color of the other printed matter.</p> <p>A fail must be indicated if the lead substrate of the child care article exceeds 100 ppm.</p> <p>Composite testing using the minimum weight calculation method is acceptable as long as the detection limit is appropriate. For the compositing of three materials, the MDL must be 10 ppm or less. For the compositing of two samples, the MDL must be 15 ppm or less. If the test results obtained are in excess of 32 ppm, a retest of the individual materials that made up the composite material must be performed.</p>	<p>The Test Report must be from a CPSC approved lab.</p> <p>Note: Test Reports must contain the verifiable MDL of the test equipment used.</p>	M	PASS

Walmart does not guarantee that the information contained in this protocol is current, or that all requirements are listed. Walmart is committed to providing our customers with safe products that comply with all appropriate regulations and standards. Walmart does not provide legal advice to its suppliers, so where needed, suppliers should seek their own legal counsel on how to comply with all laws applicable to their product. Pricing information please refer to client price list "WMRT-GB-\$LST-GB-PRICE LIST".



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
18037-USA- (V28)
REG CHILD CARE ARTICLES**

BV Lab Number: **96253120624**
Technician Name: DUY
Test Date: NOVEMBER 08, 2025
Reviewed By/Date: JOHN/ DECEMBER 02, 2025

No. Of Samples Required for Complete Testing	3	
No. Of (Fully Packed) Cartons For Transit Testing:		
No. Of Working Days For Complete Testing:	6	

Client Approval:	Heather Webb
	21/Jan/2025
Creation Date:	17/Sep/2010
Last Revision Date:	20/Jan/2025
Pricing Review Date	
Technical Review Date:	

Key

A	Additional Charge For This Test
M	Mandatory Requirement
R	Regulatory

Result Key

C	Claimed
M	Meets
R	Recorded
NM	Does Not Meet
NT	Not Tested
NA	Not Applicable

Rating Key

PASS	Pass
FAIL	Fail



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
00000-USA- (V75)
ALL PRODUCTS HMZ**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

Evaluation	Citation / Method	Criteria	Comments	Result	Rating
<p>SCOPE: This protocol covers quality/performance requirements for ALL Products for Walmart and Walmart.com in the followings departments: Home: 14, 17, 19, 20, 22, 71 & 74 Hardlines: 03, 09, 10, 11, 12, 16, & 56 Entertainment, Toys and Seasonal: 05, 06, 07, 18, 67, 72 & 87</p> <p>If there are special instructions of the same property assessment in the product specific protocol, then apply the corresponding special instructions in the product specific protocol instead of the test line on this protocol.</p> <p>Walmart does not guarantee that the information contained in this protocol is current or that all requirements are listed. Additional requirements may be required by Product Safety and Compliance, Sustainability or Color. Please contact the assigned 3rd Party Testing Laboratory for advisement on full testing requirements.</p>					
SUPPLEMENTARY PROTOCOL					
A PRIVATE BRAND INSTRUCTION REVIEW	WMRT-HL-09105-USA	For dept 74 the GM PB Instruction Review Protocol will be effective 12/1/24. For all other GM departments do not fail until 10/1/24. GM Private Label Product Instruction Review Protocol not applicable to dept 71.		NA	/
A SUSTAINABILITY CLAIMS	WMRT-GB-00992.03-USA	The sample should be reviewed against the requirement of sustainable claims.		NA	/
A COLOR APPROVAL	WMRT-SL-00000.99-GBL	The sample should be reviewed for the supplemental protocol. D19 products not within the scope of the Color Protocol, however D19 Mainstays brand yarn is within the scope of the Color Protocol per special instructions.		NA	/
A Batteries	WMRT-EL-PTCL-04735-USA	Must test to the Batteries protocol, if applicable.		NA	/
A Food contact products	WMRT-HL-PTCL-06005-USA	The sample should be reviewed against the requirements.		NA	/
A ALL D10 PRODUCTS GENERAL REQUIREMENTS HMZ	WMRT-HL-06502.10-USA	The sample should be reviewed against the requirements.		NA	/



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
00000-USA- (V75)
ALL PRODUCTS HMZ**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

	Evaluation	Citation / Method	Criteria	Comments	Result	Rating
A	ALL ELECTRICAL PRODUCTS PROTOCOL FOR HOME HL ETS DEPARTMENTS	WMRT-EL-PTCL-08446-USA	Electrical devices/products shall also comply to the requirement as specified in the supplemental protocol.		NA	/
A	Performance Label Claims	WMRT-GB-08612-USA	The sample should be reviewed for the supplemental protocol for all GM products.		NA	/
A	Battery operated product	WMRT-TY-PTCL-08001.02-USA	Test to Battery Operated Product Protocol WMRT-TY-PTCL-08001.02-USA.		NA	/
STAR 2 - REGULATORY/COMPLIANCE PACKAGING AND LABELING						
R	Addition of date of manufacture to law label	Visual	For filled products meant to be slept, reclined, or sat upon, supplier must include "Date of Manufacture" on bottom of law label. Date code must be in letter and number format, below the black line under the country of origin. Only Month and Year are required. Font should be in similar height and style as other data listed on law label. Effective Date for Failure: May 1, 2024. **For products that already include "date of manufacture" due to any other WM or Regulatory requirement, you may disregard this test line to avoid duplicity in labeled information. Note: Law Label - WM Technical and Quality Requirement	National Brands are exempt from this requirement	NA	/
STAR 3 - QUALITY/PERFORMANCE						
	Mill ID	Wal-Mart requirement	Preproduction Submissions Only in the following departments: Home: 14, 17, 19, 20, 22, 71, 74 For Preproduction submission, Mill ID is required. If the Mill ID is not listed on the TRF, the sample will put on Hold until the information is provided. Report Mill ID as data only	Note: Cut & sew facilities are not required to register for a Mill ID unless they also have an integrated wet process. Note: Mill ID is required for Tier 2 facilities. These types of Tier 2 facilities include garment and fabric printing and dyeing facilities, weaving / knitting mills, garment laundering facilities and all other wet processing facilities	NA	/
	Higg ID	Wal-Mart requirement	Effective July 1, 2023 Walmart & Walmart.com Map, Preproduction and Production National and Private Brands		NA	/



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
00000-USA- (V75)
ALL PRODUCTS HMZ**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

	Evaluation	Citation / Method	Criteria	Comments	Result	Rating
			<p>Apparel: 23, 24, 25, 26, 29, 30, 31, 33, 34 Home: 14, 17, 20, 22, 71, 74 (Includes Soft Home and Hard Home if there is a textile component)</p> <p>Rate as Data beginning July 1, 2023, if the Higg ID is not listed or provided on the TRF.</p> <p>Beginning October 1, 2023, Rate as Fail, if missing the Higg ID.</p> <p>Note: Does not apply to Hard Home supplier of products that do not contain a textile component.</p>			
	Appropriate Transit Determination	Walmart Requirement per Flow Chart	<p>Applicable to Private and Exclusive Brand items in Home Departments (D14, D17, D19, D20, D22, D71, D74) HARDLINES Departments (3, 9, 10, 11, 12, 16, 56), and ETS Departments (5, 6, 7, 18, 67, 72, 87) for pre-production (if Transit Test report is available during pre-production), production, and annual production testing.</p> <p>NOTE: Soft goods in 7, 9, 10, 11, 14, 16, 17, 18, 19, 20, and 22 such as stuffed animals, camping and sports apparel, sports towels, cleaning towels, safety gloves, napkins, placemats, tablecloths, seat cushions, pillows, fabric curtains, Halloween costumes, plastic cutlery, paper plates/cups, fabric, yarn, towels, liners, bath rugs, sheets, blankets, and bedding are exempt from transit testing requirements.</p> <p>Third party lab must determine the appropriate ISTA testing method per the flow charts shown. Flow charts are located at end of protocol for reference. Record the type of ISTA testing determined appropriate.</p> <p>Note: This will be either ISTA 3A, 3B, 3E (for palletized store features) or 6A-FedEx International. (FedEx Small Parcel Network).</p> <p>Note: Atmospheric conditioning and clamp testing are required portions within all levels of ISTA testing.</p>	Record lab determined ISTA method required by flow chart (See appendix). Note: product dimensions and weight should be recorded for internal use but do not need to appear in the final test report.	NA	/
	Passing Transit Test report	Document review	Applicable to Private and Exclusive Brand items in Home Departments (D14, D17, D19, D20, D22, D71, D74) HARDLINES Departments (3, 9, 10, 11, 12, 16, 56), and ETS Departments (5, 6, 7, 18, 67, 72, 87) for pre-production (if Transit Test	Record supplier provided ISTA testing shown in valid transit test report from supplier.	NA	/



BUREAU VERITAS

TEST PROTOCOL FOR 00000-USA- (V75) ALL PRODUCTS HMZ

BV Lab Number: 96253120624
Technician Name: DUY
Test Date: NOVEMBER 08, 2025
Reviewed By/Date: JOHN/ DECEMBER 02, 2025

Table with 5 columns: Evaluation, Citation / Method, Criteria, Comments, Result, Rating. The Criteria column contains detailed text regarding ISTA transit test reports, including notes on soft goods, supplier requirements, and effective dates for various departments.



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
00000-USA- (V75)
ALL PRODUCTS HMZ**

BV Lab Number: **96253120624**
Technician Name: DUY
Test Date: NOVEMBER 08, 2025
Reviewed By/Date: JOHN/ DECEMBER 02, 2025

Evaluation	Citation / Method	Criteria	Comments	Result	Rating
		If there has been changes with the item or packaging (other than only artwork, labeling, etc.) a new ISTA certified lab transit test report will be required.			
UPC bar codes	Visual	[Not applicable to preproduction] - Retail packaging shall have barcode. - Barcode shall be successfully scanned and number read by scanner shall match human readable number.		M UPC#: 065857170269	PASS
D20 Bath and Shower Sets-UPC label	Wal-Mart requirement	Sets sold in D20 including bath towel sets, shower sets, and rug sets will display the UPC code on the sewn-in care label of the soft textile items included in the set. -This UPC code labeling will aid in the identification of soft bath, rug or soft textile shower items which become separated from their set packaging in store or are returned to stores without packaging -A separate UPC code label is also acceptable if that is more easily executed than adding the UPC code to the care label -Multi-pack washcloths are exempt from this requirement		NA	/
Instructions	Visual	Products which require instructions for use or assembly / installation, shall be provided with complete and correct instructions that can be understood and followed. There shall be no misspelled words. (Note: Never rely solely on a spell checker). Instruction information shall be verified step by step from start to finish to verify all steps are accurate. There shall be no omissions, mislabeling, errors. These shall be identified and recorded in detail as a marked up copy and included in the report. All package contents shall be verified and recorded in the report. Absence or presence of all contents shall be verified again during in-store testing. Any instruction manual steps that are incorrect shall be reported as a fail.		M	PASS
Telephone numbers	Visual	[Phone Number(s) (e.g., on packaging / instructions / product / warranty)]		M	PASS



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
00000-USA- (V75)
ALL PRODUCTS HMZ**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

	Evaluation	Citation / Method	Criteria	Comments	Result	Rating
			<p>All listed phone numbers (if provided not limited to country code of 1) shall be called and verified as working. Call center introduction or menu align with brand or product</p> <p>Note: when the call is being picked up, if no language is in English, do not fail this testing line for non-1 country codes (i.e., outside US and Canada) but include a remark on the report. For phone numbers within US and Canada, there shall be at least an option for English.</p>			
	Website Links / QR code	Actual use	<p>All website links and/or QR codes (if provided) shall be verified as working.</p> <p>National Brand Products: Website links and/or QR codes shall not link to competitor retailer sites.</p> <p>Private Brand Products: Website links and/or QR codes shall not link to competitor retailer sites.</p> <p>Website links and/or QR codes shall link to either the the national brand's site or to a Walmart site.</p> <p>Note: For both National and Private Brand at the time of initial production testing, if the product display page (PDP) is not active but does take the user to a Walmart website, the result is to be noted as PDP not active and not result in a failed rating.</p> <p>If the product display page (PDP) does not display at Annual or Instore then the result would be a fail.</p>		M	PASS
	Parts inventory	Visual check	Actual part (hardware, component, tool, or parts of a set) quantity shall be included and product shall have at least the number of pieces listed.		M	PASS
A	Assembly instructions	Visual	<p>Applicable to the following departments/products: D9 Tents, Tree Stands, Hunting Blinds, Basketball Hoops D10 D16 Grill and Patio Furniture Products including grills, smokers, griddles, outdoor furniture, gazebos and pergolas, fire pits and patio heaters D17 D19 D20- Bath Furniture D71 D74</p>	<p>Refer to WMRT-GB-SUPP-ASSEMBLY SURVEY document.</p> <p>Data only</p>	SEE ASSEMBLY SURVEY	DATA



BUREAU
VERITAS

TEST PROTOCOL FOR
00000-USA- (V75)
ALL PRODUCTS HMZ

BV Lab Number: 96253120624
Technician Name: DUY
Test Date: NOVEMBER 08, 2025
Reviewed By/Date: JOHN/ DECEMBER 02, 2025

Evaluation	Citation / Method	Criteria	Comments	Result	Rating
		<p>Applicable to all of GM 1/1/24</p> <p>Data only. No pass/fail rating is to be assigned. Product and instructions must be evaluated against the Assembly Survey. The survey is intended to identify opportunities for improvement to assembly or instructions and to capture the assembly time required. Any poor ratings shall be noted in the remarks in the final report and images included if necessary. The completed survey is to be included at the end of the report.</p> <p>Assembly is defined as those actions needed to use the product for the first time.</p>			
Mandatory fields	Wal-mart Requirement	<p>For production submission for the following Walmart departments only (does not include Walmart.com)</p> <p>Apparel: 23(41), 24, 25, 26, 27, 28, 29, 30, 21, 32, 33, 34, 35, 36 Home and Seasonal: 14, 17, 19 (44/52), 20, 22, 71 & 74 Hardlines: 03, 09 (45/48/51), 10 (42), 11, 12, & 16 Entertainment: 05 (53/55/73), 06, 72, & 87 Toys and Seasonal: 07 (43), 18, & 67</p> <p>All mandatory fields should be provided by supplier at the time samples are submitted for evaluation as follows:</p> <p>Program Supplier Name Supplier ID Retail Market Department Item Description Importer of Record Factory Name* Factory Number (8 or 9 digits)* Brand Name (Required for Factory Disclosure Determination) Walmart Private Label (Yes or No) Test Type (Phase) Country of Origin Pass / Fail requirement. *Factory Name and Number are required for private and proprietary brands exclusive to Walmart only.</p>		NA	/



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
00000-USA- (V75)
ALL PRODUCTS HMZ**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

Evaluation	Citation / Method	Criteria	Comments	Result	Rating
Required fields	Wal-Mart requirement	<p>For production submission for the following Walmart departments only (does not include Walmart.com) Apparel: 23(41), 24, 25, 26, 27, 28, 29, 30, 21, 32, 33, 34, 35, 36 Home and Seasonal: 14, 17, 19 (44/52), 20, 22, 71 & 74 Hardlines: 03, 09 (45/48/51), 10 (42), 11, 12, & 16 Entertainment: 05 (53/55/73), 06, 72, & 87 Toys and Seasonal: 07 (43), 18, & 67 All required fields should be provided by supplier at the time samples are submitted for evaluation as follows: Supplier Contact Host Vendor Number Item Number Vendor Stock Number UPC Code Retest Indicator Sourcing Office (Import Only) PO Number Previous Report Number (If Retest or Replenishment) Season (Home / Apparel Items) Approved Flammability Number(s) (Home / Apparel Items) Approved Lab Dip Number(s) (Home / Apparel Items) Approved Shade Band Number(s) (Home / Apparel Items) Color (s) (Home / Apparel Items) Mill ID (Home / Apparel Items) Labeled Care Instructions (Home / Apparel Items) Labeled Fiber Content (Home / Apparel Items) Will not impact overall report rating.</p>		NA	/
Product specifications or bill of materials	Wal-Mart requirement	<p>Applicable for PRIVATE BRAND PRODUCTION submissions.</p> <p>For the following Walmart and Walmart.com departments only (does not include Walmart.com LTD Testing for the limited program, Sam's Club, Sams.com submissions.</p> <p>Home: 14, 17, 19, 20, 22, 71 & 74 Hardlines: 03, 09, 10, 11, 12, 16, & 56 Entertainment, Toys and Seasonal: 05, 06, 07, 18, 67, 72 & 87</p>	<p>Sample tag and BOM example are available in CPSDOC as WMRT-GB-SUPP-HOME DEPARTMENTS SAMPLE TAG FOR SPEC REQ and WMRT-GB-SUPP-BILL OF MATERIALS EXAMPLE FORMAT</p> <p>For Walmart D71, refer to the WMRT-GB-SUPP-BILL OF</p>	NA	/



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
00000-USA- (V75)
ALL PRODUCTS HMZ**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

	Evaluation	Citation / Method	Criteria	Comments	Result	Rating
			<p>*NOTE: For Walmart D71, refer to supplemental weight protocol for BOM requirements (WMRT-HL-PTCL-03700-USA-DEPARTMENT 71 FURNITURE WEIGHT SUPPLEMENTAL for BOM).</p> <p>Private label suppliers are required to provide product specifications and/or bill of materials when submitting product for production testing. It is requested that it also be provided for pre-production and supplier only testing.</p> <p>Both a BOM/Product Specification and sample tag are required for Home departments (14,17,19, 20, 22 & 74) only. Vendors can reach out to their department quality manager or Global Sourcing partner to gain access to a BOM/Product Specification template if they do not have an internal version that they can use.</p> <p>The lab will review the BOM/Product Spec to ensure they provide relevant data, such as: Technical drawing with measurements, BOM with defined materials, Product features, Product measurements, labeling such as law tags (as required), date/lot code information defined), and are similar in nature to the WM example. If the lab is questioning if the information provided by the vendor is acceptable they can reach out to their department quality manager for assistance.</p> <p>The documentation submitted (product specification/BOM and sample tag) is to be included at the end of the report.</p>	<p>MATERIALS D71 EXAMPLE FORMAT</p>		
	Dimensions	Dimensional measurement	Report overall dimensions, including thickness if hollow. Other dimensions may need to be reported if critical to product function. Report individual dimensions.	<p>Not pass / fail unless claimed. If claimed, $\pm 5\%$ tolerance. If the product is intended to fit a space, or another product, then both sides of the tolerance applies. Do not fail if the product is outside the tolerance and the discrepancy favors the consumer. Examples: if rope is more than 5% longer than claimed, do not fail.</p>	<p>OVERALL DIMENSION</p> <p>NO CLAIM RECORD:</p> <p>BUNK BED: 79.13"L x 69.38"W x 64.88"H</p> <p>TWIN BED: 79.13"L x 41.75"W x 31.13"H</p>	DATA



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
00000-USA- (V75)
ALL PRODUCTS HMZ**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

Evaluation	Citation / Method	Criteria	Comments	Result	Rating
				FULL BED: 79.13"L x 58"W x 33.75"H	
Weight of product without packaging and instructions	Weight measurements	[Except powder, liquid, paste or other similar viscous consumable products] Report overall product (assembled, if applicable) weight. Do not include packaging or any documents.	Not pass / fail unless claimed. If claimed, it shall be within -5% and +10% tolerance. Do not fail if the product is outside the tolerance and the discrepancy favors the consumer. Example: if product is supposed to be lightweight, and is more than 5% under the claimed weight, do not fail.	NET WEIGHT: NO CLAIM RECORD: BUNK BED: 123 LBS TWIN BED: 44.8 LBS FULL BED: 59.6 LBS	DATA
Net Contents	Dimensional measurements	[Powder, liquid, paste or other similar viscous consumable products] Report net content in weight or volume.	Not pass / fail unless claimed. If claimed, it shall be within -10% tolerance with no upper limit. In addition, do not fail if a larger tolerance is allowed by NIST 133.	NA	/
Thickness of paper	TAPPI T411 om-21 (Mod)	[Bulk paper products] Record thickness	For all GM	NA	/
Grammage of paper and paperboard	TAPPI T410 om-23 (Mod)	[Bulk paper products] Record gsm, and/or basis weight (measure basis weight for products with basis weight claims only)	For all GM	NA	/
Defects and workmanship	Visual examination	[Product, packaging and Instructions] Shall have no discernible surface degradation, including but not limited to crazing, denting, bubbles, cracks, stains, deformations, chips, fractures, waves, shear marks, scratches, scuff marks, indentations, or blisters. Shall have no components missing, malformed, misaligned, and / or fractured.		M	PASS
Surface corrosion	Visual	[Except as designed intentionally for effect] There shall be no sign of corrosion on the product as received .		M	PASS



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
00000-USA- (V75)
ALL PRODUCTS HMZ**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

	Evaluation	Citation / Method	Criteria	Comments	Result	Rating
			Acceptance criteria: Shall meet ASTM D610 / B537 grade 10.			
	Color or finish quality	Visual examination	[Color of External Surface] Color of exterior shall match the color stated on product packaging.		M	PASS
A	Product experience laboratory testing	Actual use	[Private Brand only] Product Experience Testing is required for the following Private Brand products: Ceiling Fans, Drones, Grills, Wireless Chargers, Tents, Mobile Accessories, Furniture requiring assembly, Smart Home, Bath Furniture Gaming Furniture, Patio Furniture, Computer Accessories (keyboards/mice/adapters), Digital Doorknobs / Digital Deadbolt Locks, TV Mounts, Window Blinds Audio (Soundbars/BT Speakers/Headphones), Small Appliances, Projectors/Screens, Toys requiring extensive assembly/connectivity, Connected Devices, Holiday Train Sets, Remote Controls, Holiday Inflatables with blower Streaming, Christmas Tree Stands for Live Trees Antennas, Bikes / Bike Accessories, Tablets Documentation of previous PEL testing must be provided for digital deadbolts / digital door knobs after May 1 2026. Results will be recorded as ""Data Only"" until May 1 2026. For all other products in the list above this will be recorded as data only. Note: A linking letter / letter of guarantee must to be provided if the product ID is not on the PEL report.		NA	/
A	Battery operated - Try me	Actual use / functionality	"Try Me" Feature Operability Product shall meet one of the following requirements: *"Try Me" feature is functional after 500 cycles with supplied batteries OR *Supplier has submitted a self test report which confirms the "Try Me" feature to be functional for at least 500 cycles with supplied batteries. Note 1: Products with a solid on/off switch, which could shut off the product are exempt from this requirement Note 2: For production level testing only. Do not perform at instore		NA	/



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
00000-USA- (V75)
ALL PRODUCTS HMZ**

BV Lab Number: **96253120624**
Technician Name: DUY
Test Date: NOVEMBER 08, 2025
Reviewed By/Date: JOHN/ DECEMBER 02, 2025

Evaluation	Citation / Method	Criteria	Comments	Result	Rating
Actual use - functionality	Actual use / functionality	<p>Shall function as intended as received and after assembly (if necessary).</p> <p>Report details of evaluation (features tested / methods used / materials tested etc.) if not already covered by other tests.</p> <p>If it is not feasible for actual use of the product, the method for simulated usage shall be detailed on the report.</p> <p>Note: additional charge and samples may be required for special features.</p>		M	PASS
Durability	Durability, visual exam	<p>[Adhesive-attached only] [Ex. snaps, hook and loop, snap buckles and/or hooks, cam buckles, etc]</p> <p>Fasteners shall withstand 50 cycles of attaching and detaching and remain serviceable. Fastener components shall not separate from product. Any partial separation shall be considered a FAIL.</p> <p>Include digital image of fasteners after cycling, regardless of test verdict.</p> <p>If product is intended for outdoor use, the test is performed after being exposed to 140F for 4 hours, 0F for 4 hours, and 4 hours water spray at lab ambient temperature for 4 hours.</p>		NA	/
Construction	Visual inspection	<p>[Accessible Components]</p> <p>All accessible components on the product shall be securely fixed as intended and prevented from unintentional turning. If assembly and / or installation is required, before the assessment, first assemble and / or install the product by following the instructions or common general practice (if no instructions are provided).</p>		M	PASS
Magnetic strength	Actual use, visual exam	<p>[For products intended to be suspended by a provided magnet]</p> <p>Products equipped with magnet(s) must support its own weight when attached to a painted 0.11" thick steel plate for 24 hours.</p>		NA	/
Colorfastness to light	AATCC 16.3-20	<p>[Option 3] [Only applicable to D10 products]</p> <p>Grade 4.0 minimum after 40 AFU. Report actual.</p>		NA	/



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
00000-USA- (V75)
ALL PRODUCTS HMZ**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

	Evaluation	Citation / Method	Criteria	Comments	Result	Rating
			Note: Required only for items labeled fade resistant or similar.			
	Resistance to corrosion	Wal-Mart requirement	<p>[For D10 external automotive components only: wiper blade, wheel cover, other exterior automotive acc]</p> <p>Product demonstrates no visible surface corrosion after 7 hours exposure to 95% humidity at 100°F.</p> <p>Effective 9/1/26 D10 External automotive components will be required to meet the 1% salt fog corrosion resistance requirement below.</p>		NA	/
	Resistance to corrosion	ASTM B117-19 modified	<p>[Accessible, metallic components of all outdoor products, excluding disposable products]</p> <p>Demonstrates no visible surface corrosion (grade 9 per ASTM D610 / B537) on metal surfaces after exposure to 1% salt fog at 95°F (35°C) for 24 hours per ASTM B117</p> <p>Exceptions: Uncoated cast iron, uncoated zinc alloys or uncoated brass Exemption: Not applicable to outdoor BBQ tools (tongs, spatulas, etc)</p> <p>Note: If there is a corrosion test based on ASTM B117 on the product specific protocol, perform the test on the product specific protocol instead of this test.</p>		NA	/
	Assembly & Installation	Visual	<p>[Hardware Provided for Installation]</p> <p>Shall not strip, break or lose serviceability when installed in the intended material (e.g. SPF 2 x 4) for installation. Report material used in testing.</p> <p>Note: screws/hardware intended for product assembly are excluded from this requirement.</p>		NA	/
A	Resistance to environmental exposure	Freezer, oven	<p>[Outdoor Products Only]</p> <p>Shall not degrade after one cycle at the below conditions. Visual changes are acceptable, detached components are not acceptable.</p> <p>4 hours at 140°F 4 hours at 0°F</p>		NA	/



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
00000-USA- (V75)
ALL PRODUCTS HMZ**

BV Lab Number: **96253120624**
Technician Name: DUY
Test Date: NOVEMBER 08, 2025
Reviewed By/Date: JOHN/ DECEMBER 02, 2025

	Evaluation	Citation / Method	Criteria	Comments	Result	Rating
			<p>4 hours water spray (refer to UL 588) - For products intended for covered outdoor usage or similar label claim do not perform the water spray test (example: artwork intended for a covered outdoor environment)</p> <p>Note: For products that are UL listed to a specification that requires 1 hour water spray, perform the water spray test for 1 hour in lieu of 4 hours</p>			
A	Color	ASTM D2244-21	<p>[Private brand and by WM request, or as stated on WM product specification only]</p> <p>[Applicable to Entertainment departments 5, 55, 72, 85] CMC color tolerance equation- best agreement between visual assessment and measured color difference.</p> <p>Spectrophotometer Conditions-</p> <p>Specular component included (SPI)</p> <p>Aperture size: SAV, MAV or LAV- recommend to use largest possible based on sample size</p> <p>UV excluded/UV400</p> <p>Observer: 10 Degree</p> <p>Recommended Illuminate- Walmart LED (source: Datacolor or Xrite)</p> <p>Tolerance- dE(CMC) 2:1- recommend a tolerance of 1.5 if the color standard and test specimen are the same or similar material. If not we would recommend a higher tolerance depending on difference in substrates.</p> <p>Color std stated in Private Brand Specification, or provided by WM.</p> <p>Should a failure occur, pictures shall be included of sample and standard</p> <p>All colored components of product visually match the component evaluated via spectrophotometer.</p>		NA	/
A	Moisture content	Weight measurement	<p>[Solid wood] Shall not exceed 12 %. For Walmart D14 / D74, there is an additional minimum moisture content of 6 %.</p>		M	PASS



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
00000-USA- (V75)
ALL PRODUCTS HMZ**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

	Evaluation	Citation / Method	Criteria	Comments	Result	Rating
		before and after oven dry method			(SOLID WOOD: 10.5%)	
A	Moisture content	Moisture meter or oven dry method	<p>[Initial moisture content] [Applicable to Home departments 20 and 22 solid wood items, not applicable to MDF or plywood items]</p> <p>Moisture level of the wood is to be measured at no less than 8 locations on the item. Moisture level of each location is to be between 8 to 12% and there can be no more than 1% variation across all measurements. Products which do not meet this requirement are to be rated as failed.</p> <p>Any item which displays cracking, splitting, failed joints or marred finish following this evaluation is to be rated as failed, regardless of the moisture content findings.</p>		NA	/
A	Moisture content	Moisture meter or oven dry method	<p>[Moisture content after exposure to high humidity] [Applicable to Home departments 20 and 22 solid wood items, not applicable to MDF or plywood items]</p> <p>Product is to be exposed to 95% humidity at 100 deg F for 24 hours. After exposure, the product will be checked for finish damage, as well as swelling, cracking, joint failure or any other visible or structural defect.</p> <p>Moisture level of the wood is to be measured at no less than 8 locations on the item. Moisture level of each location is to be between 8 to 12% and there can be no more than 1% variation across all measurements. Products which do not meet this requirement are to be rated as failed.</p> <p>Any item which displays cracking, splitting, failed joints or marred finish following this evaluation is to be rated as failed, regardless of the moisture content findings.</p>		NA	/
A	Moisture content	Moisture meter or oven dry method	<p>[Moisture content after exposure to drying] [Applicable to Home departments 20 and 22 solid wood items, not applicable to MDF or plywood items]</p> <p>Product is to be exposed to 140 deg F temperature for 24 hours. After exposure, the product will be checked for finish damage, as well as cracking, splitting, joint failure, or any other visible or structural defect.</p> <p>Moisture level of the wood is to be measured at no less than 8 locations across the item. Moisture level of each location is to be between 8 to 12% and there can be no more than 1% variation across all measurements. Products which do not meet this requirement are to be rated as failed.</p>		NA	/



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
00000-USA- (V75)
ALL PRODUCTS HMZ**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

	Evaluation	Citation / Method	Criteria	Comments	Result	Rating
			Any item which displays cracking, splitting, failed joints or marred finish following this evaluation is to be rated as failed, regardless of the moisture content findings.			
A	Fabric count of woven fabric	ASTM D3775-17e1	<p>Effective: S1 2022 Applicable to departments Home: 14,17,19,20,22,71 & 74 and Automotive:10 Tested at MAP stage if applicable. Test at Preproduction stage. If preproduction stage is exempt from testing, test at production stage.</p> <p>Coated Fabrics only Note: Uncoated fabric must be sent in for testing for this test.</p> <p>As specified in Product Specification or Purchase Order ($\pm 5.0\%$) of the total count Report number of ends and number of picks separately and as a total count (Warp + Pick) value. Base on total count for Pass/ fail.</p>		NA	/
A	Yarn size	ASTM D1059-17	<p>Effective: S1 2022 Applicable to departments Home: 14,17,19,20,22,71 & 74 and Automotive:10 Tested at MAP stage if applicable. Test at Preproduction stage. If preproduction stage is exempt from testing, test at production stage.</p> <p>Coated Fabrics only Note: Uncoated fabric must be sent in for testing for this test.</p> <p>As specified in product specification or purchase order ($\pm 10.0\%$).</p>		NA	/
	Aesthetic approval	Wal-Mart requirement	<p>Applicable for D14/D16/D17/D19/D71/D74/D20/D22 Private Label items. Includes both pre-production and production (new). Does not include Walmart.com, Sam's Club or SamsClub.com or Walmart Puerto Rico submissions. Does not include Production Rebuy/Replenishment/Annual Testing types.</p> <p>As of October 26, 2018, Pioneer Woman is a Private Brand which will require aesthetic approval. D74 excludes small electric items such as irons, steamers, vacuums, etc. Applicable submissions must receive approval from the Walmart Product Development Specialist.</p>	Refer to WMRT-GB-SUPP-AESTHETIC APPROVAL FORM to be initiated by lab	NA	/



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
00000-USA- (V75)
ALL PRODUCTS HMZ**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

	Evaluation	Citation / Method	Criteria	Comments	Result	Rating
			While Beautiful is a PB/Exclusive, it will not follow the same aesthetic approval process as PB due to all design/aesthetic approvals being done by an outside source (not Walmart).			
	Bluetooth certification	Visual	<p>If the product uses Bluetooth, it must be listed as a qualified product with the Bluetooth organization. Vendor must provide a copy of declaration ID for validation check. Certificate must match submitted item.</p> <p>Verify the certificate is valid and listed on the following website: http://www.bluetooth.org</p>		NA	/
	Pairing setup reliability	Actual use, visual exam	<p>[Bluetooth Pairing setup reliability]</p> <p>Pair the accessory with a controller Ensure that the initial Pair was successful.</p> <p>Delete accessory and remove the admin pairing using the controller (i.e. phone).</p> <p>This shall be repeated 10 times, with each cycle starting as soon as accessory is discovered broadcasting as an unpaired device.</p> <p>Pairing test is performed within 2 m distance from the product unless other distance is specified by the manufacturer.</p> <p>Shall not exhibit any defect during pairing/un-pairing.</p>		NA	/
	WiFi certification	Visual	<p>If the product claims Wi-Fi 'certified', it must be listed as a Wi-Fi CERTIFIED product with the Wi-Fi Alliance. Vendor to provide a copy of the WiFi certificate for validation check.</p> <p>Verify the certificate is valid and listed on the following website: http://www.wi-fi.org/certification</p> <p>Note: If product is not Wi-Fi certified, report "Not Wi-Fi certified" and rate as DATA.</p>		NA	/
A	Sticker requirement	Wal-Mart requirement	<p>[Ez Peel Regular Sticker or Label Requirement] [Private Brands]</p> <p>Applicable to stickers or peel-off labels which are located on surfaces of the product and are intended to be removed after installation, purchase or assembly.</p>	Refer to image appendix	NA	/



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
00000-USA- (V75)
ALL PRODUCTS HMZ**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

Evaluation	Citation / Method	Criteria	Comments	Result	Rating
		<p>Pass for sticker(s) that can be removed by hand/fingernail pressure and leave no residue or damage to finish. The item is to be passed for this requirement.</p> <p>Fail if removal by hand and fingernail leaves a sticky or visible residue or damages the product finish. Also fail if sticker does not come off product or does not properly adhere to product.</p>			
A Sticker requirement	Wal-Mart requirement	<p>[EZ Peel Tamper Resistant Sticker Requirement] [Private Brands]</p> <p>Applicable to tamper resistant UPC stickers that are located on surfaces of the product and are intended to be removed after installation, purchase or assembly.</p> <p>Pass for sticker(s) that removes in pieces and/or at perforations on the sticker. They may be removed by hand/fingernail pressure and leave no residue or damage to finish. The item is to be passed for this requirement.</p> <p>Fail if when removed by hand the sticker comes off in one piece or the UPC code is not damaged. Also fail if it leaves a sticky or visible residue or damages the product finish and if sticker does not come off product or does not properly adhere to product.</p>	Refer to image appendix	NA	/

Pricing information please refer to client price list "WMRT-GB-\$LST-GB-PRICE LIST"

No. Of Samples Required for Complete Testing	2	
No. Of (Fully Packed) Cartons For Transit Testing:	1	
No. Of Working Days For Complete Testing:	5	

Client Approval:	Ryan Deleon
	14/Oct/2025
Creation Date:	09/Aug/2018
Last Revision Date:	14/Oct/2025
Pricing Review Date	
Technical Review Date:	



**TEST PROTOCOL FOR
00000-USA- (V75)
ALL PRODUCTS HMZ**

BV Lab Number: **96253120624**
Technician Name: DUY
Test Date: NOVEMBER 08, 2025
Reviewed By/Date: JOHN/ DECEMBER 02, 2025

Key

A	Additional Charge For This Test
M	Mandatory Requirement
R	Regulatory

Result Key

C	Claimed
R	Recorded
NT	Not Tested
NM	Does Not Meet
NA	Not Applicable
M	Meets

Rating Key

PASS	Pass
FAIL	Fail



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
00000-USA- (V75)
ALL PRODUCTS HMZ**

BV Lab Number: **96253120624**
Technician Name: DUY
Test Date: NOVEMBER 08, 2025
Reviewed By/Date: JOHN/ DECEMBER 02, 2025

Image Appendix

Sticker requirement
1.png



Sticker requirement
2.png





Transit Testing- Flow Chart.1.png

GM Home: Private and Exclusive Brands


If any of the following conditions are met, your product is considered Ships in Own Container "SIOC" and is **required** to ship in its own case:

- Any item shipped into Walmart as a 1/1 item
- Any item whose sellable unit is in a shippable container
- Any single side of case is greater than 25" in length OR
- The second largest side of case is greater than 20" in length OR
- The smallest side of case is greater than 14" in length OR
- The case weighs more than 30 pounds OR
- Volume is greater than 3.25 cubic feet

NOTE - This page applies to Walmart GM Home: Private and Exclusive Brands items only.

NOTE - Suppliers may obtain a copy of Walmart's instructions for the **required ISTA Test Protocols on Retail Link > Academy > Transportation Channels > Packaging and**

Walmart Home Private Brands Transit Testing - Flow Chart



• If any one of the following conditions are met, item will ship LTL:
>150lbs
>108" in longest dimension (9ft)
>165" in length (L) + girth (2W+2H)
If none of the above are met, package will travel small parcel carrier.

Labeling > Walmart Package Standards/Transit Testing.
NOTE - Certified ISTA Tests will be collect for D14/D71 during Production Testing.
If the proper ISTA testing is not complete, the item will **fail** product testing.

Completed Transit Tests

Once the transit test results are complete, the supplier or global sourcing partner must submit a copy to ISTATesting@wal-mart.com.

Walmart may request a retest for items with rates above department average.

Items **exempt** from testing requirements shown below:

Soft Goods, including but not limited to:

- D14: napkins, placemats, tablecloth/runner
- D17: pillows, fabric curtains
- D19: fabric, yarn
- D20: towels, curtains/liners, bath rug
- D22: sheets, blankets, pillows, bedding/quilt sets



BUREAU VERITAS

TEST PROTOCOL FOR 00000-USA- (V75) ALL PRODUCTS HMZ

BV Lab Number: 96253120624
Technician Name: DUY
Test Date: NOVEMBER 08, 2025
Reviewed By/Date: JOHN/ DECEMBER 02, 2025

Transit Testing – Flow Chart.2.png

Required Package Testing, cont...

GM Entertainment, Toys and Seasonal (ETS): Private and Exclusive Brands


If any of the following conditions are met, your product is considered Ships in Own Container "SIOC" and is **required** to ship in its own case:

- Any item shipped into Walmart as a 1/1 item
- Any item whose sellable unit is in a shippable container
- Any single side of case is greater than 25" in length OR
- The second largest side of case is greater than 20" in length OR
- The smallest side of case is greater than 14" in length OR
- The case weighs more than 30 pounds OR
- Volume is greater than 3.25 cubic feet

NOTE - This page applies to Walmart GM ETS: Private and Exclusive Brands items only.

Large-screen TVs are required to pass a Walmart-specific TV test protocol.

Walmart ETS Private Brands Transit Testing – Flow Chart



• If any one of the following conditions are met, item will ship LTL:
>150lbs
>108" in longest dimension (9ft)
>165" in length (L) + girth (2W+2H)
If none of the above are met, package will travel small parcel carrier.

NOTE - ISTA testing once completed should be sent to ISTATesting@wal-mart.com.

NOTE - Suppliers may obtain a copy of Walmart's instructions for the required ISTA Test Protocols on Retail Link > Academy > Transportation Channels > Packaging and Labeling > Walmart Package Standards/Transit Testing.

Completed Transit Tests

Once the transit test results are complete, the supplier or global sourcing partner must submit a copy to ISTATesting@wal-mart.com.

Walmart may request a retest for items with rates above department average.

Items exempt from testing requirements shown below:

- Soft Goods, including but not limited to:
- D7: stuffed animals
 - D18: Halloween Costumes, Cutlery, Paper plates/cups



BUREAU VERITAS

TEST PROTOCOL FOR 00000-USA- (V75) ALL PRODUCTS HMZ

BV Lab Number: 96253120624
Technician Name: DUY
Test Date: NOVEMBER 08, 2025
Reviewed By/Date: JOHN/ DECEMBER 02, 2025

Transit Testing – Flow Chart.4.png

Required Package Testing, cont...

GM Hardlines: Private and Exclusive Brands

If any of the following conditions are met, your product is considered Ships in Own Container "SIOC" and is **required** to ship in its own case:

- Any item shipped into Walmart as a 1/1 item
- Any item whose sellable unit is in a shippable container
- Any single side of case is greater than 25" in length OR
- The second largest side of case is greater than 20" in length OR
- The smallest side of case is greater than 14" in length OR
- The case weighs more than 30 pounds OR
- Volume is greater than 3.25 cubic feet

NOTE - This page applies to Walmart GM Hardlines: Private and Exclusive Brands items only.

NOTE - ISTA testing once completed should be sent to ISTATesting@wal-mart.com.

NOTE - Suppliers may obtain a copy of these **required Walmart ISTA Test Protocols** on Retail Link > Academy > Transportation Channels > Packaging and Labeling > Walmart Package Standards/Transit Testing.

Completed Transit Tests

Once the transit test results are complete, the supplier or global sourcing partner must submit a copy to ISTATesting@wal-mart.com.


Walmart may request a retest for items with rates above department average.

Items **exempt** from testing requirements shown below:

Soft Goods, including but not limited to:

- D9: Camping and sports clothing apparel, sports towels
- D10: Cleaning towels
- D11: Safety gloves
- D16: Seat cushions, throw pillows

Walmart Hardlines Private Brands Transit Testing – Flow Chart



- If any one of the following conditions are met, item will ship LTL:
>150lbs
>108" in longest dimension (9ft)
>165" in length (L) + girth (2W+2H)
If none of the above are met, package will travel small parcel carrier.



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
10000-USA- (V215)
REG ALL PRODUCTS**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

Evaluation	Citation / Method	Criteria	Comments	Result	Rating
SCOPE: Applies to all Products.					
NOTE: 1. Additional requirements may apply to this product. Please refer to the US Product Safety & Compliance Manual for details. (Retail Link --> Apps --> Product Safety and Compliance Library) 2. Walmart does not guarantee that the information contained in this protocol is current, or that all requirements are listed. Walmart is committed to providing our customers with safe products that comply with all appropriate regulations and standards. Walmart does not provide legal advice to its suppliers, so where needed, suppliers should seek their own legal counsel on how to comply with all laws applicable to their product. 3. All Products: Walmart USA Product Safety and Compliance Standard: In addition to the requirements noted in this and any other Walmart protocol, unless otherwise exempted in writing, products must comply with all applicable local, state, and federal rules, bans, standards, regulations, and applicable industry consensus standards. The laws and citations listed in Walmart protocols are subject to change – Suppliers are required to ensure Products are in compliance with the most current version of applicable laws, regulations, bans, rules, and standards.					
SUPPLEMENTARY PROTOCOL					
A REG EPA PESTICIDE	WMRT-GB- PTCL-16898-USA	Test to EPA Pesticide Protocol WMRT-GB-PTCL-16898-USA		NA	/
A Banned Products	WMRT-GB-PTCL-10004-USA	Test to all Banned Products Protocol WMRT-GB-PTCL-10004-USA		NA	/
A Sporting Goods	WMRT-HL-PTCL-14970.08-USA	Test to Sporting Goods - Sling Shots, BB Guns, Pellet Guns, Air Guns, Pepper Spray, and Tear Gas Protocol WMRT-HL-PTCL-14970.08-USA		NA	/
STAR 2 - REGULATORY/COMPLIANCE REGULATIONS					
A Magnets R	16 CFR 1262	<p>Covered products must comply with the most current version of the regulation.</p> <p>Covered products include products that contain one or more loose or separable magnets, and that are designed, marketed, or intended to be used for entertainment, jewelry (including children's jewelry), mental stimulation, stress relief, or a combination of these purposes, but does not include products sold and/or distributed solely to school educators, researchers, professionals, and/or commercial or industrial users exclusively for educational, research, professional, commercial, and/or industrial purposes.</p>		NA	/
A Connected R devices	Walmart USA Product Safety and Compliance Standard based on: California Cal Civ Code § 1798.91.04 - Cal Civ	As of January 1, 2020, all products that connect to the Internet, directly or indirectly, and that are assigned an Internet Protocol address, Bluetooth address, or another address or number that identifies the connected device for the purpose of making a short-range wireless connection to another device, must be equipped with	Lab must fail this test line if supplier fails to complete the certification form. Refer to WMRT-GB-SUPP-CONNECTED DEVICES CERTIFICATION form.	NA	/



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
10000-USA- (V215)
REG ALL PRODUCTS**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

Evaluation	Citation / Method	Criteria	Comments	Result	Rating
	Code § 1798.91.06 Oregon ORS § 646A.813	<p>a reasonable security feature or features to comply with California and Oregon's requirements for connected devices.</p> <p>Suppliers of covered products must submit a completed Connected Devices Certification Form at the time of production testing.</p>			
A Connected R devices	Walmart USA Product Safety and Compliance Standard based on: California Cal Civ Code § 1798.91.04 - Cal Civ Code § 1798.91.06 Oregon ORS § 646A.813	<p>As of January 1, 2020, all products that connect to the Internet, directly or indirectly, and that are assigned an Internet Protocol address, Bluetooth address, or another address or number that identifies the connected device for the purpose of making a short-range wireless connection to another device, must be equipped with a reasonable security feature or features to comply with California and Oregon's requirements for connected devices.</p> <p>Covered products equipped with a means for authentication outside a local area network shall have either:</p> <ol style="list-style-type: none"> 1. A preprogrammed password unique to each device manufactured, or 2. The device contains a security feature that requires a user to generate a new means of authentication before access is granted to the device for the first time. 		NA	/
A Fiber products R	Textile Fiber Products Identification Act (15 U.S.C. §§ 70-70k)	At the time of production testing, suppliers of covered products must have a copy of a continuing guarantee on-file with the lab, provide a continuing guaranty (see form), or provide evidence of having a Textile Fiber Products Identification Act continuing guaranty filed with the FTC.	<p>Lab must fail this test line if supplier fails to submit the required documentation. The document required under this test line DOES NOT replace the need for any other product testing required under Walmart's Product Safety and Compliance Program.</p> <p>Refer to CONTINUING GUARANTY FOR PRODUCTS SUBJECT TO THE TEXTILE FIBER PRODUCTS IDENTIFICATION ACT.</p> <p>Only one identifying number is needed on the form, either UPC</p>	NA	/



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
10000-USA- (V215)
REG ALL PRODUCTS**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

	Evaluation	Citation / Method	Criteria	Comments	Result	Rating
				<p>or Item Number will be acceptable.</p> <p>Refer to WMRT-GB-SUPP-CONTINUING GUARANTY TEXTILE FIBER PRODUCTS form.</p>		
A R	Wool products	Wool Products Labeling Act (15 U.S.C. §§ 68-68j)	At the time of production testing, suppliers of covered products must have a copy of an item specific continuing guarantee on-file with the lab, provide an item specific continuing guaranty (see form), or provide evidence of having a Wool Products Labeling Act continuing guaranty filed with the FTC.	<p>Lab must fail this test line if supplier fails to submit the required documentation. The document required under this test line DOES NOT replace the need for any other product testing required under Walmart's Product Safety and Compliance Program.</p> <p>Only one identifying number is needed on the form, either UPC or Item Number will be acceptable.</p> <p>Refer to WMRT-GB-SUPP-CONTINUING GUARANTY WOOL AND FUR PRODUCTS form.</p>	NA	/
A R	Reese's Law - Poison Prevention Packaging Standards	15 USC § 2056e (notes) / 16 CFR 1700.15	<p>Any button cell or coin battery, manufactured after February 12, 2023, sold separately or included separately with a consumer product sold must be packaged in accordance with the Poison Prevention Packaging standards.</p> <p>In lieu of testing, documentation may be submitted in the form of a passing test report valid for the lifetime of the product packaging so long as no change in material, design and composition of the packaging.</p>	<p>Button cell or coin batteries able to show proof of compliance with the marking and packaging provisions of the ANSI Safety Standard for Portable Lithium Primary Cells and Batteries (ANSI C18.3M) are exempt from this requirement.</p> <p>The test report may be accepted from a Non-CPSC accredited lab.</p>	NA	/
A R	Wood Heaters, Central Heaters	40 CFR 60.530 - 60.539(b)	Covered products must comply with the most current regulation.		NA	/



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
10000-USA- (V215)
REG ALL PRODUCTS**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

	Evaluation	Citation / Method	Criteria	Comments	Result	Rating
			Covered products include, furnaces, boilers, stove and/or apparatuses used in the process of burning wood fuel for the primary purpose of producing heat or power.			
A R	Vermont-Wood Fuel Burning Equipment	12-001 Code Vt. R. 12-031-001-X - CHAPTER 5	Wood Fuel Burning Equipment must be comply with this regulation. Covered products include, furnaces , boilers, stove and/or apparatuses used in the process of burning wood fuel for the primary purpose of producing heat or power. In lieu of testing, documentation may be submitted in the form of a Supplier Declaration of Compliance dated within 1 year.		NA	/
A R	Restrictions of three-dimensional sexual devices	Code of Ala. § 13A-12-200.2; O.C.G.A. § 16-12-80; Miss. Code Ann. § 97-29-105; Va. Code Ann. § 18.2-374	A three-dimensional sexual device designed or marketed as primarily useful for the stimulation of human genital organs must not be offered for sale in the states of Alabama, Georgia, Mississippi, or Virginia.		NA	/
R	Restrictions of Radar detectors in VA and DC	VA: § 46.2-1079 / DC: D.C. Mun. Regs. tit. 18 § 736	Covered products cannot be sold in VA and DC.		NA	/
STAR 2 - REGULATORY/COMPLIANCE RESTRICTED SUBSTANCES						
R	CFCs and HCFCs	Clean Air Act Title VI Sec.602 / 40 CFR 82	All aerosol products and pressurized containers, shall not contain any Class 1 or Class II ozone depleting CFCs or HCFCs as outlined in the Clean Air Act. In lieu of testing, documentation may be submitted in the form of either a test report or a Letter of Guarantee dated within 1 year.	The test report may be accepted from a Non-CPSC accredited lab.	NA	/
	Mercury - total content (substrate and surface coating)	Walmart USA Product Safety and Compliance Standard based on various state Laws	Products that are silvery liquids with similar properties to mercury shall contain no intentionally added mercury (detection limit of 5 PPM). In lieu of testing, documentation may be submitted in the form of a test report dated within 1 year.	The test shall not be applicable to surface coating. The Test Report must be from a CPSC accepted laboratory.	NA	/
	Natural products - seeds	Walmart USA Product Safety and Compliance Standard based on USDA	Products made with natural materials such as straw and/or pinecones shall contain no seeds. Test by inspection and shaking the sample.		NA	/



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
10000-USA- (V215)
REG ALL PRODUCTS**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

	Evaluation	Citation / Method	Criteria	Comments	Result	Rating
A	Maine, New York, Oregon, Vermont, Washington Chemicals of High Concern to Children	Walmart USA Product Safety and Compliance Standard based on Maine 38 MRSA Ch 16-D, ss 1691-1699-B / New York NY CLS ECL ss 37-905 & ss 37-907 / Oregon 17 ORS Ch 786 / Vermont 18 VSA Ch 38A, ss 1771-1779 / Washington RCW 70A.430.060-70A.430.080	Under current state law, suppliers of children's products must report to the states of Maine, New York, Oregon, Washington, and Vermont if their product contains reportable chemicals beyond the specified limit. All suppliers must submit the completed Compliance Certification Form for CHCC Reporting back to the test lab for each product at the time of production or annual testing.	Lab must fail this test line if supplier fails to complete the certification form. WMRT-GB-SUPP-CHCC CERTIFICATION FORM.	M (THE COMPLETED COMPLIANCE FORM FOR CHCC WAS PROVIDED DATE: JULY 02, 2025)	PASS
A R	Flame retardant chemicals	Cal Bus & Prof Code § 19101 / 6 Del. C. Subtit. II, CH. 25G / D.C. Code § 8-108.02a / HI HB 2013 / 410 ILCS 48 / 38 M.R.S. § 1609-A / Md. Code, Health-Gen. § 24-306 / Md. Code, Health-Gen. § 24-306.1 / ALM GL ch. 21A, § 28 / MCL § 324, Act 451 / Minn. Stat. 2021 § 325F.071 / Nev. Rev. Stat. Ann. §597.7139 / N.H. Rev. Stat. § 359-Q:2 / NY Env. Conserv. L. § 37-703 / NY Env. Conserv. L. § 37-705 / NY Env. Conserv. L. § 37-1003 / NY Env. Conserv. L § 37-1007 / ORS § 453.085(16) / R.I. Gen. Laws § 23-26-3.1 / R.I. Gen. Laws § 23-75-3 / 9 V.S.A. §	Covered products must comply with the most recent version of the regulations. Covered products include: - all products(DC, HI, IL, MI, and OR); - children's products(CA, DE, MD, MA, MN, NV, NY, RI, VT, and WA); - juvenile products(MD); - mattresses(CA, DE, MD, MN, NV, and NY); - upholstered furniture(CA, DE, ME, MD, MA, MN, NV, NH, NY, RI, VT, and WA); - bedding(MA); - carpeting(MA); - window treatments(MA); - textiles(MN, NV); - electric or electronic displays(NY); and - recreational products made from polyurethane foam(WA). Suppliers of covered products must submit a completed Flame Retardant Certification at the time of Production Testing.]	Refer to WMRT-GB-SUPP-FLAME RETARDANT CERTIFICATION FORM.	M (FLAME RETARDANT CERTIFICATION FORM WAS PROVIDED DATE: NOVEMBER 05, 2025)	PASS



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
10000-USA- (V215)
REG ALL PRODUCTS**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

	Evaluation	Citation / Method	Criteria	Comments	Result	Rating
		2973 / 9 V.S.A. § 2974 / RCW 70A.430.030 / WAC Ch. 173-337				
A	Hemp and Hemp Derived Products	Walmart USA Product Safety and Compliance Standard based on 7 CFR § 990.1	<p>The weight of the total content must be undetectable of any of the major/ commonly found cannabinoids which includes:</p> <p>CBD, CBDA, CBC, CBDV, CBG, CBGA, CBN, THCV, THCA, 8-THC, 9-THC</p> <p>(Lower reporting limits are 100 ppm for CBD and 200 ppm for the other listed cannabinoids)</p> <p>In lieu of testing, documentation may be submitted in the form of a test report dated within 1 year.</p> <p>Client requirement</p>	<p>Any detectable trace of any of the major/commonly found cannabinoids should reflect a "FAIL" and the Walmart PSC team should be notified of the results of the testing.</p> <p>Products receiving a "FAIL" for this reason are NOT permitted an automatic retest.</p> <p>The test report may be accepted from a Non-CPSC accredited lab.</p>	NA	/
A R	Lead - Home Improvement Items	Proposition 65	<p>Home improvement items (solder wire, ingots, etc.) containing lead at a detectable level (10 PPM) must have a Proposition 65 warning present.</p> <p>In lieu of testing, documentation may be submitted in the form of a test report dated within 1 year.</p> <p>NOTE: - If the product bears an appropriate Proposition 65 warning label, it shall not be tested for this requirement.</p> <p>Client requirement</p>	The test report may be accepted from a Non-CPSC accredited lab.	NA	/
A R	HFCs End-Use and other prohibited substances (Aerosol Propellants, Foams, and Household (Consumer) Refrigeration): California,	MD- COMAR 26.11.33; CO-5 CCR 1001-26; VT-12-003 Code Vt. R. 12-031-003-X - Chap.38; CA-Cal Health & Saf Code § 39734; MA-310 CMR 7.76; N.J- N.J. Stat. § 26:2C-61; NY- 6 NYCRR Part 494; RI- 250-RICR-120-05-53;	<p>Covered products shall comply with applicable HFC and refrigerants requirements. If the product includes a refrigerant (HFCs) prohibited in any of the listed states, the product must be restricted from that state.</p> <p>In lieu of testing, documentation may be submitted in the form of a Letter of Guarantee dated within 1 year.</p>	<p>Please note in the test report the specific regulation failure(s) and state(s) (if applicable).</p> <p>Letter of Guarantee must state that:Product contains no HFC OR that the Product is compliant in named states.</p>	NA	/



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
10000-USA- (V215)
REG ALL PRODUCTS**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

	Evaluation	Citation / Method	Criteria	Comments	Result	Rating
	Colorado, Maine, Maryland, Massachusetts, New Jersey, New York, Rhode Island, Vermont, Washington	WA- WAC173-443; ME-38 MRSA §1612				
A R	Perfluoroalkyl and polyfluoroalkyl substances (PFAS)-Doc	CA-Cal. Health & Saf. Code § 108945 to 108946 / CA-Cal. Health & Saf. Code § 109000 / CA-Cal. Health & Saf. Code § 108981.5 / CA-Cal. Health & Saf. Code § 108971 / CA-Cal. Health & Saf. Code § 25258.3 / CO-Colo. Rev. Stat. § 25-15-604 / CT-Conn. Gen. Stat. § 22a-225i / CT-CT SB 292 / HI-HRS § 321- 602 / MD-Md. Code, Envir. § 6-1604.1 / MD-Md. Environment Code Ann. § 9-1902 / MD-Md. Health- General § 21-259.2 / MD-Md. Code Ann. § 6-16A-01-05 / MD-Md. Code, Envir. § 6-16A- 03 / ME-MRSA 38 §1614(5) / MN-Minn. Stat. § 116.943 (5) / MN-Minn. Stat. § 325F.075 / NH-N.H. Rev. Stat. § 154:8-c / NY-NY CLS ECL § 37- 0121 / NY-NY CLS	CA, CO, CT, HI, MD, ME, MN, NH, NY, RI, OR, VT & WA Requirement PFAS chemicals are prohibited if intentionally added for below products: CA, CO, & MN - Juvenile Products ; CA, CO, CT, HI, MD, MN, NY, OR, RI, VT & WA - Food Packaging and Foodware Containers - Made of Paper, Paperboard, or derived from Plant Fibers; Foodware Containers ; CO, MD, ME, MN, VT, WA - Carpets, rugs, & fabric treatments ; WA - Aftermarket Stain and Water Resistance Treatments ; MN, VT - Ski Wax ; CO - Gas and oil products ; MD - Playground Surfacing Materials ; CT - Soil Amendments ; NY - Apparel ; CA - Textile Articles ; CA, CO, MD, MN, WA - Cosmetics ; CO, MN - Upholstered Furniture and Indoor Textile Furnishings ; CA & MN - Menstruation Products ; MN - Dental Floss ; MN - Cleaning Products (including air care products); MN - Cookware ; NH - Firefighting station wear CA Textile Articles and Juvenile Products containing regulated PFAS are prohibited if at or above 100 ppm of total organic fluorine. In lieu of testing, WMRT-GB-SUPP PFAS SUPPLIER STATEMENT OF DECLARATION FORM will be accepted	Refer to WMRT-GB-SUPP-PFAS SUPPLIER STATEMENT OF DECLARATION FORM.	M (PFAS SUPPLIER STATEMENT OF DECLARATION FORM WAS PROVIDED DATE: JULY 02, 2025)	PASS



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
10000-USA- (V215)
REG ALL PRODUCTS**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

Evaluation	Citation / Method	Criteria	Comments	Result	Rating
	ECL § 37-0209 / OR-ORS § 459.474 / RI-R.I. Gen. Laws 23-18.13-4 / VT-18 V.S.A. § 1672 / VT-18 V.S.A. § 1682-1683 / VT-18 V.S.A. § 1692 / WA-RCW 70A.222.070 / WA-WA HB 1047 / WA-WAC 173-337	Please note in the test report the specific regulation failure(s) and state(s) (if applicable).			
A Total lead and cadmium in consumer products	Minn. Stat. § 325E.3892	<p>A person may not sale or offer for sale any of the following products containing lead at more than 90 ppm (.009%) or containing cadmium at more than 75 ppm (.0075%):</p> <ul style="list-style-type: none"> jewelry; toys; cosmetics and personal care products; puzzles, board games, card games, and similar games; play sets and play structures; outdoor games; school supplies; except ink pens and mechanical pencils; pots and pans; cups, bowls, and other food containers; craft supplies and jewelry-making supplies; chalk, crayons, paints, and other art supplies except professional artist materials, including but not limited to oil-based paints, water-based paints, pastels, pigments, ceramic glazes, markers, and encaustics; fidget spinners; costumes and costume accessories; children's and seasonal party supplies; keys, key chains, and key rings; and clothing, footwear, headwear, and accessories. <p>"Pastels" means a crayon composed of powdered pigments bonded with gum or resin.</p> <p>Note: - Documentation must be submitted in the form of a Supplier Certification dated within 1 year at the time of production or annual testing.</p>	<p>Products exempt from regulation: Covered products containing lead or cadmium, or both, when regulation is preempted by federal law. Products that contain lead only in solder used in internal components if the product is not sold or held for sale in Minnesota after July 1, 2028 and the manufacturer of the product submits biennial reports to the commissioner of the pollution control agency that explains why lead cannot be removed from the product. Keys that contain lead. Pots and pans, if the pot or pan is made of cast iron or steel, has cadmium contained only in a vitreous enamel that does not come into contact with food and does not contain lead in concentration greater than the 90 ppm (.009%). Signing Compliance Certification Form serves as proof of compliance for all of the above exemption requirements.</p> <p>Refer to WMRT-GB-SUPP-MN LEAD AND CADMIUM</p>	NA	/



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
10000-USA- (V215)
REG ALL PRODUCTS**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

Evaluation	Citation / Method	Criteria	Comments	Result	Rating
		- Products containing lead or cadmium, or both, are exempt from this requirement if they are already required to meet a federal lead or cadmium standard.	SUPPLIER COMPLIANCE CERTIFICATION FORM		
STAR 2 - REGULATORY/COMPLIANCE PHYSICAL AND MECHANICAL					
R Fidget spinners	Wal-Mart requirement	All products identified as "Fidget Spinners" are to be treated as toys and tested to the applicable sections of ASTM F963 standard, regardless of age grade provided on the product or package.		NA	/
Age grading	Walmart USA Product Safety and Compliance Standard based on CPSC Age Determination Guidelines and ASTM F963 Annex A1 Age Grading Guidelines	All products shall be tested according to either the appropriate age grade or the labeled age grade if it is more stringent. In the event the sample is not age labeled, the test lab shall determine the appropriate age grade and test accordingly.		LABEL AGE GRADE: NOT PRESENT APPROPRIATE AND TESTED AGE GRADE: UPPER BUNK: CHILDREN PRODUCT, OVER 6 YEARS OF AGE LOWER BUNK/ TWIN BED/ FULL BED: CHILDREN PRODUCT, OVER 3 YEARS OF AGE	DATA
R U.S. Department of Energy Efficiency Requirements	10 CFR 429 and 10 CFR 430 and 10 CFR 431	Covered products shall comply with applicable DOE energy efficiency requirements. In lieu of testing, documentation may be submitted in the form of either a test report or a Verification via DOE compliance certification database in website Valid for life of the product model so long as no change in materials, components, material/component part supplier, design, factory, or manufacturing process Note: All test reports submitted must be in English. DOE will not accept reports in any other language. Record report number, DOE covered product, and Date of report.	The test report may be accepted from a Non-CPSC accredited lab.	NA	/



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
10000-USA- (V215)
REG ALL PRODUCTS**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

	Evaluation	Citation / Method	Criteria	Comments	Result	Rating
	Feathers - use restrictions (as applicable)	Walmart USA Product Safety and Compliance Standard	Exposed natural feathers are not allowed on items worn or intended to be wrapped or secured on the body and cannot be quickly withdrawn by the wearer.	CPSD-GB-01057-MTHD Natural feathers are acceptable on items that are not worn on the body or can be easily withdrawn by the wearer. Unexposed natural feathers are allowed on adult and children's apparel. When natural feathers are used, vendor shall submit documentation which specify the country of origin and type of bird the feathers are come from.	NA	/
A R	Flammability (contact adhesives)	16 CFR 1302	Extremely Flammable Contact Adhesives are banned. In lieu of testing, documentation may be submitted in the form of a test report dated within 1 year.	The Test Report must be from a CPSC accepted laboratory.	NA	/
R	Flammability - solids	Walmart USA Product Safety and Compliance standard based on 16 CFR 1500.44 and 16 CFR 1500.3(c)(6)(vi)	All products with an ignition source or intended to be used near an ignition source shall not exceed the maximum allowable limit of no greater than 0.1 inches per second, unless appropriately labeled. In lieu of testing, documentation may be submitted in the form of a test report dated within 1 year.	The Test Report must be from a CPSC accepted laboratory.	M (TEST BY REQUEST)	PASS
R	Flammability - pressurized container	16 CFR 1500.3(c)(6)(viii)	Self-pressurized container should not be regarded as flammable per 16 CFR 1500.3 (c)(6)(viii) and 1500.45. In lieu of testing, documentation may be submitted in the form of a test report dated within 1 year.	The Test Report must be from a CPSC accepted laboratory.	NA	/
	Stuffing cleanliness	Walmart USA Product Safety and Compliance Standard based on various state Laws	Loose fillers shall be free of objectionable matter and contamination such as animal infestation, splinters, metal chips, etc.	CPSD-GB-01057-MTHD	NA	/
A R	Reese's Law - Safety Standard for Consumer Products	16 CFR § 1263.3	Consumer Products containing or designed to use batteries that present an ingestion hazard must comply with the most current version of the regulation.	Toy products able to show proof of compliance with the battery accessibility and labeling requirements of 16 CFR 1250	NA	/



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
10000-USA- (V215)
REG ALL PRODUCTS**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

	Evaluation	Citation / Method	Criteria	Comments	Result	Rating
	Containing or Designed to Use Batteries that Present Ingestion Hazards			are exempt from this requirement. Zinc-Air batteries are exempt from this requirement.		
R	Energy and Water Efficiency Regulations	<p>Arizona: Ariz. Rev. Stat. § 44-1375 et seq; California: Cal. Code Regs. tit. 20 § 1601 et seq; Colorado: Colo. Rev. Stat. § 6-7.5-101 et seq; Connecticut: Agencies Regs. § 16a-48 et seq; District of Columbia: D.C. Code § 8-1771 et seq; Georgia: Title 8, Chap 2, Article 1, Part 1, § 8-2-1 et seq; Hawaii: Revised Status, Title 12, 196-81 et seq; Maine: Me. Stat. tit. 38 § 1616; / DEP 06-096, Chapter 180 Appliance Efficiency Standards Maryland: Md. Code, State Gov't § 9-2006 and Md. Code Regs. 14.26.03 et seq; Nevada: Nev. Rev. Stat. § 701 et seq; New Hampshire: N.H. Rev. Stat. § 339-G:1 et seq; New Jersey: N.J. Stat. § 52:27D-141.20 et seq; / New York: Chapter 17-A, Article 16 and Chapter 43-B, Article 15. Title 3.</p>	<p>Covered products shall comply with applicable energy efficiency requirements</p> <p>In lieu of testing, documentation may be submitted in the form of a test report valid for the life of the product model so long as no change in materials, components, material/component part supplier, design, factory or manufacturing process.</p> <p>Please note in the test report the specific regulation failure(s) and state(s) (if applicable).</p>	The test report may be accepted from a Non-CPSC accredited lab.	NA	/



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
10000-USA- (V215)
REG ALL PRODUCTS**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

	Evaluation	Citation / Method	Criteria	Comments	Result	Rating
		Section 15-0314; NYCRR, Title 21, Part 509 Appliance and Equipment Efficiency standards; Oregon: ORS Vol 13.Title 36A.§ 469 et seq; Rhode Island: R.I. Gen. Laws § 39-27.1-1 et seq; Texas: 30 Tex. Admin. Code § 290.252 et seq; Vermont: 9 V.S.A. § 2791 et seq; Washington. Rev. Code § 19.260.010 et seq				
R	CA and OR Consumer Right to Repair Act	CA Public Resource Code Section 42488 (SB244), ORS 180.095 (SB1596)	Manufacturers must comply with the CA and OR Right to Repair requirements. Suppliers shall provide a Declaration indicating they are compliant. Please note in the test report the specific regulation failure(s) and state(s) (if applicable).	Refer to WMRT-GB-SUPP-DECLARATION FOR RIGHT TO REPAIR.	NA	/
STAR 2 - REGULATORY/COMPLIANCE PACKAGING AND LABELING						
A R	Applicability of the treated articles exemption to antimicrobial pesticides	40 CFR 152.25(a)	[As applicable – Products (“articles”) that make antimicrobial claims (antibacterial, antifungal, odor control, or similar claims) on labeling on online content] (Does not apply to EPA registered products or FDA regulated products) Pass if product meets below requirements. If product is reported as FAIL, the product is subject for review under the Pesticide Protocol. 1) Antimicrobial claims must have appropriate qualifying statements that clearly state applied treatment is intended to protect the article itself and not the user (no public health claims). Claims must comport with Treated Articles Exemption to Antimicrobial Pesticides (EPA PR Notice 2000-1): https://www.epa.gov/sites/production/files/2014-04/documents/pr2000-1.pdf 2) The incorporated antimicrobial pesticide must be registered with EPA for use in or on the article. Obtain EPA registered product name		NA	/



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
10000-USA- (V215)
REG ALL PRODUCTS**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

	Evaluation	Citation / Method	Criteria	Comments	Result	Rating
			<p>and registration number or EPA approved label. Verify claims and site uses are found on label.</p> <p>Online content must be reviewed.</p>			
R	California: CEC marking	Cal. Code Regs. tit. 20 § 1607	<p>Shall be marked with the following:</p> <ul style="list-style-type: none"> -Manufacturer's name or brand name or trademark -Model number -Date of manufacture with year and month or small increment. Additionally, an equivalent date code may be used if supplier provides the de-coding showing that date of manufacture, year and month or small increment is included in the code. -Efficiency Rating -Energy Performance Information 		NA	/
R	Energy and Water Efficiency Regulations	<p>California: Cal. Code Regs. tit. 20 § 1607; Colorado: Colo. Rev. Stat. § 6-7.5-109; Connecticut: Conn. Agencies Regs. § 16a-48-6; District of Columbia: D.C. Code § 8-1771.05; Georgia: Title 8, Chap 2, Article 1, Part 1, § 8-2-3 Hawaii: Revised Status, Title 12, 196-88; Maryland: Md. Code Regs. 14.26.03.11; Nevada: Nev. Rev. Stat. § 701.774; New Hampshire: N.H. Rev. Stat. § 339-G:7; New Jersey: N.J. Stat. § 52:27D-141.20; Oregon: ORS Vol 13.Title 36A. § 469.255; Rhode Island: R.I. Gen. Laws</p>	<p>Covered products shall comply with the states' applicable labeling and database disclosure requirements.</p> <p>Shall be marked with the following:</p> <ul style="list-style-type: none"> -A mark, label, or a tag on the product indicating compliance with the efficiency requirements -Manufacturer's name or brand name or trademark -Model number -Date of manufacture with year and month or small increment. Additionally, an equivalent date code may be used if supplier provides the de-coding showing that date of manufacture, year and month or small increment is included in the code. -Efficiency Rating 		NA	/



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
10000-USA- (V215)
REG ALL PRODUCTS**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

	Evaluation	Citation / Method	Criteria	Comments	Result	Rating
		§ 39-27.1-7; Texas: 30 Tex. Admin. Code § 290.260; Vermont: 9 V.S.A. § 2798; Washington. Rev. Code § 19.260.070;				
	Texas: Energy and Water Efficiency Regulations	Texas: 30 Tex. Admin. Code § 290.260;	<p>A person may not sell, offer for sale, distribute, or import into this state a new commercial or residential clothes washing machine, dish washing machine, or lawn sprinkler unless the clothes washing machine, dish washing machine, or lawn sprinkler is marked or labeled in accordance with these sections.</p> <p>(1) Each clothes washing machine and dish washing machine shall have an attached label that shows the amount of water used per cycle.</p> <p>(2) Each lawn sprinkler shall be marked with the water usage expressed in gallons per minute (gpm) by either a permanent mark on each sprinkler, or a label or tag attached to each sprinkler.</p>		NA	/
	Energy Efficiency Marking and/or Labeling (FTC)	16 CFR 305	Covered products shall be marked in compliance with the regulation.		NA	/
R	Biodegradable, degradable, decomposable claims	Walmart USA Product Safety and Compliance Standard based on California Pub. Res. Code Chapter 5.7 (42355 - 42358.5); Colorado Revised Statutes § 25-17-804; Ann. Code of Maryland Chapter 374 Subtitle 21 (9-2101 – 9-2105); Revised Code of Washington Title 70A Chapter 455 Section 020 (RCW § 70A.455.020)	<p>Labeling for any consumer product shall not use the terms or any form of the terms biodegradable, degradable, decomposable, oxo-degradable, or imply in any way that the product will break down, fragment, biodegrade, or decompose in a landfill or other environment.</p> <p>All types of packaging for a consumer product shall not include the terms or any form of the terms biodegradable, degradable, decomposable, oxo-degradable, or imply in any way that the product will break down, fragment, biodegrade, or decompose in a landfill or other environment.</p> <p>Product, packaging and online content must be reviewed.</p>		NA	/



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
10000-USA- (V215)
REG ALL PRODUCTS**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

	Evaluation	Citation / Method	Criteria	Comments	Result	Rating
R	California, Maryland, Minnesota, and Washington: Compostable Plastic Bag Claims	California Pub. Res. Code Chapter 5.7 § 42357.5; Ann. Code of Maryland Chapter 374 Subtitle 21 (9-2101 – 9-2105); Minn Stat. § 325E.046 & Revised Code of Washington Title 70A Chapter 455 Section 050 (RCW § 70A.455.050)	<p>Plastic bags which include a "compostable" claim must be:</p> <p>(1) Labeled with a certification logo indicating the bag meets the ASTM D6400 standard; and</p> <p>(2) Comply with one of the following:</p> <ul style="list-style-type: none"> • Made from a color of green, labeled with the word "compostable" on one side of the bag, and the label shall be at least one inch in height; or • Labeled with the word "compostable" on both sides of the bag, with the label appearing: <ul style="list-style-type: none"> • As green colored lettering, at least one inch in height; OR • Within a contrasting green color band of at least one inch in height with color contrasting lettering of at least one-half inch in height. <p>If the bag is smaller than 14 inches by 14 inches, the lettering and stripe shall be in proportion to the size of the bag.</p> <p>A plastic bag which includes a "compostable" claim and is sold or distributed in the state shall not display a chasing arrow resin identification code or recycling symbol of any form.</p> <p>Product, packaging, and online content must be reviewed.</p> <p>In lieu of testing, documentation may be submitted in the form of a test report dated within 1 year.</p>	The Test Report may be accepted from a Non-CPSC accredited lab.	NA	/
R	Colorado and Washington Compostable Product and Product Packaging Labeling Requirements	C.R.S. § 25-17-803; RCW § 70A.455.040 & RCW § 70A.455.060	<p>[Excluding Small Products]</p> <p>A product and/or product packaging that includes a "compostable" claim must:</p> <ul style="list-style-type: none"> • Include a logo indicating the product has been certified by a recognized third-party independent verification body (BPI, TUV, etc.) as meeting ASTM standards D6400 or D6868; • Include the word "compostable"; and • Use green-colored labeling, striping, or other recognizable green symbols, colors, tinting, marks, or design patterns. 	Items comprised of 100% fiber or comprised entirely of untreated wood are exempt from this requirement.	NA	/



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
10000-USA- (V215)
REG ALL PRODUCTS**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

	Evaluation	Citation / Method	Criteria	Comments	Result	Rating
			<p>A product and/or product packaging that includes a "compostable" claim shall not display a chasing arrow resin identification code or recycling symbol of any form.</p> <p>Product, packaging, and online content must be reviewed.</p>			
R	Colorado and Washington Compostable Product and Product Packaging Labeling Requirements	C.R.S. § 25-17-803; RCW § 70A.455.040 & RCW § 70A.455.060	<p>[Small Product Only] A small product and/or small product packaging that includes a "compostable" claim must:</p> <ul style="list-style-type: none"> • Include a logo indicating the product has been certified by a recognized third-party independent verification body (BPI, TUV, etc.) as meeting ASTM standards D6400 or D6868; • Use green, beige, or brown colored labeling, striping, or other recognizable green, beige, or brown symbols, colors, tinting, marks, or design pattern; and • Include the word "compostable" where possible. <p>If the product or product packaging has a width of one-half inch or less of printable surface space, the word "Compostable" product marking requirement is exempt. All other requirements must be satisfied.</p> <p>A product and/or product packaging that includes a "compostable" claim shall not display a chasing arrow resin identification code or recycling symbol of any form.</p> <p>Product, packaging, and online content must be reviewed.</p>	<p>Items comprised of 100% fiber or comprised entirely of untreated wood are exempt from this requirement.</p> <p>Small product means a product with a width of one-half inch or less of printable surface. Includes, but not limited to, straws, knives, forks, spoons, etc.</p>	NA	/
R	California, Maryland, & Washington: Compostable, home compostable, marine degradable, Soil Degradable AG Mulch Film, or Biodegradable Mulch Film claims for	California Pub. Res. Code Chapter 5.7 (42355 - 42358.5); Ann. Code of Maryland Chapter 374 Subtitle 21 (9-2101 – 9-2105); Revised Code of Washington Title 70A Chapter 455	<p>Any consumer product and/or any type of packaging for a consumer product that contains or is made of plastic shall not use any of the terms compostable, home compostable, marine degradable, soil degradable AG mulch film or biodegradable mulch film unless the plastic product meets the applicable standard as follows:</p> <ul style="list-style-type: none"> • Compostable Plastics ASTM D6400 standard • Biodegradable Plastics Used as Coatings on Paper and Other Compostable Substrates ASTM D6868 standard • Home Compostable Plastics (CA and MD ONLY) 	The test report may be accepted from a Non-CPSC accredited lab.	NA	/



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
10000-USA- (V215)
REG ALL PRODUCTS**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

Evaluation	Citation / Method	Criteria	Comments	Result	Rating
plastic articles and components		<p>EN (European Norm) 13432 standard adapted to low-temperature composting in accordance with the Vincotte OK Compost Home certification.</p> <ul style="list-style-type: none"> • Home Compostable (WA ONLY) ASTM D6400 or D6868 standard The product may not be labeled "home compostable only." • Non-Floating Biodegradable Plastics in the Marine Environment (CA ONLY) ASTM D7081 standard • Soil Degradable AG Mulch Film or Biodegradable Mulch Film Plastics (i) Either the Vincotte OK Biodegradable Soil certification standard, or at ambient temperatures and in soil have at least 90% biodegradation absolute or relative to microcrystalline cellulose in less than 2 years' time, tested according to ISO 17556 standard or ASTM D5988 standard; AND (ii) Fulfills ASTM D6400 standard for plant growth and regulated metals requirements. <p>"Plastic product" means a product made of plastic, whether alone or in combination with other materials including paperboard. Plastic product includes:</p> <ul style="list-style-type: none"> • A packaging or a packaging component; • A bag, sack, wrap, or other thin plastic sheet film product; • A food or beverage container or a container component, including, but not limited to, a tray, clamshell, straw, lid, or utensil; and • Any other plastic product or part of a plastic product. <p>"Personal care products" are excluded from the regulations.</p> <p>Product, packaging, and online content must be reviewed.</p> <p>Please note in the test report the specific state for home compostable failures.</p> <p>In lieu of testing, document may be submitted in form of test report dated within 1 year.</p>			
Claim verification	Federal Trade Commission (FTC)	Product shall meet all label claims, both factual and objective. Any claim not addressed by the Product Safety and Compliance Team	Refer to "WMRT-GB-08612-DATA-CLAIM-VERIFICATION"	M (SEE CLAIM TABLE)	PASS



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
10000-USA- (V215)
REG ALL PRODUCTS**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

Evaluation	Citation / Method	Criteria	Comments	Result	Rating
	and Various State Laws	<p>should be managed by the Walmart Technical and Quality teams. Testing shall be performed to substantiate label claims.</p> <p>Packaging, labeling and online content must be reviewed.</p> <p>In lieu of testing, documentation may be submitted in the form of either a test report or Bill of Materials with Letter of Guarantee certifying the product does not contain BPA - Only allowed for silicone, polypropylene, and thermal plastic elastomer.</p>	<p>This includes a claim that a product is made without or free of any chemical.</p> <p>For BPA-free claims, the maximum allowed limit is 0.1 ppm.</p> <p>The Test Report may be accepted from a Non-CPSC accredited lab.</p>		
Industry or Regulatory Claims	Federal Trade Commission (FTC) and Various State Laws	<p>Any product claiming to meet industry or regulatory standards must have the claim substantiated using the corresponding claimed industry or regulatory standard.</p> <p>Packaging, labeling and online content must be reviewed.</p> <p>In lieu of testing, documentation may be submitted in the form of a test report dated within 1 year.</p>	<p>Substantiation includes tests, analyses, research, or studies that have been conducted and evaluated in an objective manner by a qualified organization that are generally accepted in the industry to be accurate and reliable. Supplier certifications may only be accepted if in line with regulations.</p>	NA	/
Material claims (wood, metal, plastic, etc.)	Walmart USA Product Safety and Compliance Standard	<p>All material claims must be substantiated using an industry accepted method.</p> <p>Packaging, labeling and online content must be reviewed.</p> <p>In lieu of testing, documentation may be submitted in the form of either a test report or a Letter of Guarantee (for wood only) dated within 1 year.</p>	<p>The Test Report may be accepted from a Non-CPSC accredited lab.</p>	NA	/
Sterilization claims	USP<71>	<p>Any product with a sterilization claim must meet the requirements of USP 71.</p> <p>Packaging, labeling and online content must be reviewed.</p> <p>In Lieu of testing, documentation may be submitted in form of test report dated within 1 year.</p>	<p>The Test Report may be accepted from a Non-CPSC accredited lab.</p>	NA	/



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
10000-USA- (V215)
REG ALL PRODUCTS**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

Evaluation	Citation / Method	Criteria	Comments	Result	Rating
License claims	Walmart USA Product Safety and Compliance Standard	All licensed products must have documentation from licensor showing approval for licensing. Packaging, labeling and online content must be reviewed.		NA	/
Flushability or septic safe claims	Walmart USA Product Safety and Compliance Standard	Product must meet acceptance criteria for flush ability as published in the Guidance Document for Assessing the Flush ability of Nonwoven Consumer Products. Packaging, labeling and online content must be reviewed. In lieu of testing, documentation may be submitted in the form of a test report valid for the life of the product so long as no change in materials, components, material/component part supplier, design, factory, or manufacturing process.	http://www.inda.org/wp-content/uploads/2019/04/Guidelines-for-Assessing-the-Flushability-of-Disposable-Nonwoven-Products-Edition-4-Final.pdf https://www.edana.org/docs/default-source/product-stewardship/guidelines-for-assessing-the-flushability-of-disposable-nonwoven-products-ed-4-finalb76f3ccdd5286df88968ff0000bfc5c0.pdf?sfvrsn=34b4409b_2 The test report may be accepted from a Non-CPSC accredited lab.	NA	/
Claims of impact on the structure or function of the body	Walmart Product Safety and Compliance Requirement	For claims of impact on the structure or function of the body, a claim substantiation study from a reputable source (e.g., academic study, peer reviewed journal, product study, etc.) must be provided. Packaging, labeling and online content must be reviewed. Examples of claims of impact on the structure or function of the body include (but are not limited to): "Relieves [disease, condition]," "Treats [disease, condition]," "Prevents [disease, condition]." In lieu of testing, documentation may be submitted in the form of a test report dated within 1 year.	The test report may be accepted from a Non-CPSC accredited lab.	NA	/
A R Made in the USA claim	FTC Act Section 5a / California BPC Division 7 Part 3	Suppliers participating in the Walmart U.S. Manufacturing Logo Campaign are exempt from testing this label claim verification, however they must comply with the guidelines for the U.S. Manufacturing Campaign.	This label claim verification does not cover the Walmart U.S. Manufacturing Logo Campaign requirements.	NA	/



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
10000-USA- (V215)
REG ALL PRODUCTS**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

	Evaluation	Citation / Method	Criteria	Comments	Result	Rating
		Chapter 1 Article 2 Section 17533.7	<p>Suppliers not participating in the Walmart U.S. Manufacturing Logo Campaign that make expressed or implied "Made in the USA" type claims, must submit an executed Made in USA Supplier Certification to the test lab for each item at the time of production testing.</p> <p>Packaging, labeling and online content must be reviewed.</p> <p>The Made in USA Supplier Certification must be executed by an officer of the supplier's company.</p> <p>Additional guidance can be found at:</p> <p>https://www.ftc.gov/public-statements/1997/12/enforcement-policy-statement-us-origin-claims</p> <p>https://www.ftc.gov/news-events/media-resources/tools-consumers/made-usa</p> <p>https://www.ftc.gov/tips-advice/business-center/guidance/complying-made-usa-standard</p> <p>https://www.ftc.gov/system/files/documents/plain-language/alt101-selling-american-made-products-made-usa-claims.pdf</p> <p>https://www.ftc.gov/news-events/blogs/business-blog/2015/11/made-usa-claims-three-cheers-said-right-true</p>	<p>Refer to WMRT-GB-SUPP-MADE IN USA SUPPLIER CERTIFICATION form.</p> <p>Refer to the Walmart U.S. Manufacturing approved logo's below to verify minimum font size for Private Brand packaging and spacing requirements for logo subclaims.</p>		
R	Non-toxic claims	16 CFR 1500.3(b)(5) and 1500.3(b)(7)-(9)	<p>Toxicological Risk Assessment shall be conducted for products bearing a "Non-Toxic" claim.</p> <p>Packaging, labeling and online content must be reviewed.</p> <p>In lieu of testing, documentation may be submitted in the form of either a test report or a review by a board certified toxicologist dated within 5 years, unless there has been a reformulation or material change.</p>	The Test Report must be from a CPSC accepted laboratory.	NA	/
A R	PFAS No/Made Without/Free of Claims	Walmart USA Product Safety and Compliance Standard	Claims of "No", "Made Without" or "Free Of" any PFAS chemicals must be substantiated.	The test report may be accepted from a Non-CPSC accredited lab.	NA	/



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
10000-USA- (V215)
REG ALL PRODUCTS**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

	Evaluation	Citation / Method	Criteria	Comments	Result	Rating
		based on Cal. Health & Saf. Code § 109011-109012; Colo. Rev. Stat. § 25-15-604	<p>Claims that the product is free of a specific PFAS chemical must be substantiated with scientific evidence supporting that the product does not contain any level of individual PFAS chemicals.</p> <p>Packaging, labeling, and online content must be reviewed.</p> <p>In lieu of testing, documentation may be submitted in the form of a test report dated within 1 year.</p>			
R	Country of origin marking	19 USC 1304	<p>Every article imported into the United States shall be marked in a way to indicate to the ultimate purchaser in the United States the English name of the country of origin of the article. The article shall be marked in a conspicuous place as legibly, indelibly, and permanently as the nature of the article (or container) will permit.</p> <p>Packaging, labeling and online content must be reviewed.</p>		M	PASS
	Declaration of identity, responsibility, and quantity for package products (Products not regulated by FPLA) EXCEPT size, placement and readability of labeling	Walmart USA Product Safety and Compliance Standard based on various state Laws	<p>Packaging and Labeling content must meet the requirements outlined below. Declaration of Identity - The identity of the product shall appear on the package label and shall not be misleading or deceptive. The identity shall be:</p> <ul style="list-style-type: none"> • the name specified in, or required by, any federal or state regulation, or • the common or usual name, or • the generic name or other appropriate description, including a statement of function. <p>Note: If a product is clearly recognizable, a declaration of identity is not required (i.e. open stock dinnerware). Note: Brand names/ logos may appear on product as part of the identity.</p> <p>Declaration of Responsibility - The name and location (street address, city, state and zip code) of the manufacturer, packer, or distributor shall appear on the package if that package is sold, kept, offered, or exposed for sale at a location other than the premises where it was packed.</p> <ul style="list-style-type: none"> • The street address and zip code may be omitted if the company is located in a readily accessible, widely published, and publicly available resource including but not limited to a printed directory, electronic database or website. 		M	PASS



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
10000-USA- (V215)
REG ALL PRODUCTS**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

	Evaluation	Citation / Method	Criteria	Comments	Result	Rating
			<p>Declaration of Quantity - A declaration of net quantity shall be accurate and shall appear on the package unless the item is measured by count and contains six or fewer pieces that are clearly visible.</p> <ul style="list-style-type: none"> Quantity statements should include US customary units and SI metric units when applicable. <p>Note: Where there is a firmly established general usage and trade custom with respect to the terms used in expressing a declaration of quantity such declaration of quantity may be expressed in traditional terms, example 15 in steering wheel cover.</p> <p>Note: Dimensions are not required for irregularly shaped products unless dimensions are commonly used for the item to make a buying decisions.</p>			
	Declaration of identity, responsibility, and quantity for packaged products (not regulated by FPLA) Size, placement and readability of labeling ONLY	Walmart USA Product Safety and Compliance Standard based on various state Laws	<p>Packaging and Labeling size, placement and readability must meet the requirements outlined below related to the Declaration of Identity, Declaration of Responsibility and Declaration of Quantity. All information is required to appear on a consumer package and shall be prominently displayed in the English language. Prominently displayed shall be defined as follows:</p> <ul style="list-style-type: none"> Type size large enough to be read; Good contrast in color between font and background; Conspicuous and legible type without obscuring design or vignettes. 	Size = Stated font size requirements. Placement = Stated placement of information (i.e. "prominent" or "Principal Display Panel") Readability = Spelling and grammar, abbreviations (i.e. "in" versus "inches")	M	PASS
A R	Formaldehyde Labeling, as applicable to Composite Wood Products	40 CFR Part 770 (TSCA Title VI)	<p>Composite wood containing products must be labeled with a TSCA Title VI label. Below are the parameters for this label.</p> <p>If practicable, labels must be on both the product and the package containing the finished product. If deemed impracticable, the label must appear on either the packaging or the product. Labels on a product which are visible at the point of sale satisfy both the product and package labeling requirement. Labels may be tags, stickers, stamped, or printed directly on the composite wood product or finished goods and should be in a location that is easily accessible.</p> <p>The required information may be on a separate label or incorporated into other existing labels. Labels must be in English and the format, color, size, and font of the label are the decision of the manufacturer or fabricator.</p> <p>Labels must include, at a minimum, the following information:</p>	After March 22, 2019, only products exempt from TSCA Title VI under the de minimis rule will be permitted to have the CARB ATCM labeling as required (see test ID PL85A-J).	M	PASS



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
10000-USA- (V215)
REG ALL PRODUCTS**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

	Evaluation	Citation / Method	Criteria	Comments	Result	Rating
			<ul style="list-style-type: none"> Fabricator's name or Importer or Distributor's name Date the finished good was produced using two digit month and four digit year (mm/yyyy or yyyy/mm) or the two digit month, two digit day, and four digit year (mm/dd/yyyy). A statement of compliance to denote that the composite wood product or finished good complies with TSCA Title VI. The statement of compliance must reference the "TSCA Title VI" citation. <p>If deemed impracticable to place the label on both packaging and product, the supplier must provide a letter to the lab justifying why it is not practicable. Labs will not determine whether to accept or deny the justification letter, but must note receipt of the letter and maintain those records.</p>			
A R	Formaldehyde Labeling, as applicable to composite wood products exempt from TSCA Title VI under the de minimis rule	17 Cal. Code Reg. § 93120	<p>California ARB labeling requirements are satisfied by US EPA TSCA Title VI labeling. However, composite wood products exempt from TSCA Title VI labeling under the de minimis rule must still meet California requirements for labeling.</p> <p>Labels must include, at a minimum, the following information:</p> <ul style="list-style-type: none"> Fabricator's name or Importer or Distributor's name* Date the finished good was produced using two digit month and four digit year (mm/yyyy or yyyy/mm) or the two digit month, two digit day, and four digit year (mm/dd/yyyy). The ARB assigned number of the approved third party certifier, if applicable. A statement of compliance to denote that the composite wood product or finished good complies with the ATCM. The statement must include the applicable compliance level (Phase 2) or whether the product is made with NAF/ULEF based resins. 		NA	/
	Instruction language	Walmart USA Product Safety and Compliance Standard	Use and care instructions should be clear and understandable, without errors or spelling mistakes, and provided in English.		M	PASS
R	Labeling regulation - Federal Trade Commission (FTC) EXCEPT	F.P. and L. Act (16 CFR 500)	Packaging and Labeling content must comply with most current version of FPLA if applicable.		NA	/



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
10000-USA- (V215)
REG ALL PRODUCTS**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

	Evaluation	Citation / Method	Criteria	Comments	Result	Rating
	size, placement and readability of labeling					
R	Labeling regulation - Federal Trade Commission (FTC) Size, placement and readability of labeling ONLY	F.P. and L. Act (16 CFR 500)	<p>Packaging and Labeling size, placement and readability must comply with most current version of FPLA, if applicable.</p> <p>Note: Walmart's expectation is to measure font size for all products that fall under the scope of 16 CFR 500.</p>	<p>Size = Stated font size requirements. Placement = Stated placement of information (i.e. "prominent" or "Principal Display Panel") Readability = Spelling and grammar, abbreviations (i.e. "in" versus "inches")</p>	NA	/
A	Law labels - stuffed articles	Walmart USA Product Safety and Compliance Standard based on IABFLO Uniform Labeling Format and Various State Laws	Filled Bedding, Furniture, Sleeping Bags, Toys and other applicable items meant to be slept, reclined or sat upon must meet specific uniform law label requirements. All Samples shall be reviewed against the requirements of Law Label (Bedding Tag) as referenced in the current Manual of Labeling Laws (ISPA).	<p>www.iabflo.com www.sleepproducts.org</p> <p>Verification via GRS Website OR</p> <ol style="list-style-type: none"> 1. All applicable state applications 2. Proofs of payment 3. Proof of GRS registration 	NA	/
R	Pennsylvania Bedding, Upholstery, and Stuffed toys - Recycled Fiber Claims	34 Pa. Chapter 47, Subchap. A and H	<p>Stuffed Toys and Filled Bedding, Upholstered Furniture, Sleeping Bags, and other applicable items meant to be slept, reclined, or sat upon are prohibited from claiming recycled or regenerated fiber in connection with the fill or outer shell of the product on the product packaging, labeling, and affixed law label.</p> <p>Packaging, labeling and online content must be reviewed.</p>		NA	/
	Leather and imitation leather	15 U.S.C. 45 / 16 CFR 24	<p>Imitation or Simulated Leather must be disclosed (e.g., Non Leather, Simulated Leather, Vinyl, Vinyl Coated Fabric, Plastic, etc.) Bonded leather, ground leather, pulverized leather, shredded leather, reconstituted leather, if stated, must also include the percentage of leather fibers and non leather substances in the material. Example 60% leather fiber, 40% non leather substances . Trade names, coined name, trademark are not allowed if it misrepresents directly or by implication that an industry product is made in whole or in part from animal skin or hide.</p> <p>Packaging, labeling and online content must be reviewed.</p>	This does not apply to furniture	NA	/



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
10000-USA- (V215)
REG ALL PRODUCTS**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

	Evaluation	Citation / Method	Criteria	Comments	Result	Rating
R	Aerosols	16 CFR 1500.130	Self-pressurized containers shall conform to the labeling requirements as defined in 16 CFR 1500.130		NA	/
	Plastic bag warning statement	Walmart USA Product Safety and Compliance Standard based on Various State Laws: California, New York, Chicago, Massachusetts, and Rhode Island State and City Laws modified	Plastic bags with a thickness less than one mil (1/1000 inch) having an opening size of five inches in diameter or more must have the following warning or an equivalent warning visible from at least one side of the bag. If the total length and width is more than 40 inches, this warning or an equivalent warning must repeat at 20 inch intervals and be visible from one side of the bag: Warning: To avoid danger of suffocation, keep this plastic bag away from babies and children. Do not use this bag in cribs, beds, carriages or playpens. This bag is not a toy. California, Massachusetts, New York, and Rhode Island provide minimum type size for the warning. The following table sets forth type sizes that will satisfy all four state requirements. Total Length and Width of Bag Size of Print 60 inches or more at least 24 point 40 to 59 inches at least 18 point 25 to 39 inches at least 14 point Less than 25 inches at least 10 point *Virginia's law is intended for dry cleaning bags only and requires at least 36 point type.		NA	/
R	Faux fur	Walmart USA Product Safety and Compliance Standard based on 16 CFR 301 and New York State General Business Law Section 399-aaa and US HR 2480	Must be marked in a way to indicate to the ultimate purchaser whether the product is faux fur. Label must be visible at point of sale and permanent up to point of sale. Packaging, labeling and online content must be reviewed.		NA	/
R	Poison prevention packaging and labeling EXCEPT size, placement and readability of labeling	16 CFR 1700 / 16 CFR 1500.14	Shall comply with the most current requirements of 16 CFR 1700 "Poison Prevention Packaging" and 16 CFR 1500.14, "Product Requiring Special Labeling under section 3(b)." In lieu of testing, documentation may be submitted in the form of a test report dated within 1 year.		NA	/
R	Poison Prevention	16 CFR 1700 / 16 CFR 1500.14	Packaging and labeling size, placement and readability shall comply with the most current requirements of 16 CFR 1700 "Poison	Size = Stated font size requirements. Placement =	NA	/



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
10000-USA- (V215)
REG ALL PRODUCTS**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

	Evaluation	Citation / Method	Criteria	Comments	Result	Rating
	Packaging and Labeling Size, placement and readability of labeling ONLY		Prevention Packaging" and 16 CFR 1500.14, "Product Requiring Special Labeling under section 3(b)."	Stated placement of information (i.e. "prominent" or "Principal Display Panel") Readability = Spelling and grammar, abbreviations (i.e. "in" versus "inches")		
A R	Textile fiber products identification and wool products labeling act	16 CFR 300/303	<p>Must be visible at point of sale. If label is not visible through packaging, fiber content must be repeated on packaging. Generic fiber name must be used and the contents spelled correctly and listed in descending order of predominance. Where textile fiber products subject to the Act contain (1) any wool or (2) 5% or more of the total fiber weight of recycled wool, such fibers shall be designated and disclosed as wool or recycled wool.</p> <p>Note: To determine the actual percentage, refer to the physical characteristics section for Fiber Content AATCC 20/20A/ASTM D629. If lab analysis does not match claim, then the label will fail. Blends: Maximum 3% Tolerance. Single Fiber: 0% Tolerance.</p> <p>In lieu of testing, documentation may be submitted in the form of a test report dated within 1 year.</p> <p>Packaging, labeling and online content must be reviewed.</p>	<p>AATCC 20/20 A / ASTM D629 (1) Any Wool must be disclosed even if it is less than 5% of the total fiber weight (2) Fibre present in the amount of 5% or more of the total fiber weight must be disclosed.</p> <p>The test report must be from a CPSC approved laboratory.</p>	NA	/
A R	Toxics in packaging	Walmart USA Product Safety and Compliance Standard based on various state Laws	<p>Intentional introduction of any amount of lead, mercury, cadmium or hexavalent chromium in any packaging is prohibited. Incidental presence of these metals is limited to 100 ppm total concentration of lead, mercury, cadmium and hexavalent chromium in any packaging.</p> <p>In lieu of testing, documentation may be submitted in the form of either a test report or a Supplier Declaration of Compliance signed by company officer dated within 1 year.</p> <p>Client requirement</p>	The test report may be accepted from a Non-CPSC accredited lab.	M (COC WAS PROVIDED DATE: OCTOBER 17, 2025)	PASS
R	California Proposition 65 - Warning Label	Title 27, California Code of Regulations, Article 6 Clear and Reasonable Warnings / ANSI Z535.4-2023	<p>Products and/or packaging containing a Proposition 65 warning must meet requirements (bulleted below) set out in Title 27, California Code of Regulations, Article 6, Clear and Reasonable Warnings.</p> <p>Must include these bullet points:</p>	When/if warnings are present on the product/packaging, they must be formatted correctly. Intent of this test line is not verification of the requirement to warn.	NA	/



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
10000-USA- (V215)
REG ALL PRODUCTS**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

	Evaluation	Citation / Method	Criteria	Comments	Result	Rating
			<ul style="list-style-type: none"> - Warning symbol to the left of the word "WARNING" capitalized in bold - Chemical(s) found in product (short form will exclude chemical names) - If the chemical is a listed carcinogen and/or reproductive toxicant - Substantially similiar language for specific exposure pathway(s) found in Section 25603 (short form will exclude language) - Website URL (www.P65Warnings.ca.gov) <p>Packaging, labeling and online content must be reviewed.</p>			
A R	3D Pens containing ABS filaments, PC-ABS filaments and HIPS filaments	Walmart USA Product Safety and Compliance Standard based on California Proposition 65	<p>3D Pens containing acrylonitrile-butadiene-styrene (ABS) filaments, polycarbonate ABS (PC-ABS) filaments and high impact polystyrene (HIPS) filaments must meet requirements of a California Proposition 65 warning.</p> <p>Packaging, labeling and online content must be reviewed.</p>		NA	/
A R	Wearing apparel, bolt fabric, and textile products (If care label present)	16 CFR 423	<p>Shall be tested to substantiate care label content. Items not required to contain a care label but having a label present shall be laundered according to label instructions only. A general appearance evaluation shall be conducted.</p> <p>Packaging, labeling and online content must be reviewed.</p>	Pass/Fail for the mechanics of the labeling.	NA	/
R	Bamboo textiles	Walmart USA Product Safety and Compliance Standard based on Federal Trade Commission (FTC) Guidance	<p>Any textile described as bamboo shall be labeled and advertised or described, in any/every instance as "rayon (or viscose) made from bamboo." This means that every time the word bamboo appears it must be qualified as "rayon (or viscose) made from bamboo."</p> <p>Additionally, such products shall NOT be labeled, advertised, or described, in any instance (e.g., on the packaging or product labels, title, or any description) as: (1) Hypoallergenic, (2) Antimicrobial, or (3) Antibacterial, unless there is support for such a claim independent of the product having been derived from bamboo (e.g., antimicrobial coating)</p> <p>Packaging, labeling and online content must be reviewed.</p>	Products receiving a "FAIL" for this reason are NOT permitted an automatic retest.	NA	/



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
10000-USA- (V215)
REG ALL PRODUCTS**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

	Evaluation	Citation / Method	Criteria	Comments	Result	Rating
R	Washington trash bag labeling	RCW 70A.245.060	<p>Manufacturers must label each package containing plastic trash bags with:</p> <p>The name of the manufacturer and the city, state, and country where the manufacturer is located; or</p> <p>A uniform resource locator or quick response code to an internet website that contains the name of the manufacturer and the city, state, and country where the manufacturer is located.</p>		NA	/
R	Disposable Wipe Labeling	Walmart USA Product Safety and Compliance Standard based on Cal. Pub. Resources Code Section 49651, Illinois Wipes Labeling Act, Oregon Annotated Statutes Section 646A.540, Revised Code of Washington 70A.525.005, and Colo. Rev. Stat. § 25-18.9, 2023 Bill Text MI H.B. 4596, Public Act of 2024 No. 43	<p>A manufacturer shall comply with all the following for every Covered Product regardless of packaging type, unless stated otherwise below:</p> <ul style="list-style-type: none"> • Shall place the symbol and label the phrase "Do Not Flush" at a size that is equal to at least 2% of the surface area on the principal display panel in a prominent and reasonably visible location that is viewable each time a wipe is dispensed • A manufacturer shall ensure the packaging seams, folds, or other package design elements do not obscure the symbol or label notice • A manufacturer shall ensure the symbol and label notice have sufficiently high contrast with the immediate background of the packaging to render them more likely to be seen and read by the ordinary customer • A manufacturer shall not make any representation about the flushable attributes, flushable benefits, flushable performance, or flushable efficacy of a Covered Product <p>A manufacturer shall comply with one of the following options based on packaging type:</p> <p>Cylindrical packaging:</p> <ul style="list-style-type: none"> • Place the "Do Not Flush" symbol and label notice on the principal display panel • Place the "Do Not Flush" symbol on the principal display panel, and either the symbol or label notice, or the symbol and label notice in combination, on the flip lid, subject to the following: 	<p>http://www.inda.org/wp-content/uploads/2019/04/Guidelines-for-Assessing-the-Flushability-of-Disposable-Nonwoven-Products-Edition-4-Final.pdf</p>	NA	/



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
10000-USA- (V215)
REG ALL PRODUCTS**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

Evaluation	Citation / Method	Criteria	Comments	Result	Rating
		<ul style="list-style-type: none"> • If the label notice does not appear on the flip lid, the label notice shall be placed on the principal display panel; • The symbol or label notice, or the symbol and label notice in combination, on the flip lid may be embossed, and in this scenario would not need to require with the high contrast requirement; • The symbol or label notice, or the symbol and label notice in combination, on the flip lid shall cover a minimum of 8 percent of the surface area of the flip lid. <p>Flexible film packaging:</p> <ul style="list-style-type: none"> • Place the symbol on the principal display panel and dispensing side panel and place the label notice on either the principal display panel or dispensing side panel • If the principal display panel is on the dispensing side of the package, two symbols are not required <p>Refillable tubs or other rigid packaging:</p> <ul style="list-style-type: none"> • Place the symbol and label notice on the principal display panel <p>Packaging not intended to dispense individual wipes:</p> <ul style="list-style-type: none"> • Place the symbol and label notice on the principal display panel <p>Bulk packaging:</p> <ul style="list-style-type: none"> • Both the outer package visible at retail and the individual packages contain within shall comply with the labeling requirements. <p>INDA/EDANA Flushability reference document provided for additional review.</p>			
<p>R California cleaning product right to know - Private brand</p>	<p>Walmart USA Product Safety and Compliance Standard based on Cal Health &</p>	<p>A covered Private Brand (including Walmart and Sam's Club exclusive and proprietary brands) product shall have the disclosure form readily available on Walmart.com and Samsclub.com.</p>	<p>https://www.issa.com/wpcontent/uploads/issa_summary_ca_cleaning_product_rtk_act_002_.pdf</p>	<p>NA</p>	<p>/</p>



BUREAU VERITAS

TEST PROTOCOL FOR 10000-USA- (V215) REG ALL PRODUCTS

BV Lab Number: 96253120624
Technician Name: DUY
Test Date: NOVEMBER 08, 2025
Reviewed By/Date: JOHN/ DECEMBER 02, 2025

Table with 6 columns: Evaluation, Citation / Method, Criteria, Comments, Result, Rating. It contains three rows of test criteria related to website information and California cleaning product labeling requirements.



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
10000-USA- (V215)
REG ALL PRODUCTS**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

Evaluation	Citation / Method	Criteria	Comments	Result	Rating
		<p>- "Contains Fragrance Allergen" if fragrance ingredient is included on the EU Cosmetics Regulation 1223/2009 - Colorants may be listed as "colorants" and non-allergen fragrance ingredients may be listed as "fragrances"</p> <p>Note: Evaluate ingredient nomenclature only</p> <p>Ingredients that are confidential business information may be listed using a generic name.</p> <p>ISSA reference document provided for additional guidance.</p>			
R	Walmart USA Product Safety and Compliance Standard based on FTC's Green Guides	<p>Green/eco claims must be:</p> <ul style="list-style-type: none"> • Clear and specific about the benefits it provides to the environment. • Truthful and not misleading; • Based on scientific evidence that can be substantiated and verified; • Relevant to the particular product; and • Must be presented in a manner that clearly indicates whether the claim applies to the complete product, a component of the product, or the packaging. <p>FTC Guides for the use of Environmental Marketing Claims provided for additional guidance.</p> <p>Green claims shall not be vague and non-specific (Including but not limited to Environmentally Safe, Environmentally Friendly, Green, Natures Friend, Ozone Friendly, Planet Friendly, Earth Friendly, Natural, Sustainable, Eco-Friendly, Happy Planet).</p> <p>Packaging, labeling, and online content must be reviewed.</p> <p>In lieu of testing, documentation may be submitted in the form of a test report dated within 1 year.</p> <p>All Private Brand Green Claims not substantiated via Eco-Records are within scope of this requirement.</p>	<p>https://www.ftc.gov/sites/default/files/attachments/press-releases/ftc-issues-revised-green-guides/greenguides.pdf</p> <p>The test report may be accepted from a Non-CPSC accredited lab.</p>	NA	/



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
10000-USA- (V215)
REG ALL PRODUCTS**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

	Evaluation	Citation / Method	Criteria	Comments	Result	Rating
R	Made in Oklahoma Logo	Okla. Admin. Code § 35:40-23-6	<p>Any manufacturers using the "Made in Oklahoma" program logo must be a member of the Made in Oklahoma program.</p> <p>Labs must review Made in Oklahoma Program website at the time of testing to verify membership.</p> <p>Packaging, labeling, and online content must be reviewed.</p>	<p>https://www.madeinoklahoma.net /</p>	NA	/
	California Express Warranties	Cal Civ. Code § 1790 et. seq. (The Song-Beverly Act)	<p>Expressed (written) warranties for consumer goods, as defined, must not have wording implying the warranty would become effective earlier than the date of actual delivery of the good.</p> <p>Express warranty and Online Content must be reviewed.</p>	<p>"Consumer goods" means any new product or part thereof that is used, bought, or leased for use primarily for personal, family, or household purposes, except for clothing and consumables.</p> <p>"Consumer goods" shall include new and used assistive devices sold at retail.</p>	NA	/
R	California Chemical Warning - cookware	California Health & Safety Code, 109011 to 109012 / Colo. Rev. Stat. § 25-15-604	<p>[For Private Brand only]</p> <p>Cookware containing intentionally added designated chemicals require an online warning. Warnings must include:</p> <p>(a) List of all chemicals in the cookware that are also present on the designated list.</p> <p>(b) Names of the authoritative list or lists referenced by the Department of Toxic Substances Control</p> <p>(c) Link to the internet website for the authoritative list or lists</p> <p>(d) Statement about why PFAS chemicals were added to the product.</p> <p>Online content must be reviewed.</p> <p>Note: - It should not be failed if the Product ID Numbers is not available at the time of testing.</p>	<p>Note: When warnings are present on Walmart.com or Samsclub.com, they must be formatted correctly.</p> <p>Intent of this test line is not verification of the requirement to warn.</p> <p>https://dtsc.ca.gov/scp/authoritative-lists/</p> <p>Cookware includes, but is not limited to, pots, pans, skillets, indoor and outdoor grills, baking sheets, baking molds, trays, bowls, cooking utensils, food storage containers.</p> <p>Does not apply to drinking water bottles, tumblers, and stainless-steel cups.</p>	NA	/



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
10000-USA- (V215)
REG ALL PRODUCTS**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

	Evaluation	Citation / Method	Criteria	Comments	Result	Rating
A R	VOC Packaging & Labeling (Federal)	40 CFR 59.205	Manufacturers of consumer products identified in 40 CFR §59.202 shall clearly display on the product container or package the day, month, and year on which the product was manufactured, or a code indicating such date.		NA	/
A R	VOC Packaging & Labeling (State)	17 CCR 94512(b-e) / 250-RICR-120-05-31.7 and 31.8	Certain covered products, including but not limited to, aerosol adhesives, adhesive removers, electronic cleaners, electrical cleaners, energized electrical cleaners, contact adhesives, non-aerosol sealant/caulking compounds, multi-purpose solvents, and paint thinners must comply with additional container labeling requirements.		NA	/
A R	Architectural and Industrial Maintenance Coatings labelling (VOC)	Ohio Admin. Code § 3745-113-04	Covered products shall include the following information on the product label: a) the date the coating was manufactured or a date code representing the date; b) a statement of the manufacturer's thinning recommendations; and c) the VOC content, calculated as the maximum or actual VOC content, the maximum VOC content as determined from all potential or actual product formulations, or the VOC content as determined using a prescribed testing method. VOC content shall be displayed in grams of VOC per liter of coating. Certain covered products, including but not limited to, faux finishing coatings, clear brushing lacquers, quick dry enamels, stone consolidants, and wood coatings, must comply with specific labeling requirements outlined in OAC 3745-113-04(A)(4-14).	https://codes.ohio.gov/ohio-administrative-code/rule-3745-113-04	NA	/
	Weapon or self-defense claims	Walmart USA Product Safety and Compliance Standard	Products shall not be labeled, advertised, or described, in any instance (e.g. on the packaging or product labels) as for attacking and/or self-defense. Sporting goods including self-defense spray products are excluded. Packaging, labeling and online content must be reviewed.		NA	/
A R	Chemical Disclosure/Labeling in Cookware	California Health & Safety Code, 109011 to 109012 / Colo. Rev. Stat. § 25-15-604	Manufacturers of cookware with one or more intentionally added designated and/or PFAS chemical(s) in the handle of the product or in any product surface that comes into contact with food, foodstuffs,	Cookware includes, but is not limited to, pots, pans, skillets, indoor and outdoor grills, baking sheets, baking molds, trays,	NA	/



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
10000-USA- (V215)
REG ALL PRODUCTS**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

	Evaluation	Citation / Method	Criteria	Comments	Result	Rating
			<p>or beverages must include the following information on the product label, all of which must be visible and legible to the consumer:</p> <p>a) the phrase "This product contains..." followed by a list of intentionally added designated chemicals; b) in English and Spanish, the phrase "For more information about chemicals in this product, visit..." followed by a web address that provides the required information; and c) a QR code to a web page providing required information.</p> <p>Cookware is exempt from the package labeling requirements if: a) the surface of the cookware cannot fit a product label of at least two square inches; and b) the cookware does not contain either an exterior container or wrapper on which a product label can be affixed or a tag or other attachment with information about the product attached to the cookware.</p>	<p>bowls, cooking utensils, and food storage containers.</p> <p>When warnings are present, they must be formatted correctly. Intent of this test line is not verification of the requirement to warn.</p> <p>Does not apply to drinking water bottles, tumblers, and stainless-steel cups.</p>		
A R	Reese's Law - Product and Product Packaging Labeling Requirements for Consumer Products Containing or Designed to Use Batteries that Present Ingestion Hazards	16 CFR § 1263.3	Consumer Products containing or designed to use batteries that present an ingestion hazard must comply with the most current version of the regulations.	<p>Toy products able to show proof of compliance with the labeling requirements of 16 CFR 1250 are exempt from this requirement.</p> <p>Zinc-Air batteries are exempt from this requirement.</p>	NA	/
A R	Reese's Law - Button Cell or Coin Battery Packaging Labeling Requirements	16 CFR § 1263.4	Labeling of Button cell or coin batteries must comply with the most current version of the regulation.		NA	/
R	Washington Non-	RCW 70A.455.070	The product and/or product packaging for non-compostable film bags must comply with the following requirements:		NA	/



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
10000-USA- (V215)
REG ALL PRODUCTS**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

	Evaluation	Citation / Method	Criteria	Comments	Result	Rating
	Compostable Film Bags		<ul style="list-style-type: none"> • May not use green, brown, or beige stripes that are larger than .25 inch wide. • May not use green, brown, or beige lettering or logos for purposes other than brand identity purposes. • May not use botanical motifs, such as leaves or vines that are green, brown, or beige. 			
R	MN Aerosol dusters	Minn. Stat. § 325F.078	<p>Must comply with the most current labeling requirements:</p> <p>(a) An aerosol duster manufactured after May 31, 2025, must not be sold in this state unless the aerosol duster clearly warns against the dangers of intentionally misusing duster aerosol products.</p> <p>(b) The font size of this warning shall be the same or larger than other warning language. The font color and background of the label must be in contrasting colors.</p> <p>(c) The label on each can of aerosol duster containing DFE must contain the following:</p> <ul style="list-style-type: none"> (1) the words "DANGER: DEATH! Breathing this product to get high can kill you!"; and (2) the poison control phone number, 1-800-222-1222. <p>(d) In order to comply with paragraph (a), a label may include, but is not limited to the words:</p> <ul style="list-style-type: none"> (1) "Deliberate misuse by concentrating and inhaling the contents can be harmful or fatal!"; and (2) "Intentional misuse by deliberately concentrating and inhaling the vapors can be harmful or fatal!". <p>(e) The safety symbols and color standards of the label described in this section must conform with the ANSI Z535 safety signage standards guidelines established by the American National Standards Institute.</p>		NA	/
STAR 2 - REGULATORY/COMPLIANCE REGISTRATIONS						
R	Washington Compostable Notification	RCW § 70A.455.120	<p>Manufacturers of a product which includes a "compostable" claim either on the product or the packaging and is intended to be sold in Washington must submit a declaration to the state certifying the product meets established compostable standards.</p> <p>Product, packaging, and online content must be reviewed.</p>	Items comprised of 100% fiber or comprised entirely of untreated wood are exempt from this requirement.	NA	/



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
10000-USA- (V215)
REG ALL PRODUCTS**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

Evaluation	Citation / Method	Criteria	Comments	Result	Rating
		<p>Suppliers must provide State of Washington Department of Ecology's e-mail confirmation of registration at the time of testing.</p>			
<p>R Toxic Substances Control Act (TSCA) Certification</p>	<p>40 CFR 721</p>	<p>To ensure that products supplied to Walmart meet the requirements of TSCA, Walmart requires all suppliers to:</p> <p>(1) check if every substance in your product is listed on the TSCA Inventory of Chemical Substances,</p> <p>(2) check if your substance is subject to Significant New Use Rules (SNURs) requirements under TSCA, and (if your chemical substance is subject to a SNUR)</p> <p>(3) notify EPA at least 90 days before commencing the manufacture (including import) or processing of these chemical substances.</p> <p>Suppliers must submit the Supplier Certification of TSCA Compliance at time of production or annual testing.</p>	<p>Refer to WMRT-GB-SUPP-SUPPLIER CERTIFICATION OF TSCA COMPLIANCE form.</p>	<p>M (THE SUPPLIER CERTIFICATION OF TSCA COMPLIANCE WAS PROVIDED DATE: JULY 02, 2025</p>	<p>PASS</p>
<p>R Energy and Water Efficiency Regulations</p>	<p>Arizona: Ariz. Ariz. Rev. Stat. § 44-1375.03; California: Cal. Code Regs. tit. 20 § 1606; Connecticut: Conn. Agencies Regs. § 16a-48-6; District of Columbia: D.C. Code § 8-1771.05; Hawaii: Revised Status, Title 12, 196-88; Maryland: Md. Code Regs. 14.26.03.09; Nevada: Nev. Rev. Stat. § 701.774; New Hampshire: N.H. Rev. Stat. § 339-G:7; New York: NYCRR, Title 21, Part 509.60 Appliance and Equipment Efficiency standards; Oregon: ORS Vol 13.Title 36A. § 469.255; Rhode</p>	<p>Covered products offered for sale must be certified to each state's certification requirements. Suppliers shall certify that products are in compliance with each state's efficiency requirements.</p> <p>A Supplier Certification need to be submitted.</p> <p>Please note in the test report the specific regulation failure(s) and state(s) (if applicable).</p>	<p>Refer to WMRT-GB-SUPP-ENERGY AND WATER EFFICIENCY SUPPLIER CERTIFICATION FORM</p>	<p>NA</p>	<p>/</p>



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
10000-USA- (V215)
REG ALL PRODUCTS**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

	Evaluation	Citation / Method	Criteria	Comments	Result	Rating
		Island: R.I. Gen. Laws § 39-27.1-7; Texas: 30 Tex. Admin. Code § 290.261; Vermont: 9 V.S.A. § 2798; Washington: Rev. Code § 19.260.070;				
A R	Spray sprinkler- WaterSense	Colorado: Colo. Rev. Stat. § 6-7.5-105; District of Columbia: D.C. Code § 8-1771.03; Hawaii: Revised Status, Title 12, 196-85; Maryland: Md. Code, State Gov't § 9-2006; Maine: DEP 06-096, Chapter 180 Appliance Efficiency Standards Rhode Island: R.I. Gen. Laws § 39-27.1-4; Vermont: 9 V.S.A. § 2795; Washington: Rev. Code § 19.260.040;	Spray sprinklers shall comply with WaterSense certification requirements Check product registration at https://lookforwatersense.epa.gov/products/Product-Search-Results-Sprinkler.html In lieu of testing, documentation may be submitted in the form of a test report dated within 1 year.	The test report may be accepted from a Non-CPSC accredited lab.	NA	/
A	Plumbing and Gas Products - Massachusetts Registration	248 CMR 10.00 Uniform State Plumbing Code	Plumbing and gas products shall be registered. Registration is checked via website. https://licensing.reg.state.ma.us/pubLic/pl_products/pb_product.asp In lieu of a completed registration from the State of Massachusetts a Letter of Guarantee that an application has been submitted and state fee has been paid will be considered adequate evidence of compliance		NA	/
A R	U.S. Department of Energy Certification of Energy Efficiency Compliance	10 CFR 429	Covered products must be currently certified through the DOE as meeting applicable energy efficiency requirements (reference 10 CFR 429). Direct Import Items: Third Party Laboratories authorized by Walmart must submit certification to the DOE on Walmart's behalf.	Refer to WMRT-GB-SUPP-DOE PROCESS	NA	/



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
10000-USA- (V215)
REG ALL PRODUCTS**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

Evaluation	Citation / Method	Criteria	Comments	Result	Rating
		<p>NOTE: If a product was already submitted to DOE for certification under pre-production testing, no need to resubmit for production as long as the base model has not changed.</p> <p>Record CCMS # and Basic Model Number in report.</p> <p>NOTE: Do not issue report without proof of registration (CCMS #)</p>			
Energy Guide Labels (FTC)	16 CFR 305.6 and 16 CFR 305.8	<p>Duplicate Energy Guide Label for covered product must be maintained online on a publicly accessible web site in a manner that allows catalog sellers to hyperlink to the label or download it for use in Web sites or paper catalogs. The label for each specific model must remain on the Web site for six months after production of that model ceases.</p> <p>Domestic items: after September 15, 2017, domestic suppliers must submit a web link to FTC through CCMS for each new or renewed covered product.</p> <p>Direct Import Items: after September 15, 2017, Suppliers must submit the web link to Third Party Laboratories authorized by Walmart. Third Party Laboratories must submit the web site address for the duplicate label of each new or renewed covered products to FTC through CCMS.</p> <p>The link must meet one of the following criteria: 1. a specific link to a URL for each label; 2. a link to a PDF download for each label; or 3. a link to a Web site that takes users directly to a searchable database of the covered labels from which the label image or download may be accessed using the model number as certified to DOE</p> <p>"Covered Products" for purposes of this requirement are: Refrigerators, Refrigerator-Freezers, Freezers, Room Air Conditioners, Water Heaters, Clothes Washers, Dishwashers, Televisions, Central Air Conditioners, Heat Pumps, Furnaces, Pool Heaters, and Ceiling Fans</p>		NA	/



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
10000-USA- (V215)
REG ALL PRODUCTS**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

	Evaluation	Citation / Method	Criteria	Comments	Result	Rating
A R	Law labels - stuffed articles	Walmart USA Product Safety and Compliance Standard based on IABFLO Uniform Registration Requirements and various state laws	<p>Verify URN is properly registered.</p> <p>Log into Global Registration Services at www.globalrsinc.com;</p> <p>To determine vendor compliancy, search ONE:</p> <p>URN</p> <p>Format: CA61966. Not CA-61966</p> <p>BAR CODE</p> <p>Note that if the product description and bar code cannot be found, a URN cannot be matched and Certification cannot be determined. Please try searching by URN to get accurate results.</p> <p>Status</p> <p>Certified - all licenses held and in good standing</p> <p>Non-compliant - one or more licenses expired over 30 days</p> <p>Missing Data - not all required licenses were provided for verification</p> <p>No Records Found - data has not been provided by Vendor</p> <p>URN not registered with the GRS system product barcode not registered in the system, although URN may be typo in the search field</p> <p>If verification via www.globalrsinc.com is not available, all of the following documentation MUST be provided in order to receive a passing result for this requirement:</p> <ol style="list-style-type: none"> 1. All applicable state applications 2. Proofs of payment 3. Proof of GRS registration <p>Note: Effective February 1, 2017 Ohio will no longer enforce Bedding Laws as they pertain to Pet Bedding and Pet Toy Registration.</p>	NOTE: Do not fail based on UPC OR responsible party name in GRS.	NA	/
R	Organic certification	7 CFR 205.100	Any agricultural commodity or product that is sold, labeled, or represented as "100 percent organic," "organic," or "made with		NA	/



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
10000-USA- (V215)
REG ALL PRODUCTS**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

	Evaluation	Citation / Method	Criteria	Comments	Result	Rating
			<p>organic" must be USDA organic certified (for example: Organic Cotton), meaning it has met the requirements of the USDA National Organic Program (NOP) standards.</p> <p>In order to show compliance, the supplier must submit certification which references USDA NOP. GOTS\OCS Certificates that also indicate USDA NOP Compliance are acceptable.</p>			
R	Organic claims for products outside USDA NOP program	Federal Trade Commission (FTC) and Various State Laws	<p>Any product (i.e. fertilizers, soil amendments, potting soil, mulch etc.) that is sold, labeled, or represented as being organic outside what is covered under USDA NOP program shall provide certification by a Material Review Organization (MRO) recognized by the USDA NOP such as:</p> <ul style="list-style-type: none"> • OMRI (Organic Materials Review Institute) • WSDA (Washington State Department of Agriculture) • CDFA (California Department of Food and Agriculture Organic Input Material Program) • US EPA (Environmental Protection Agency) <p>In order to show compliance, the supplier must submit certification which references one of the above listed organizations.</p>		NA	/
A R	Composite Wood Products	40 CFR Part 770 (TSCA Title VI)	<p>For Walmart or Sam's Club Direct Import products only: Suppliers must submit an executed TSCA Title VI Composite Wood Certification to the test lab for each covered item, at the time of production testing.</p> <p>Completed certification forms must be included within the production test report.</p>	Refer to TSCA TITLE VI COMPOSITE WOOD COMPONENTS CERTIFICATION	M (TSCA FORM AND CERTIFICATE WERE PROVIDED DATE: NOVEMBER 05, 2025)	PASS
R	Plant and Wood products	16 U.S.C. 3371	<p>The Lacey Act makes it illegal to import, export, transport, sell, receive, acquire, or purchase in interstate or foreign commerce any wood or other plant-based materials, with limited exceptions, taken or traded in violation of the state and federal laws of the United States or relevant foreign law.</p> <p>All suppliers must submit the Supplier Certification of Lacey Act Compliance at the time of production or annual testing.</p>	Refer to WMRT-GB-SUPP-SUPPLIER CERTIFICATION OF LACEY ACT COMPLIANCE	M (THE SUPPLIER CERTIFICATION OF LACEY ACT COMPLIANCE WAS PROVIDED DATE: JULY 02, 2025)	PASS



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
10000-USA- (V215)
REG ALL PRODUCTS**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

	Evaluation	Citation / Method	Criteria	Comments	Result	Rating
R	California priority product notification	22 CCR § 69503.7 & 22 CCR Ch. 55	<p>[California Safer Consumer Products]</p> <p>Manufacturers are required to provide the state of California notification if their products are included on the California Priority Product List. After providing notification, the state of California requires manufacturers of Priority Products to take certain actions to address the chemical(s) of concern.</p> <p>In lieu of testing, WMRT-GB-SUPP-SAFER CONSUMER PRODUCTS SUPPLIER STATEMENT OF DECLARATION FORM will be accepted.</p>	Link to Priority Product List for additional guidance: https://dtsc.ca.gov/scp/priority-products/	NA	/
R	West Virginia Registration of Hemp Products	W. Va. Code §61-30-4, §61-30-2	<p>The manufacturer of all hemp products, including hemp fiber products, available for distribution in West Virginia shall register annually with the Department of Agriculture. This includes products manufactured in West Virginia, another state, or another country.</p> <p>Hemp product means any product derived from, or made by, processing hemp plants or plant parts, that are prepared in a form available for commercial sale.</p> <p>Registrations shall expire on December 31 of the year for which the registration was issued, regardless of the date the registration is received.</p>		NA	/
R	Washington safer consumer products - reporting requirements	Washington Safer Products Restrictions and Reporting WAC 173-337	<p>Manufacturers of covered products are required to provide the state of Washington notification if their products contain either PFAS or organohalogen flame retardants.</p> <p>Covered products and chemicals include:</p> <p>Leather and Textile Furniture and Furnishings Intended for Outdoor Use containing intentionally added PFAS; Electric and Electronic Products with Plastic External Enclosures, Intended for Outdoor Use containing intentionally added organohalogen flame retardants; and Recreational Covered Wall Padding Made from Polyurethane Foam containing intentionally added organohalogen flame retardants.</p>	WMRT-GB-SUPP-SAFER CONSUMER PRODUCTS SUPPLIER STATEMENT OF DECLARATION FORM must be utilized to satisfy this requirement (one declaration per product submission)	NA	/



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
10000-USA- (V215)
REG ALL PRODUCTS**

BV Lab Number: **96253120624**
 Technician Name: DUY
 Test Date: NOVEMBER 08, 2025
 Reviewed By/Date: JOHN/ DECEMBER 02, 2025

Evaluation	Citation / Method	Criteria	Comments	Result	Rating
		<p>In lieu of testing, WMRT-GB-SUPP-SAFER CONSUMER PRODUCTS SUPPLIER STATEMENT OF DECLARATION FORM will be accepted."</p> <p>Note: One declaration per product submission</p>			

Pricing information please refer to client price list "WMRT-GB-\$LST-GB-PRICE LIST"

No. Of Samples Required for Complete Testing	3	
No. Of (Fully Packed) Cartons For Transit Testing:	1	
No. Of Working Days For Complete Testing:	5	

Client Approval:	Ryan Deleon
	04/Nov/2025
Creation Date:	02/Sep/2010
Last Revision Date:	04/Nov/2025
Pricing Review Date	
Technical Review Date:	19/Feb/2020

Key

A Additional Charge For This Test
 M Mandatory Requirement
 R Regulatory

Result Key

C Claimed
 R Recorded
 NT Not Tested
 NM Does Not Meet
 NA Not Applicable
 M Meets



**BUREAU
VERITAS**

Rating Key

PASS

FAIL

Pass

Fail

**TEST PROTOCOL FOR
10000-USA- (V215)
REG ALL PRODUCTS**

BV Lab Number: **96253120624**
Technician Name: DUY
Test Date: NOVEMBER 08, 2025
Reviewed By/Date: JOHN/ DECEMBER 02, 2025



BUREAU
VERITAS

TEST PROTOCOL FOR
10000-USA- (V215)
REG ALL PRODUCTS

BV Lab Number: 96253120624
Technician Name: DUY
Test Date: NOVEMBER 08, 2025
Reviewed By/Date: JOHN/ DECEMBER 02, 2025

Image Appendix

Made in Oklahoma
Logo.jpg



Walmart U.S.
Manufacturing
Logo Part-1.PNG

Primary (Vertical)



Minimum size for placement on Private
Brands packaging.

Minimum font size= 5pt



Secondary (Horizontal)



Small spaces ONLY



Walmart has the following logo options for products that do not qualify for the
Made in the USA logo, but do have significant USA components.

Products that have 60% or more U.S. parts may qualify for one of the
following logos.



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
10000-USA- (V215)
REG ALL PRODUCTS**

BV Lab Number: **96253120624**
Technician Name: DUY
Test Date: NOVEMBER 08, 2025
Reviewed By/Date: JOHN/ DECEMBER 02, 2025

Walmart U.S.
Manufacturing
Logo Part-2.PNG

Made in the USA
Factory Certified



Please only use these two colors when
using this logo lockup.

**Made in the
USA**
Factory Certified

**Made in the
USA**
Factory Certified

To prevent deception, this Walmart "Made in the USA" logo or claim can be applied **ONLY** to products that have been made entirely in the United States.*

If any portion or component part of the product has been manufactured outside of the United States, or if this product has been assembled outside of the United States, this "Made in the USA" logo or claim may not be used.



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
10000-USA- (V215)
REG ALL PRODUCTS**

BV Lab Number: **96253120624**
Technician Name: DUY
Test Date: NOVEMBER 08, 2025
Reviewed By/Date: JOHN/ DECEMBER 02, 2025

Walmart U.S.
Manufacturing
Logo Part-3.PNG

**Assembled in the
USA**
Factory Certified

**Grown in the
USA**
Factory Certified

**Assembled in the
USA**
**With 60% or more US parts
Factory Certified**

**Grown in the
USA**
**With 60% or more US parts
Factory Certified**

Walmart has the following logo options for products that do not qualify for the Grown in the USA logo, but do have significant USA components.

Item is made with less than 60% US parts, but final substantial transformation takes place in the USA.

Walmart has the following logo options for products that do not qualify for the Assembled in the USA logo, but do have significant USA components.

Item is made with less than 60% US parts, but final substantial transformation takes place in the USA.



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
10000-USA- (V215)
REG ALL PRODUCTS**

BV Lab Number: **96253120624**
Technician Name: DUY
Test Date: NOVEMBER 08, 2025
Reviewed By/Date: JOHN/ DECEMBER 02, 2025

Walmart U.S.
Manufacturing
Logo Part-4.PNG

**Engine made in the
USA**
Factory Certified

**Made in the
USA**
**With 60% or more US parts
Factory Certified**

**Engine made in the
USA**
**With 60% or more US parts
Factory Certified**

Walmart has the following logo options for products that do not qualify for the Engine Made in the USA logo, but do have significant USA components.

Item is made with less than 60% US parts, but final substantial transformation takes place in the USA.



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
10000-USA- (V215)
REG ALL PRODUCTS**

BV Lab Number: **96253120624**
Technician Name: DUY
Test Date: NOVEMBER 08, 2025
Reviewed By/Date: JOHN/ DECEMBER 02, 2025

Walmart U.S.
Manufacturing
Logo Part-5.PNG

Logo Subclaim

The subclaim regulation should follow the examples on the side.



The spacing between the subclaim and logo should be the same as the height of "Factory Certified".



The spacing between the sub-claim and logo should be the same as the 0 of 60%.



**BUREAU
VERITAS**

**TEST PROTOCOL FOR
10000-USA- (V215)
REG ALL PRODUCTS**

BV Lab Number: **96253120624**
Technician Name: DUY
Test Date: NOVEMBER 08, 2025
Reviewed By/Date: JOHN/ DECEMBER 02, 2025

Walmart U.S.
Manufacturing
Logo Part-6.PNG



Do not modify proportions.



Do not scale below .5 of an inch.



Do not substitute colors.



Do not add effects.

FULL BED



TWIN BED



BUNK BED





BLACK HARDWARE



BLACK HOOK



BLACK



GRAY



ESPRESSO



WHITE



BLUE



CARTON



TRACKING LABEL



WARNING LABEL





ASSEMBLY SURVEY

Item Number and Description: Twin/ Full Bunk Bed

Warranty Card Included: Y

Time to Assemble: 60 minutes

Customer Service Phone Number Included: Y

Quantity of Hardware (# Pieces):

Extra Hardware Included and Identified: N

Ø1/4" x 100mm Joint Connector (4mm Hex Head): 16 pcs
 Ø6.5mm x 48mm Wood Joint Connector (4mm Hex Head): 8 pcs
 Ø6.5mm x 100mm Wood Joint Connector (4mm Hex Head): 24 pcs
 Ø4mm x 35mm Flat Head Wood Screw: 26 pcs
 Ø19mm x 95mm Wood Dowel: 4 pcs
 Ø4mm x 30mm Flat Head Wood Screw: 6 pcs
 Ø9mm x 17mm Hex Cap: 2 pcs
 Ø1/4" x 32mm Hex Socket Head Bolt: 5 pcs
 Ø10mm x 50mm Wood Dowel: 64 pcs
 Ø11.8mm x 15mm Barrel Nut: 16 pcs
 Ø4mm x 19mm Flat Head Screw: 2 pcs
 Allen Key: 1 pc

Follow instructions provided with product. Refer to the step in the instructions to complete the survey below.
 For each step identified below, circle the number to the right that best fits your experience
 (First column is for instruction/directions experience; Second column is for the physical assembly experience).

Instruction (List Issue)	Scale		Assembly (List Issue)	Scale	
	Poor	Great		Poor	Great
Step 1 to Step 10:/	2	/		2	

Overall Comments: (List Step # and concerns or praise and if it was for assembly or instructions):